



ENVIRONMENTAL IMPLEMENTATION REPORT / FUNCTIONAL SERVICING STUDY - MAIN REPORT (4TH SUBMISSION)

June 2017

14 Mile Creek West and the Lazy Pat Farm Property
(3269 Dundas Street West), North Oakville West

PREPARED FOR:



PREPARED BY:



D14-011-18



July 14, 2017

File No. 09M-00013-01 (14.09222.001)

Town of Oakville
1225 Trafalgar Road
Oakville ON L6H 0H3

Attention: Mr. Mark H. Simeoni, Director of Planning Services

Dear Sir:

**Subject: Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farms Property, North Oakville West (4th Submission)
Zoning By-law Amendment (Z.1333.01) and Revised Draft Plan of Subdivision (24T-11001)**

WSP Canada Group Limited (WSP) (formerly MMM Group Limited) is pleased to submit our 4th Submission of the Environmental Implementation Report / Functional Servicing Study (EIR/FSS), June 2017, for 14 Mile Creek West and the Lazy Pat Farms Property, North Oakville West and a revised Draft Plan of Subdivision, associated with the above applications. The EIR/FSS has been prepared in accordance with the approved Terms of Reference for EIR/FSS studies for North Oakville, in support of a Draft Plan of Subdivision and Zoning By-law Amendment application for the Subject Property, and addresses Town and agency comments on the 3rd Submission of the EIR/FSS, dated November 2014, and subsequent interim submissions.

The purpose of the EIR is to characterize and analyze the natural heritage features and functions, and to determine and address the potential impacts of the proposed development application, including servicing requirements, on the Natural Heritage System (NHS). The purpose of the FSS is to identify servicing requirements related to sanitary, water, stormwater, roads, and site grading.

1.0 Areas of Expertise and Technical Lead

The EIR/FSS has been prepared by a multidisciplinary team to address the broad range of issues to be studied through the EIR/FSS. WSP Canada Group Limited (formerly MMM Group Limited) is the lead consultant in the preparation of the EIR/FSS. The following highlights the technical areas of expertise and the lead qualified professional(s) overseeing the preparation of the EIR/FSS.

Area of Expertise	Professional Lead(s)
Land Use Planning and Project Management	Chris Tyrrell, MCIP, RPP, Vice President, Planning, Landscape Architecture and Urban Design (WSP) Randall Roth, MCIP, RPP, Senior Project Manager, Planning, Landscape Architecture and Urban Design (WSP)
Municipal Servicing	Alex Williams, P.Eng., Senior Project Engineer, Municipal Engineering (WSP)

100 Commerce Valley Drive West
Thornhill, ON, Canada L3T 0A1

Tel.: +1 905 882-1100

Tel.: +1 905 882-0055
wsp.com

Area of Expertise	Professional Lead(s)
Stormwater Management and Water Resources	Steve van Haren, P.Eng., P.E., Manager, Water Resources (WSP) Ashraf Zaghal, Ph.D., P.Eng, Manager, Water Resources (WSP) Lamoire Alexander, P.Eng., Senior Project Manager, Water Resources (WSP)
Ecology and Aquatics	Mark Cece, B.Sc., Manager, Environment / Environmental Management (WSP)
Geology and Hydrogeology	Andrew Kulin, P.Eng., Senior Hydrogeologist / Geological Engineer, Environment / Environmental Management (WSP)
Transportation	Greig Bumstead, Senior Project Manager, Transportation Planning (WSP)
Fluvial Geomorphological & Erosion Threshold Assessment	Ed Gazendam, M. Eng. , P. Eng. (Water's Edge)
Geotechnical and Slope Stability Analysis	Baruyr E. Baghdasarian, M.Eng., B.A.Sc., B.Sc., Geotechnical Engineer (Exp. Consulting (formerly Trow Associates Inc.))

2.0 Summary of Comments and Responses

The attached Comments and Response tables summarize the comments and WSP responses Conservation Halton's (CH), Development Engineering, and MNR comments on the 3rd Submission of the EIR/FSS, dated November 2014, and subsequent interim submissions.

As indicated in the CH letter to the Town of Oakville, dated March 10, 2017, CH indicates that that they are willing to accept the reduction of flows in Reach 14W-12A if the following five conditions can be met. As such, a brief description of how each of the conditions are addressed is provided below along with references to supporting documentation within the EIR/FSS report.

1. *Discuss the feasibility of locating the tie-in of Reach 14W-22 to Reach 14W-12A 20 m upstream of the confluence with Reach 14W-12.*

The determination of the connection point of Reach 14W-22 to Reach 14W-12A was undertaken and resulted in the location to be 20 m upstream of the confluence with Reach 14W-12. The main constraint associated with the connection point is topography and grading. A detailed description of the assessment undertaken to confirm this location is located in Section 5.9.1 and Appendix 6.7 in the revised EIR/FSS report.

As part of the hydraulic assessment and floodplain mapping, we have assessed the water surface profiles under proposed conditions (Appendix 6.7). Under existing conditions, the existing HEC RAS model was refined and updated to account for any changes in water surface elevations, due to changes in channel hydraulics at the confluence of Reach 14W-16 and Reach 14W-12. The existing HEC RAS model had not included Reach 14W-12A. As such, we have added a channel representing Reach 14W-12A and a cross section downstream of the junction where Reach 14W-12A, Reach 14W-16 and 14W-12 meet. As a result, and as shown in Appendix 6.7, water surface profiles have been presented, and they show a smooth gradually-varied profile. For demonstration purposes, all phases are presented for the connection from Reach 14W-22 and from Reach 14W-12A.

2. *Discuss how the realigned Reach 14W-22 will replicate the loss of flows, specifically from an aquatic ecology perspective.*

With the proposed development, flows in Reach 14W-12A will be reduced due to redirection to other Reaches, including Reach 14W-22. Although Reach 14W-22 will convey the flow that were in Reach 14W-13 and 14W-14 pre-development, it will not convey the same flow volumes due to

a reduced drainage area post-development (Refer to Section 7.4.3 Post Development Conditions). From an ecological perspective, the reduced flows present in Reach 14W-22 will not have a negative effect to the habitat present due to the proposed natural channel design, and the sustained duration and frequency of peak flows under proposed conditions (refer to Appendix 7.4 Flow Regime Memo). Under existing conditions, a reduced flow through the semi-defined Reach of 14W-13 and Reach 14W-14 with dense vegetation and a wide flow path would potentially have an effect on the ecological function (e.g., reduce water depth for fish passage or habitat function). However, in the realigned Reach 14W-22, with the riffle / pool sequence and connecting low flow channel, the reduced flow volume will be confined in the low flow channel and within pools. Both of these features are lacking in existing reaches; however, in the new channel, they will function to provide habitat for fish and benthic macroinvertebrates, as well as, convey nutrient drift downstream. Refer to Section 5.9.1 in the revised EIR/FSS report.

3. *Discuss how the realigned Reach 14W-22 will replicate the loss of allochthonous contributions from Reach 14W-12A.*

Associated with the realigned Reach 14W-22, a new stream corridor will be created. This new corridor will be wider than the existing corridors through active agricultural lands and will be planted to create a dense riparian corridor. In addition, a variety of wetland habitats including small offline ponds and meadow marshes that will seasonally flood will be included which will provide habitat for wildlife, potentially anurans. This dense riparian corridor will be a source of allochthonous inputs which will be conveyed downstream during high and medium flow events to provide nutrients for fish and benthic macroinvertebrates. Refer to Section 5.9.1 in the revised EIR/FSS report. These proposed offline habitats are technically feasible in terms of fluvial geomorphic considerations, as well as, stream hydrology considerations due to the following key aspects:

- Natural channel design features provide ecological functions that are not existent under current conditions within 14W-14; and,
 - Peak flows will have the same duration and frequency as peak flows under 14W-14. While peak flow magnitudes will be reduced by 15-20% in some cases, the proposed flows are anticipated to sustain ecological functions as needed.
4. *Monitoring will include the Adaptive Environmental Monitoring (AEM) approach and Reach 14W-22 will be monitored to ensure it is functioning as related to the approved modelling and design.*

Within the EIS/FSS, a commitment will be made to undertake the monitoring following the Adaptive Environmental Monitoring (AEM) approach. This approach allows for flexibility in the monitoring plan so that modifications and refinements can be incorporated during the monitoring period to maximize the fulfillment of the monitoring objectives. Specifically related to Reach 14W-22, monitoring will document the function of this reach and any non-functioning design criteria will be subjected to refinement to ensure it is functioning as intended. Refer to Section 5.9.4 and Appendix 7.4 in the revised EIR/FSS report; however, a finalized detailed monitoring plan will be developed during detailed design.

5. *Ministry of Natural Resources and Forestry (MNRF) provides their approval.*

We have been engaged in on-going consultation with the MNRF regarding the maintenance of flows to Occupied Redside Dace habitat in Reach 14W-12. Currently, it has been demonstrated that post-development, flows in Reach 14W-12 will not be reduced. Flow contributions to maintain the flow in Reach 14W-12 will come from a variety of sources rather than just one under pre-development conditions, Reach 14W-12A. These include inputs from Reach 14W-12A, Reach 14W-22 and the SWM facilities. The flow contributions from SWM facilities will be monitored to ensure it complies with the thermal and dissolved oxygen requirements for discharging to Redside Dace habitat. A response to MNRF discussing this issue was sent on June 6, 2017. Refer to Sections 5.9.1 and Appendix 7.4.



We look forward to working with you to advance these applications to approval in a timely manner. Please call should you have any questions or require clarification on any matters discussed.

Yours truly,

WSP Canada Group Limited

A handwritten signature in black ink, appearing to read 'Chris Tyrrell'.

Chris Tyrrell, MCIP, RPP

Vice President

Planning, Landscape Architecture and Urban Design

Attachments: Comment and Response Tables

CC: Mike Reel, QuadReal Property Group
Robert Thun, B.Sc., MCIP, RPP, Town of Oakville, Planning Services



July 4, 2017

File No. 09M-00013-01 (14.09222.001)

bcIMC Realty Corp.
c/o QuadReal Property Group
Commerce Court West
199 Bay Street, Suite 2100
P.O Box 373
CC Postal Station
Toronto, Ontario M5L 1G2

Attention: Mike Reel, Vice President, Development

Dear Sir:

**Subject: Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farms Property, North Oakville West (4th Submission)
Zoning By-law Amendment (Z.1333.01) and Revised Draft Plan of Subdivision (24T-11001)**

WSP Canada Group Limited (WSP) (formerly MMM Group Limited) is pleased to submit our 4th Submission of the Environmental Implementation Report / Functional Servicing Study (EIR/FSS), June 2017, for 14 Mile Creek West and the Lazy Pat Farms Property, North Oakville West, and a revised Draft Plan of Subdivision and Zoning By-law Amendment Schedule. The revised EIR/FSS is in support of a Draft Plan of Subdivision and Zoning By-law Amendment application for the Subject Property, and addresses Town and agency comments on the 3rd Submission of the EIR/FSS, dated November 2014, and subsequent interim submissions.

The purpose of the EIR is to characterize and analyze the natural heritage features and functions, and to determine and address the potential impacts of a proposed development application, including servicing requirements, on the Natural Heritage System (NHS). The purpose of the FSS is to identify servicing requirements related to sanitary, water, stormwater, roads, and site grading.

We thank you for the opportunity to undertake this Study. Please call should you have any questions or require clarification on any matters discussed.

Yours truly,

WSP Canada Group Limited

Chris Tyrrell, MCIP, RPP
Vice President
Planning, Landscape Architecture and Urban Design

100 Commerce Valley Drive West
Thornhill, ON, Canada L3T 0A1

Tel.: +1 905 882-1100

Tel.: +1 905 882-0055

Fax: +1 905 882-0055

wsp.com

Table of Contents

Executive Summary

1.0 Introduction

2.0 Natural Heritage System Framework

3.0 Land Use

4.0 Hydrogeology and Geology

5.0 Natural Environment

6.0 Water Resources

7.0 Stormwater Management

8.0 Municipal Services

Appendices

Table of Contents	Page
Executive Summary.....	E-1
1.1 EIR Subcatchment Area and FSS Study Area.....	E-1
1.2 Natural Heritage System Framework.....	E-2
1.3 Land Use	E-2
1.4 Hydrogeology and Geology	E-2
1.5 Natural Environment.....	E-3
1.6 Water Resources	E-5
1.7 Stormwater Management	E-5
1.8 Municipal Servicing.....	E-7
1.0 Introduction.....	1-1
1.1 Study Purpose	1-1
1.2 EIR Subcatchment Area and FSS Study Area.....	1-3
1.3 Study Team	1-4
1.4 References	1-5
2.0 Natural Heritage System Framework	1-1
2.1 Natural Heritage System Components	2-1
2.2 Permitted Uses in the Natural Heritage System.....	2-3
3.0 Land Use	3-1
3.1 Development Concept Plan	3-1
3.2 Trail Planning.....	3-3
4.0 Hydrogeology and Geology	4-1
4.1 Introduction.....	4-1
4.1.1 Subwatersheds.....	4-2
4.1.1.1 Subwatershed FM1001.....	4-3
4.1.1.2 Subwatershed FM1109.....	4-3
4.1.1.3 Subwatershed FM1102.....	4-3
4.1.2 Work Program.....	4-4
4.2 Regional Physiography and Geological Setting	4-4
4.2.1 Regional Geology and Hydrostratigraphy	4-4

4.2.2	<i>Topography and Drainage</i>	4-6
4.3	Hydrogeological Evaluation	4-6
4.3.1	<i>On-Site and Off-Site Investigations</i>	4-6
4.3.1.1	Supplemental Farm Pond Investigation	4-7
4.3.1.2	Quarterly Monitoring	4-8
4.3.1.3	Investigations by Others	4-8
4.3.2	<i>Site Geology</i>	4-10
4.3.2.1	Grain Size Analyses	4-11
4.3.2.2	In-Situ Permeability Testing	4-13
4.3.2.2.1	<i>Percolation Testing</i>	4-14
4.3.2.3	Groundwater Level Monitoring	4-15
4.3.2.4	Findings of the Supplemental Farm Pond Investigation.....	4-18
4.3.2.4.1	<i>Atypical Responses of Data Logger at MP-24D (November 18, 2014 to November 26, 2014)</i>	4-21
4.3.2.4.2	<i>Discussion of MP-24 Results</i>	4-21
4.3.2.5	Stream Base Flow Measurements.....	4-23
4.3.2.6	Groundwater and Surface Water Quality	4-27
4.3.3	<i>Local Hydrogeological Setting</i>	4-28
4.4	Impacts of the Proposed Development.....	4-29
4.4.1	<i>Water Balance Methodology</i>	4-30
4.4.2	<i>Climate and Water Surplus</i>	4-30
4.4.3	<i>Inputs to Water Balance</i>	4-31
4.4.3.1	Pre-Development Conditions	4-32
4.4.3.2	Post-Development Conditions	4-33
4.4.4	<i>Water Balance</i>	4-34
4.4.4.1	Pre-Development Water Balance	4-34
4.4.4.1.1	<i>Base Flow Comparisons to Pre-Development Water Balance</i>	4-34
4.4.4.2	Post-Development Water Balances	4-35
4.4.4.3	Post-Development Water Balance with No Mitigation.....	4-37
4.4.4.4	Post-Development Water Balance with Mitigation	4-38
4.4.4.5	Discussion of Water Balance Results	4-41

4.4.4.6	Discussion of the Potential for Base Flow Reductions to Watercourses	4-42
4.4.4.7	Potential Groundwater Seepage Area Near Upper End of the Farm Pond	4-44
4.4.4.8	Dewatering Potential	4-46
4.5	Conclusions and Recommendations	4-47
5.0	Natural Environment	5-1
5.1	Introduction	5-1
5.1.1	<i>Study and Site Overview</i>	<i>5-1</i>
5.1.2	<i>Study Objectives and Scope of Work</i>	<i>5-1</i>
5.1.3	<i>Agency Consultation</i>	<i>5-5</i>
5.1.4	<i>Field Investigations</i>	<i>5-8</i>
5.2	Natural Heritage Planning Policy	5-8
5.2.1	<i>North Oakville Creeks Subwatershed Study</i>	<i>5-8</i>
5.2.1.1	Core(s) and Linkage(s)	5-9
5.2.1.2	Stream Corridors	5-9
5.2.1.3	Other Features	5-10
5.2.1.4	Forested Stands within Stream Corridors	5-11
5.2.1.5	Hydrologic Features 'A' and 'B'	5-11
5.2.2	<i>Provincial Policy Statement (MMAH 2014)</i>	<i>5-11</i>
5.2.3	<i>Conservation Halton Regulation 162/06 and Wetland Policy (2006)</i>	<i>5-14</i>
5.2.4	<i>Endangered Species Act, 2007</i>	<i>5-14</i>
5.3	Existing Conditions	5-15
5.3.1	<i>Physiography, Drainage and Soils</i>	<i>5-15</i>
5.3.2	<i>Environmental Designations</i>	<i>5-15</i>
5.3.3	<i>Species of Conservation Concern</i>	<i>5-18</i>
5.3.3.1	Species At Risk	5-18
5.3.3.2	Provincially Significant Species	5-25
5.3.3.3	Regionally Rare/Uncommon Species	5-25
5.3.4	<i>Aquatic Resources</i>	<i>5-25</i>
5.3.4.1	Fish Community	5-28
5.3.4.2	Benthic Macroinvertebrate Community	5-31
5.3.4.3	Water Quality Parameters	5-33

5.3.4.4	Aquatic Habitat	5-37
5.3.5	<i>Vegetation Resources</i>	5-45
5.3.5.1	Vegetation Approach	5-45
5.3.5.2	Vegetation Overview.....	5-46
5.3.5.3	Vegetation Communities.....	5-46
5.3.5.4	Hedgerows/Tree Clusters	5-56
5.3.5.5	Offsite Vegetation Communities associated with Core #1 and the Linkage to Core #2	5-57
5.3.6	<i>Wildlife Resources</i>	5-59
5.3.6.1	Wildlife Approach.....	5-59
5.3.6.2	Wildlife Survey Results	5-61
5.3.7	<i>Hydrogeology</i>	5-67
5.4	Description of the Proposed Development	5-68
5.5	Development of Setback Requirements	5-68
5.5.1	<i>Determining Stream Corridor Widths</i>	5-68
5.6	Proposed Concept Plan.....	5-69
5.7	Stormwater Management	5-71
5.8	Sanitary Servicing and Water Distribution	5-71
5.9	Impact Overview	5-72
5.9.1	<i>Fish Habitat Enhancement Concepts</i>	5-72
5.9.2	<i>Encroachment into Reach 14W-16 Stream Corridor Setback</i>	5-84
5.9.3	<i>Elimination of Avenue 2 Crossing of Reach 14W-16</i>	5-84
5.9.4	<i>Overview of Mitigation Measures</i>	5-84
5.10	Conclusions and Recommendations	5-86
6.0	Water Resources	6-1
6.1	Introduction	6-1
6.2	Background	6-2
6.3	Corridor Width Delineation.....	6-3
6.3.1	<i>Fluvial Geomorphic Requirements</i>	6-3
6.3.1.1	Meander Belt Width	6-4
6.3.1.2	100 Year Erosion Rate	6-4
6.3.2	<i>Top of Bank Requirements</i>	6-4

6.3.3	<i>Regulatory Floodplain Delineation Requirements</i>	6-5
6.3.4	<i>Fisheries Setback and NOCSS Setback Requirements</i>	6-5
6.3.5	<i>Hydrologic Feature ‘A’</i>	6-6
6.3.6	<i>Total Corridor Widths</i>	6-6
6.4	Conceptual Natural Channel Design	6-8
6.4.1	<i>Design Criteria</i>	6-8
6.4.2	<i>Proposed Channel Morphology</i>	6-8
6.4.2.1	Reach 14W-16.....	6-9
6.4.2.2	Reach 14W-22 Diversion (Realignment of Reach 14W-13 and Reach 14W-14).....	6-9
6.4.2.3	Reach 14W-21 Diversion.....	6-9
6.4.2.4	Reach 14W-23 (Realignment of Reach 14W-11A)	6-9
6.4.3	<i>Road Crossings</i>	6-10
6.5	Hydraulic Analysis	6-11
6.5.1	<i>Previous Studies</i>	6-11
6.5.2	<i>Existing Conditions</i>	6-12
6.5.3	<i>Flow Rates</i>	6-13
6.5.4	<i>Existing Crossings and Parameters</i>	6-13
6.5.5	<i>Proposed Conditions</i>	6-15
6.5.5.1	Channel Realignment	6-16
6.5.5.2	New Crossings.....	6-16
6.5.5.3	Flow Rates.....	6-16
6.5.5.4	Geometric Data and Parameters	6-16
6.5.6	<i>Riparian Storage Assessment</i>	6-31
6.6	Stream Length Requirements	6-34
6.7	Summary	6-35
7.0	Stormwater Management	7-1
7.1	Introduction and Background	7-1
7.2	Stormwater Management Objectives	7-2
7.3	Stormwater Management Alternatives and Proposed Approach	7-3
7.3.1	<i>Evaluation of Stormwater Management Alternatives</i>	7-3
7.3.1.1	Stormwater Management Practices.....	7-3

7.3.1.2	Evaluation	7-4
7.3.2	<i>Proposed Stormwater Management Approach</i>	7-5
7.4	Development of GAWSER Hydrologic Model	7-7
7.4.1	<i>Modelling Methodology</i>	7-7
7.4.2	<i>Existing Conditions</i>	7-7
7.4.3	<i>Post-Development Conditions</i>	7-11
7.4.3.1	Development Phasing	7-11
7.4.3.2	Post-Development Drainage Boundaries	7-11
7.4.3.3	Conveyance of Minor System Flows	7-12
7.4.3.4	Conveyance of Major Storm Flows	7-12
7.4.3.5	Post-Development Hydrologic Analysis	7-12
7.4.3.6	Results of GAWSER model for Post-development Conditions	7-14
7.5	Erosion Control Analysis	7-16
7.6	Hydrologic Flow Regimes Analysis	7-17
7.7	Topographic Depression Volumes	7-18
7.8	Design of Stormwater Management Facilities	7-20
7.8.1	<i>General</i>	7-20
7.8.2	<i>Dundas Street Expansion</i>	7-21
7.8.3	<i>Pond Design Overview and Control Criteria</i>	7-21
7.8.4	<i>Water Quality Control</i>	7-23
7.8.5	<i>Extended Detention Erosion Control</i>	7-24
7.8.6	<i>Water Quantity Control</i>	7-25
7.8.7	<i>Thermal Mitigation</i>	7-28
7.8.8	<i>Summary of SWM Pond Design</i>	7-28
7.9	Downstream Impacts for Regional Storm	7-31
7.10	Summary	7-33
8.0	Municipal Services	8-1
8.1	Introduction	8-1
8.2	Conceptual Wastewater Servicing Strategy	8-1
8.2.1	<i>General</i>	8-1
8.2.2	<i>Treatment</i>	8-2

8.2.3	<i>Collection System</i>	8-2
8.2.4	<i>Region's Timing of Required Wastewater Infrastructure</i>	8-3
8.2.5	<i>Expected Sewage Generation</i>	8-3
8.2.6	<i>Region's Concept Plan Applied to the FSS Study Area</i>	8-4
8.2.6.1	Dundas Street Wastewater Sewer	8-4
8.2.6.2	Internal Collection Systems	8-5
8.2.6.3	External Drainage Areas	8-5
8.2.7	<i>Sewer Sizing and Technical Analysis</i>	8-7
8.2.8	<i>Mitigation Measures for Wastewater Crossings of Watercourses and Natural Heritage</i>	8-7
8.3	<i>Conceptual Water Servicing Strategy</i>	8-8
8.3.1	<i>Supply</i>	8-8
8.3.2	<i>Pressure Districts</i>	8-9
8.3.3	<i>Storage</i>	8-9
8.3.4	<i>Distribution</i>	8-9
8.3.5	<i>Region's Timing</i>	8-10
8.3.6	<i>Expected Water Demand</i>	8-10
8.3.7	<i>Region's Concept Plan Applied to the FSS Study Area</i>	8-11
8.3.8	<i>Water Distribution Modeling Analysis</i>	8-12
8.3.9	<i>Water Distribution Modeling Results for Peak Hour and Maximum Day</i>	8-12
8.3.10	<i>Water Distribution Modeling Results for Maximum Day plus Fire</i>	8-13
8.3.11	<i>Additional Design Considerations</i>	8-14
8.3.11.1	Local Service Watermains	8-14
8.3.11.2	Mitigation Measures for Single Feed Watermain Supplies	8-14
8.3.11.3	Mitigation Measures for Watermain Crossings of Watercourses and Natural Heritage	8-14
8.4	<i>Stormwater</i>	8-15
8.4.1	<i>General</i>	8-15
8.4.2	<i>Minor Storm System (Sewers)</i>	8-15
8.4.3	<i>Major Storm System (Overland Flow)</i>	8-16
8.5	<i>Grading</i>	8-16
8.6	<i>Phasing</i>	8-16

8.7	Summary	8-17
-----	---------------	------

List of Figures*Included at end of Section*

1.0 Introduction

Figure 1.1 – Subject Property

Figure 1.2 – Study Areas

2.0 Natural Heritage System Framework

Figure 2.1 – Natural Heritage System Components

3.0 Land Use

Figure 3.1 – 407 West Employment Area Concept Plan

Figure 3.2 – Draft Plan of Subdivision

Figure 3.3 – 407 West Employment Area Concept Plan Trails Plan (Conceptual)

4.0 Hydrogeology and Geology

Figure 4.1 – Site Location

Figure 4.2 – Surficial Geology

Figure 4.3 – Interpreted Shallow and Bedrock Groundwater Contours

Figure 4.4 – On-Site Monitoring Locations

Figure 4.5 – Static Water Levels - Spring

Figure 4.6 – Static Water Levels - Summer

Figure 4.7 – Concept Plan and Mitigation Opportunities

Figure 4.8 – Conceptual Infiltration Swale

Figure 4.9 – Monthly and Cumulative Infiltration – bclMC Lands within FM1001

Figure 4.10 – Monthly and Cumulative Infiltration - FM1001 Subwatershed

Drawing 4.1 – Hydrogeologic Cross Sections (*plastic sleeve*)**5.0 Natural Environment**Figure 5.1 – Natural Environment Features: 407 West Employment Area and Overlapping NOCSS
EIR Subcatchments

Figure 5.2 – Vegetation Communities

Figure 5.3 – Wildlife Sampling Locations

Figure 5.4 – Aquatic Ecology – Field Investigations and Watercourse Constraints

Figure 5.5 – Vegetation Communities: Proposed Development Impact Review

Figure 5.6 – Aquatic Ecology: Proposed Development Impact Review

Figure 5.7 – Natural Heritage Features: Proposed Development Impact Review

Figure 5.8 – Natural Heritage Features: Proposed Trail Impact Review

6.0 Water Resources

Figure 6.1 – Existing Channel System and Proposed Channel Diversion and Rehabilitation

Figure 6.2 – Historical Channel Planform

Figure 6.3A – Top of Bank Delineation 14W-11

Figure 6.3B – Cross- Section Downstream of SWM Pond 3 (Ultimate Phase)

Figure 6.4A – Fourteen Mile Creek Natural Channel Design

Figure 6.4B – Diversion Channels 14W-21 and 14W-22

Figure 6.4C – Diversion Channels 14W-21 and Reach 14W-16 Rehabilitation

Figure 6.4D – Reach 14W-16A Rehabilitation

Figure 6.4E – Diversion Channel 14W-11A

Figure 6.5.1 – Corridor Delineation - Interim Phase 1A Conditions

Figure 6.5.2 – Corridor Delineation - Interim Phase 1B Conditions

Figure 6.5.3 – Corridor Delineation - Interim Phase 2 Conditions

Figure 6.5.4 – Corridor Delineation - Ultimate Conditions

Figure 6.6.1 – Hec-Ras Cross-Sections Existing Conditions

Figure 6.6.2 – Hec-Ras Cross-Sections Interim Phase 1A Conditions

Figure 6.6.3 – Hec-Ras Cross-Sections Interim Phase 1B Conditions

Figure 6.6.4 – Hec-Ras Cross-Sections Interim Phase 2 Conditions

Figure 6.6.5 – Hec-Ras Cross-Sections Ultimate Conditions

7.0 Stormwater Management

Figure 7.4.1 – Existing Drainage Boundaries and Reference Nodes

Figure 7.4.1-SCH – Modelling Schematic – Existing Conditions

Figure 7.4.2-SCH – Modelling Schematic – Interim Phase 1A Conditions

Figure 7.4.3-SCH – Modelling Schematic – Interim Phase 1B Conditions

Figure 7.4.4-SCH – Modelling Schematic – Interim Phase 2 Conditions

Figure 7.4.5-SCH – Modelling Schematic – Ultimate Conditions

Figure 7.4.2 – Interim Phase 1A Drainage Boundaries and Reference Nodes

Figure 7.4.3 – Interim Phase 1B Drainage Boundaries and Reference Nodes

Figure 7.4.4 – Interim Phase 2 Drainage Boundaries and Reference Nodes

Figure 7.4.5 – Ultimate Drainage Boundaries and Reference Nodes

Figure 7.7.1 – Topographic Depression in the Development Area

8.0 Municipal Services

Figure 8.1 – Regional Wastewater Plan

Figure 8.2 – Wastewater Drainage Plan

Figure 8.3 – Regional Water Plan

Figure 8.4 – Water Distribution Plan

Figure 8.5 – Stormwater Drainage Plan

Figure 8.6 – Conceptual Grading Plan

Figure 8.7.1 – Interim Servicing Plan Phase 1A

Figure 8.7.2 – Interim Servicing Plan Phase 1B

Figure 8.7.3 – Interim Servicing Plan Phase 2

Figure 8.8.1 – Interim Grading Plan Phase 1A

Figure 8.8.2 – Interim Grading Plan Phase 1B

Figure 8.8.3 – Interim Grading Plan Phase 2

List of Tables

Page

Table 1.1 – Subwatershed Areas.....	1-3
Table 4.1 – Subwatershed Areas.....	1-3
Table 4.2 – Hazen Estimates of Hydraulic Conductivity	4-12
Table 4.3 – Tri-Linear Soil Classification	4-12
Table 4.4 – In-Situ Permeability Testing Summary.....	4-14
Table 4.5 – Data Logger Locations.....	4-16
Table 4.6 – Mini-Piezometer MP-24 Observations	4-19
Table 4.7 – Summary of Stream Flow Observations	4-25
Table 4.8 – Watershed Specific Inputs Used in the Water Balance – FM1001.....	4-32
Table 4.9 – Pre and Post Development Water Balance – No Mitigation.....	4-37
Table 4.10 – Pre and Post Development Water Balance – With Mitigation	4-40
Table 5.1 - Summary of applicable EIR study requirements identified in the North Oakville EIR and FSS Terms of Reference (Town of Oakville, 2007)	5-2
Table 5.2 – Fish Community Data for QuadReal – Lazy Pat Lands, Oakville (MESP 2003, MMM, 2003 & MMM, 2009)	5-29
Table 5.3 – 2009 Benthic Macroinvertebrate Community Assessment Results.....	5-33
Table 5.4 – Summary of Water Temperature Data July (2009)	5-34
Table 5.5 – Summary of Water Temperature Data Analysis (2009), Chu <i>et al.</i> Method	5-35
Table 5.6 - Dissolved Oxygen Monitoring Summary (mg/l).....	5-36
Table 5.7 – Terrestrial and Wetland Vegetation Community Summary	5-48
Table 5.8 – Hedgerow/Tree Cluster Summary.....	5-56
Table 5.9 – Avifauna Species of Conservation Concern.....	5-62
Table 5.10 – Anuran Survey Summary Results.....	5-63
Table 5.11 – Species Classifications of Exiting Bats	5-65
Table 5.12 – Summary of Results by Building and Date.....	5-66
Table 5.13 – Ecological Land Classification and Impacts of Trail System	5-81
Table 5.14 – Summary of Potential Impacts to Aquatic Resources	5-89
Table 5.15 – Summary of Potential Impacts to Vegetation	5-89
Table 5.16 – Summary of Potential Impacts to Wildlife.....	5-89
Table 6.1 – Fisheries and NOCSS Setback Requirements	6-6

Table 6.2 – Total Corridor Width.....	6-7
Table 6.3 – Morphological Parameters for Proposed Channel Diversion and Rehabilitation	6-10
Table 6.4 – Summary of MTO Drainage Design Criteria	6-11
Table 6.23 - Riparian Storages for Ultimate Conditions and Phase 1b Conditions	6-33
Table 6.24 - Existing and Proposed Stream Lengths for High, Medium and Low Constraint Streams	6-34
Table 7.3.1 – Development Phases.....	7-6
Table 7.4.1 – Comparison of Catchment Areas between Original NOCSS and Updated Study	7-8
Table 7.4.2 – Unit Flow Rates and Peak Flow Rates from Original NOCSS.....	7-9
Table 7.4.3 – Revised Unit Flow Rates and Peak Flow Rates from Current Study.....	7-10
Table 7.4.4 – Comparison of Existing and Post-development Drainage Areas.....	7-11
Table 7.4.5 – Comparison of Existing and Post-development Peak Flow Rates for Regional Events	7-14
Table 7.5.1 – Results of Erosion Control Analysis for Reach D Upstream of Dundas Street (Reference Node 3).....	7-17
Table 7.5.2 – SWM Ponds Detention Times for Erosion Controls	7-17
Table 7.7.1 – Topographic Depressions in the Subject Property Development Area	7-19
Table 7.7.2 – Depressional Storage Calculations	7-19
Table 7.8.1 – Drainage Areas for the Proposed SWM Ponds.....	7-21
Table 7.8.2 – Summary of SWM Pond Permanent Pool Requirements under Ultimate Development Conditions.....	7-23
Table 7.8.3 – Summary of SWM Pond Erosion Control Design.....	7-24
Table 7.8.4 – Summary of SWM Pond Outlet Control Structures	7-26
Table 7.8.5 – Model Results of Proposed Pond 2 under Ultimate Development Conditions.....	7-27
Table 7.8.6 – Model Results of Proposed Pond 3 under Ultimate Development Conditions.....	7-27
Table 7.8.7 – Model Results of Proposed Pond 1 under Ultimate Development Conditions.....	7-27
Table 7.8.8 – Model Results of Proposed Pond 5 under Ultimate Development Conditions.....	7-27
Table 7.8.9 – Summary of Pond Design Criteria.....	7-29
Table 7.9.1 – Downstream Regional Flow Comparison.....	7-32
Table 8.1 – Average Day Wastewater Flow.....	8-3
Table 8.2 – Generated WWTP Flows: 407 West Employment Area Land Use Plan Projections.....	8-4
Table 8.3 – Peak Generated Collection System at Colonel William Parkway Trunk Sewer: 407 West Employment Area Only	8-4

Table 8.4 – Peak Generated Collection System Flows to Dundas Trunk Sewer: Tremaine Dundas Community	8-6
Table 8.5 – Peak Generated Collection System Flows to Dundas Trunk Sewer – Existing Old Bronte Road Residential Development.....	8-6
Table 8.6 – System Unit Demands	8-10
Table 8.7 – Water System Design Criteria.....	8-11
Table 8.8 – Flow Demands: Linear Infrastructure (407 West Employment Area Land Use Plan Population Projections).....	8-11
Table 8.9 – Results of Water Distribution Modeling for Proposed ASP Water System	8-13

List of Appendices

1.0 Introduction

Appendix 1.1 – EIR FSS Terms of Reference

Appendix 1.2 – References

4.0 Hydrogeology and Geology

Appendix 4.1 – MOE Water Well Records

Appendix 4.2 – Borehole Logs

Appendix 4.3 – Soil Analysis Results

Appendix 4.4 – Hydraulic Conductivity Testing

Appendix 4.5 – Water Level Data

Appendix 4.6 – Groundwater and Surface Water Quality

Appendix 4.7 – Meteorological Information and Water Balance

5.0 Natural Environment

Appendix 5.1 – Field Work Chronology and Staff List

Appendix 5.2 – Wildlife

Appendix 5.3 – Vascular Plant List

Appendix 5.4 – Core #1 and Linkage to Core #2 / Vegetation Community mapping (Modified from NOCSS)

Appendix 5.5 – ELC Field Data Sheets

Appendix 5.6 – Water Temperature Monitoring Data

Appendix 5.7 – Field Survey Collection Sheets

Appendix 5.8 – Selected Agency Communications

Appendix 5.9 – Technical Memorandum NH#1 – Reach 14W-14A Aquatic Habitat

6.0 Water Resources

Appendix 6.1 – Regional Floodplain Analysis

Appendix 6.2 – Riparian Analysis

Appendix 6.3 – Technical Memorandum – HEC-RAS Model River Reach Flood Flow Estimation

Appendix 6.4 – Technical Memorandum – Topographic Depression Volume Analysis

Appendix 6.5 – Technical Memorandum – Corridor Width Delineation

Appendix 6.6 – Technical Memorandum – Stream Length and Drainage Density Requirements

Appendix 6.7 – Technical Memorandum – Meander Belt Width Estimation

7.0 Drainage and Stormwater Management

Appendix 7.1 – Fluvial Geomorphology

Appendix 7.2 – Regional Storm Control

Appendix 7.3 – Stormwater Management Calculations

Appendix 7.4 – Thermal Mitigation Calculations

Appendix 7.5 – Monitoring Program

8.0 Municipal Services

Appendix 8.1 – Wastewater Sewer Design Sheets

Appendix 8.2 – Water Peak Hour and Maximum Day Model Results

Appendix 8.3 – Stormwater Design Sheets

Appendix 8.4 – Conceptual Plan-Profiles of the Wastewater Sewer

Appendix 8.5 – Conceptual Grading Plan

Executive Summary



Executive Summary

This Environmental Implementation Report and Functional Servicing Study (EIR/FSS) has been prepared for a portion of lands within the Fourteen Mile Creek West catchment area (FM1001) and the bclMC Realty Corp. lands, managed by QuadReal Property Group (formerly Bentall Kennedy (Canada) LP) and commonly known as the “Lazy Pat Farms” property (Subject Property). A range of environmental and municipal servicing matters are addressed in this EIR/FSS as required by the approved Terms of Reference for EIR/FSS studies for North Oakville.

The Subject Property is located within the western portion of North Oakville West Secondary Plan (NOWSP) area, which has been defined as the 407 West Employment Area. The Subject Property is located on the north side of Dundas Street West (Highway 5), generally mid-block between Tremaine Road and Bronte Road (Highway 25), in the Town of Oakville. The property encompasses an area of approximately 185 acres (75 hectares).

The purpose of the EIR is to characterize and analyze the natural heritage features and functions and to determine and address the potential impacts of a proposed development application, including servicing requirements, on the Natural Heritage System (NHS). The purpose of the FSS is to identify servicing requirements related to sanitary, water, stormwater, roads, and site grading. Further, the purpose of both the EIR and FSS is to provide a link between the Town’s North Oakville Creeks Subwatershed Study (NOCSS) Management Report and Implementation Report, the NOWSP (OPA 289) and the Draft Plan of Subdivision submissions for development applications and identification of environmental and engineering draft plan conditions of approval for the Subject Property.

The following summarizes the major findings and recommendations of the EIR/FSS.

1.1 EIR Subcatchment Area and FSS Study Area

The Subject Lands are located primarily within the FM1001 subcatchment area, and smaller portions lie within the FM1102 and FM1109 subcatchment areas. The EIR subcatchment boundaries were refined using 2002 Town of Oakville topographic mapping. A comparison of updated existing drainage areas was made with drainage areas reported in the NOCSS Study. There are differences in drainage boundary interpretation resulting in approximately a 14 ha decrease in subcatchment FM1102, a 36 ha decrease in subcatchment FM1001 and a 3 ha increase in subcatchment FM1109; however, all drainage remains within the Fourteen Mile Creek system.

EIR Subcatchment Area is defined to be the FM1001 subcatchment, focusing on the area south of Highway 407. Environmental and engineering requirements for the small portions of FM1102 and FM1109 subcatchment areas have been addressed without the need to prepare an EIR for these subcatchment areas, in accordance with the Terms of Reference.

The FSS Study Area is defined to include the Subject Property; however, additional details have been provided for the entire 407 West Employment Area (lands bounded by Dundas Street West, Tremaine Road, Highway 407 and Regional Road 25 (Bronte Road)), to ensure servicing requirements for the areas external to the Draft Plan of Subdivision are adequate.

1.2 Natural Heritage System Framework

With respect to the Subject Property and the EIR Subcatchment Area, OPA 289, NOCSS and NOCSS Addendum identify various environmental features to be protected and/or studied further during the preparation of the EIR/FSS. As illustrated on Figure NOW 3 from OPA 289 (Figure 2.1), the components of the Natural Heritage System (NHS) that are located within the EIR Subcatchment Area, and related subcatchment areas on the Subject Property include the 'High Constraint Stream Corridor Area' and 'Medium Constraint Stream Corridor Area', and features designated as 'Other Hydrological Features', which includes Low Constraint Stream Corridors, Hydrologic Features "A" and Hydrologic Features "B" and topographic depressions. These natural heritage components are further addressed through Section 2.0 and Section 5.0 of the EIR/FSS.

1.3 Land Use

The proposed land uses for the Subject Property consist of a range of employment uses and associated natural heritage and open space uses, in accordance with the Region's and Town's land use and planning directions for the 407 West Employment Area. The development concept envisions the creation of an office and business park with prestige employment uses adjacent to Highway 407, due to increased visibility along this major Provincial Highway. Mixed employment uses, which include limited service and office uses, (i.e., identified as Mixed Employment) are envisioned at the major road intersections along the Dundas Street corridor and at major Arterial intersections to serve the employment area. It is proposed that more general industrial uses, such as mixed warehousing and office uses may be accommodated internal to the business park. The Development Area Concept Plan (Figure 3.1) and proposed Draft Plan of Subdivision (Figure 3.2) are further presented in Section 3.0.

The NOWSP, Figure NOW4 conceptually identifies a Major Trail System along the Burnhamthorpe Road extension, west of Bronte Road, extending to Tremaine Road, in addition to a Major Trail System within the NHS, along the main stream corridor which traverses the Subject Property and around the NHS associated with Fourteen Mile Creek. The Town's North Oakville Trails Plan, May 2013 provides further guidance with respect to trails planning in North Oakville. Figure 3.3 illustrates the conceptual trails plan within the 407 West Employment Area. Design considerations are provided to guide further trail design at later stages in the development process where the trail system interfaces with the NHS. Section 5.0 provides further details with respect to trail planning in relation to the NHS.

The Planning Rationale Report, prepared by WSP Canada Group Limited (WSP) (formerly MMM Group Limited), in support of the Draft Plan of Subdivision and Zoning By-law Amendment applications, concludes that the development proposal is consistent with the Provincial Policy Statement, the Region of Halton Official Plan and the NOWSP.

1.4 Hydrogeology and Geology

The Subject Property and the three subwatersheds that traverse the property are located in a hydrogeological environment that is not particularly favourable towards mitigation of infiltration losses. The surficial fine-grained deposits of Halton Till found throughout the study area serves to limit infiltration to the groundwater system (69 mm/year) and as a result, the local watercourse systems receive a little over two-thirds of their total water from surface runoff (141 mm/year). Based upon the results of the water balance analysis, almost all of the groundwater base flow into the watercourses occurs over the period of November

to May, when the entire shallow system, including upgradient reaches of the channel are saturated and contributing water to the watercourses. The watercourses are observed in a dry to ponded condition during the summer months as identified by the water balance, and the comparisons of measured stream flows to estimates from the water balance methodology are reasonable.

The lower reaches of the FM1001 tributaries (generally to the south of Highway 407) are interpreted as receiving minor groundwater contributions from the Queenston Shale bedrock but these contributions are insufficient to provide enough water to maintain flow in these watercourses during the summer months as the watercourses have been observed in dry to pooled conditions during these periods. Groundwater inputs from the bedrock into the realigned watercourses after development are however expected to increase compared with the pre-development levels. Over the lower reaches of the main channel there may be greater opportunity for bedrock-based groundwater to maintain pools in the channel as the bedrock is exposed in the channel and the watercourse is shaded somewhat by large trees.

The section of the FM1109 tributary (Reach 14W-11 and Reach 14W-11A) passing through the northeast corner of the Subject Property is interpreted from collected site data to be losing water to the ground, due to the nearby influence of a buried bedrock valley to the east. The large human-made farm pond at the central portion of the Subject Property is also shown to be maintained almost entirely by surface water inflow rather than from groundwater contributions on the basis of the comparison of the measured surface water levels at the pond against the groundwater elevations at monitoring wells constructed around the pond. Minor, seasonal groundwater seepage potential has been identified at a mini-piezometer station located to the northwest of the west end of the pond alongside Reach 14W-12A where both upward and downward gradients have been recorded. The quantity of water discharging to the channel in this area has been calculated to be quite small and any losses due to construction of the pond will be made up with water from a 40 m length of infiltration trench and from controlled flow of roof runoff from nearby buildings.

The upper weathered zone of the surficial till deposits found throughout the subwatershed provides the bulk of the groundwater inputs to the local watercourses, but on a seasonal basis over about seven months of the year. The enhanced permeability of this upper zone permits infiltrating groundwater to travel through the shallow zone towards the watercourses and it is these conditions that provide the most promising potential mitigation opportunities at this site.

The greatest opportunity for mitigating against infiltration losses at the Subject Property is along the edge of the existing valley lands where the naturally weathered and fractured surficial till soils will remain undisturbed by construction and will retain their ability to convey water laterally towards the watercourses. It is along these lands that infiltration swales primarily receiving clean roof runoff are proposed, and such infiltration measures are calculated to reduce the post-development on-site infiltration deficits from approximately 62% (with no mitigation proposed) to a balance with the pre-existing conditions with the use of the infiltration swales.

1.5 Natural Environment

The Subject Property and surrounding lands consists principally of agricultural lands that are actively farmed intermixed with recreation and rural residential uses that are dissected by a local and regional road network. The notable natural features within the catchments areas of the Subject Property include the Oakville-Milton Wetlands & Uplands Candidate Life Science Area of Natural and Scientific Interest (ANSI), North Oakville – Milton Wetlands – West Provincially Significant Wetland (PSW) Complex, Trafalgar

Moraine Candidate Provincially Significant Earth Science ANSI, Halton Region Significant Woodlands, as well as, features identified in NOCSS including Core #1 and Linkage to Core #2 and Stream Corridors associated with Fourteen Mile Creek including watercourses supporting Redside Dace and Hydrological Features. With the exception of the Stream Corridors and Hydrological Features the remaining features are located beyond the boundary of the Subject Property. Within the boundaries of the Subject Property the main natural features consist of tributaries of Fourteen Mile Creek including Redside Dace habitat, as well as, their associated riparian habitat. Species at Risk (SAR) discussions with the Ministry of Natural Resources and Forestry (MNRF) (formerly Ministry of Natural Resources) were undertaken for the species identified within the Subject Property. Consultation has indicated that approvals under the Endangered Species Act (2007) will be required for impacts related Redside Dace and potentially for Bobolink, Barn Swallow, and two bat species; Little Brown Myotis and Northern Myotis. All approvals will be confirmed during detailed design.

Detailed field investigations were undertaken between 2009 and 2011 to supplement background data from the NOCSS, previous field investigations undertaken on site by WSP (formerly MMM Group Limited which was formerly Marshall Macklin Monaghan Limited) and to address comments received from Conservation Halton (CH) and the Town of Oakville. This data was used to verify the NOCSS classification of habitat, as well as, assess potential impacts to the natural features associated with the proposed concept plan. With the exception of a section of Reach 14W-12 and Reach 14W-14A, generally the field data supported the NOCSS classification of form and function and associated constraints.

Potential effects to the natural heritage system associated with the proposed concept plan were also examined, taking into consideration the habitat present, as well as, mitigation measures, to determine potential residual impacts. Previous consultation with Fisheries and Oceans Canada (DFO) has indicated that a *Fisheries Act* (FA) (1985) Authorization will not be required for the consolidation and realignment of Reach 14W-13 and Reach 14W-14, as well as, the realignment of Reach 14W-11A. The proposed realignments will provide suitable opportunities to undertake restoration works in watercourses that have been altered by agricultural activities including the incorporation of greater habitat diversity (i.e., riffles, pools) and improved riparian cover as identified in the enhancement strategies. These restoration works will be implemented to address potential adverse effects to fish and fish habitat associated with the proposed realignments works.

The development concept plan also proposes to remove the existing bypass pond (Reach 14W-14A) and its incorporation into the proposed stormwater management plan, with enhanced water quality treatment to improve water quality discharged to downstream fish habitat in Reach 14W-12. This will result in the removal of a constructed agricultural pond feature that, due to its current form, has adverse thermal and water quality effects to downstream Redside Dace habitat. Its removal is anticipated to benefit fish and fish habitat. DFO has indicated that the effects to Reach 14W-14A will not require a FA (1985) Authorization.

The proposed development will also result in changes to flow within the reaches, most notably within the upper section of Reach 14W-12 (referred to as Reach 14W-12A in this report). The effect of this change in flow was examined based on the ecological function of the relatively short section of the reach to be affected and the anticipated change in flow. Based on the function of this short section, it is anticipated that any adverse effects can be addressed through the proposed habitat enhancements in other reaches.

The natural heritage components are further addressed in Section 5.0.

1.6 Water Resources

The refinement of corridor widths for high and medium constraint streams have been completed based on the guidance provided in the NOCSS. A medium constraint stream corridor (Reach 14W-14) and a low constraint stream corridor (Reach 14W-13) of the West Branch of Fourteen Mile Creek within the Subject Property are proposed to be diverted to Reach 14W-12A, approximately 20 metres upstream of the connection with 14W-12 to accommodate the development. The proposed diversion (Reach 14W-21) along Highway 407 will intercept flows from Reach 14W-13 and Reach 14W-14 just downstream of Highway 407 and eventually divert them to Reach 14W-12A via another proposed diversion (Reach 14W-22) along the southwest limits of the Subject Property. Another medium constraint stream corridor (Reach 14W-11A) of the West Branch of Fourteen Mile Creek will be realigned along Highway 407 and the northeast limits of the Subject Property.

All proposed diversion channels have been developed based on the principles of Natural Channel Design and NOCSS requirements. The proposed Natural Channel Design features (e.g., pools, riffles, and floodplain wetlands) provide great opportunity to sustain or even improve the ecological functions already existing in Reach 14W-13, Reach 14W-14, and Reach 14W-11A.

The HEC RAS model was updated to account for the proposed re-alignments. Changes in bed elevation and water surface elevations, due to changes in connectivity and continuity were analyzed in terms of conveyance, floodplain mapping, and riparian storage. The floodlines under interim and ultimate conditions were delineated, and they fall within the meander belt + factor of safety width in most cases. In a few instances, where floodlines were not encompassed within that limit, the Hazard Allowance setback was offset from the floodlines, following the recommendations of the NOCSS.

Riparian storage analysis, for all reaches within the Subject Property, shows that there is an increase in riparian storage for all flows, especially medium and high flows. There are cases where storage is decreased from 5% to 13% for flows in the lower range.

1.7 Stormwater Management

In accordance with the NOCSS, the NOCSS unit flow rates have been used along with the updated existing drainage areas to calculate pre-development peak flow rates at both EIR nodes and reference flow nodes. As required by NOCSS and the EIR/FSS Terms of Reference, alternative Stormwater Management Practices are described and evaluated for application in the EIR Subcatchment Area, and a stormwater management plan was selected to satisfy NOCSS and Town of Oakville stormwater management goals, objectives and targets.

The soils within the Subject Property have been characterized as clay loams that have a relatively low infiltration potential and the proposed employment land uses have a high imperviousness to accommodate viable employment development blocks. Therefore, minimal opportunities to implement infiltration techniques are anticipated, other than the potential for proposed infiltration swales alongside the valley corridors. Opportunities to integrate low impact development measures at the lot level will be considered at the detailed design stage. The current strategy is aimed at addressing stormwater impacts from the dense urban form planned under the Town's policies and guidelines. As the eventual imperviousness of the final blocks will be determined by the prospective tenants, conservative assumptions on block coverages have been utilized to devise a stormwater management strategy. Any built form proposals that reduce lot

imperviousness and/or install low impact development techniques or on-site stormwater management controls will reduce flow rates and pollutant loadings to the proposed stormwater management facilities and should be encouraged.

A stormwater management plan has been developed for the Subject Property based on the guidance provided in the NOCSS. Preliminary designs have been completed for the four stormwater management (SWM) facilities associated with the subject study area, including two SWM facilities within the Subject Property and the other two SWM facilities located outside of the Subject Property, east of Tremaine Road between Highway 407 and Dundas Street. The following provides a summary for the SWM plan:

- **Water Quantity:** The stormwater management facilities are sized to control the post-development peak flows to pre-development levels for the 2-year to 100-year return period events and the Regional Storm.
- **Water Quality:** The SWM facilities are designed to meet MOECC's Enhanced Level of water quality protection (Level 1) for water quality control, phosphorus control and fisheries protection (thermal mitigation).
- **Erosion Control:** The detailed erosion threshold analyses including a fluvial geomorphological study were performed to ensure the proposed SWM facilities would provide adequate erosion control protection for the downstream watercourses, so that existing channel erosion or aggradation is not exacerbated by development.
- **Hydrologic Flow Regimes Analysis:** A comprehensive investigation of the impact of development has been carried out on all flow nodes within the Subject Property. Where reaches were to be re-aligned or where habitat concerns had been communicated with the study team, detailed assessments were incorporated. Specifically, the magnitude of peak flows will only decrease by 15-20% from existing conditions for Reach 14W-22 and Reach 14W-23, and the duration and frequency will be similar. For Reach 14W-12A, although reductions in stream flows are anticipated, the wetted perimeter and continuity of the flows will be maintained.
- **Topographic Depression Volumes:** Evaluation of the existing depression storage was performed to ensure that the natural depression storage would be maintained in the SWM system.
- **SWM Pond Design:** The SWM facilities are design to meet all the criteria as enforced by the MOECC and in accordance with the Town of Oakville design guidelines.
- **Downstream Impacts for Regional Storm:** With the proposed SWM facilities providing Regional controls for the developments within the Subject Property, there will be no impact to the downstream watercourses due to the development of the Subject Property. As a prudent measure, a hydrological analysis for the entire Fourteen Mile Creek subwatershed was carried out to investigate and ensure that there would not be potential increases to flood risk for the entire downstream watercourse to its outlet at Lake Ontario during Regional Storm conditions.

1.8 Municipal Servicing

Section 8.0 outlines the municipal services for the 407 West Employment Area and Subject Property based on the proposed development concept plan. This includes proposed wastewater servicing, water distribution, stormwater servicing and management, and conceptual road and lot grading. The servicing design was developed using the information and guidelines provided by the Region of Halton's Water and Wastewater Master Plan, the NOCSS and the approved 407 West Employment Area – Area Servicing Plan, June 2014, prepared by WSP (formerly MMM Group).

Wastewater servicing design consists of a gravity flow system which drains north to south and connects to the proposed trunk sewer on Dundas Street West, ultimately discharging to the existing Colonel William Parkway wastewater system. The conceptual wastewater servicing design is described in detail in Section 8.2 and illustrated in Figure 8.2.

The water distribution system will be serviced from the Oakville pressure district Zone 3 supply, connecting at Dundas Street West and Bronte Road with an interconnection to Burlington Zone B3, connecting at Dundas Street West and Tremaine Road. Water will be supplied through a system of trunk and local mains within the proposed road network in accordance with the Regional Master Plan. Sizing of watermain was determined using the water model outlined in Section 8.3 and illustrated in Figure 8.4 and Appendix 8.2.

Stormwater servicing will consist of gravity sewers within the conceptual road network that will discharge to SWM facilities for treatment based on the catchment areas indicated in Section 7.0. The major storm system will convey the major storm flows via an overland flow route along the road rights-of-way to the designated SWM facility. The conceptual minor and major storm system designs are illustrated on Figure 8.5.

The conceptual road and lot grading was designed with the intention of matching existing grades as closely as possible while still maintaining necessary elements of the Stormwater Management Plan detailed in Section 7.0. The conceptual grading plan is illustrated on Figure 8.6.

1.0 Introduction



1.0 Introduction

1.1 Study Purpose

This Environmental Implementation Report and Functional Servicing Study (EIR/FSS) has been prepared in accordance with the requirements of the Town of Oakville North Oakville Environmental Implementation Report and Functional Servicing Study Terms of Reference (ToR), August 2, 2007 (Revised May 2013), for a portion of lands within the Fourteen Mile Creek West catchment area, commonly known as the “Lazy Pat Farms” property, as shown on Figure 1.1. This parcel of land is owned by bclMC Realty Corp. and managed by QuadReal Property Group (previously managed by Bentall Kennedy (Canada) LP) and is herein referred to as the “Subject Property”.

The Subject Property is located within the western portion of North Oakville West Secondary Plan (NOWSP) area, which has been defined as the 407 West Employment Area. The Subject Property is located on the north side of Dundas Street West (Highway 5), generally mid-block between Tremaine Road and Bronte Road (Highway 25), in the Town of Oakville. The municipal address is 3269 Dundas Street West, Oakville and is legally described as Part of Lots 33 and 34, Concession 1, North of Dundas Street, Township of Trafalgar, now in the Town of Oakville, Regional Municipality of Halton. The Subject Property encompasses an area of approximately 185 acres (75 hectares).

This EIR/FSS has been prepared to address the NOWSP policy requirements in support of the approval of a Draft Plan of Subdivision and Zoning By-law Amendment application for the Subject Property. The NOWSP was adopted by Council on May 25, 2009. On December 4, 2009, the Ontario Municipal Board (OMB) approved the majority of the NOWSP, save and except for lands shown as Appeal Area on Attachment A of the decision which generally includes the lands bound by Fourteen Mile Creek on the west; Highway 407 on the north; Bronte Road to the east (including certain lands fronting on the east side of Bronte Road); and Dundas Street to the south. These lands remain under appeal, until such time as an OMB decision is rendered. The balance of the area, which includes the Subject Property is subject to the NOWSP which came into force and effect as of December 4, 2009.

OPA 289 establishes the NOWSP for the lands generally bounded by Dundas Street, Tremaine Road, Highway 407 and the Sixteen Mile Creek. The NOWSP includes land use designations and detailed policies establishing general development objectives to guide the future development of this area.

The NOWSP also sets out the requirements which must be met before any development can proceed. This included the preparation of an EIR/FSS:

- Policy 8.8.3 a) requires that an Environmental Implementation Report (EIR) be prepared for each subcatchment area, in accordance with the directions established in the North Oakville Creeks Subwatershed Study (NOCSS) Implementation Report for each subcatchment area identified in Appendix 8.2. The EIR must demonstrate how the submissions address the overall North Oakville Creeks Subwatershed Management Report. Policy 8.8.3 a) iii) requires that Environmental Implementation Reports be prepared in accordance with ToR approved by the Town of Oakville (the “Town”), the Region of Halton (the “Region”) and the applicant(s), in consultation with Conservation Halton (“CH”).

-
- Policy 8.8.3.b) requires that a Functional Servicing Report (FSS) be prepared for each plan of subdivision or major development application. The FSS must include a preferred servicing plan based on an analysis of servicing requirements, in accordance with any approved Class Environmental Assessment Studies, Halton Transportation Master Plan and the Master Servicing Plan for the North Oakville West Planning Area and including:
 - i. servicing design requirements;
 - ii. preliminary sizing of water and wastewater infrastructure;
 - iii. layout for roads and other transportation systems including transit and trails;
 - iv. preliminary sizing and location of stormwater management facilities; and
 - v. integration with environmental features and development areas.

An Area Servicing Plan (ASP) has been prepared by MMM Group Limited for the 407 West Employment Area (area bound by Dundas Street West, Tremaine Road, Highway 407, and Regional Road 25 (Bronte Road)), based on the Area Servicing Plan ToR provided by the Region. The ASP was approved by the Region on June 2, 2014.

The work completed as part of this EIR/FSS and documented in this report was guided by requirements set out in the EIR/FSS ToR (Revised May 2013) approved by the Town and CH, and is intended to satisfy the policy requirements of OPA 289. A copy of the approved ToR is provided in Appendix 1.1.

As identified in the ToR, the purpose of the EIR is to characterize and analyze the natural heritage features and functions and to determine and address the potential impacts of a proposed development application, including servicing requirements, on the Natural Heritage System (NHS). The purpose of the FSS is to identify servicing requirements related to sanitary, water, stormwater, roads, and site grading. Further, the purpose of both the EIR and FSS is to provide a link between the Town's NOCSS Management Report and Implementation Report, the NOWSP and the Draft Plan submissions for development applications.

The objectives to be fulfilled by the EIR/FSS are set out in the approved ToR, and:

Demonstrate how the subwatershed requirements set out in the NOCSS Management Report (including targets), the Implementation Report, and Secondary Plan are being fulfilled in all proposed Draft Plans;

- Provide sufficient level of conceptual design to ensure that the various components of the NHS and infrastructure can be implemented as envisaged in the NOCSS and Secondary Plan and to ensure that the Draft Plans are consistent with this conceptual design;
- Ensure servicing requirements as determined in the FSS for the areas external to the Draft Plan are adequate;
- Identify details regarding any potential development constraints or conflicts and how they are to be resolved;
- Provide any further implementation details as needed;
- Streamline the Draft Plan approval process; and,
- Facilitate the preparation of Draft Plan conditions.

As set out in the ToR, the EIR/FSS for the Subject Property has been prepared as a joint report to fully integrate environmental and engineering recommendations to protect the function of the NHS and service the Subject Property.

1.2 EIR Subcatchment Area and FSS Study Area

The Subject Property is located primarily within the FM1001 subcatchment area; and smaller portions lie within the FM1102 and FM1109 subcatchment areas. The limits of these subcatchments within the Subject Lands are shown on Figure 1.2 and have been refined from the subcatchment areas identified in the NOCSS based on further analysis undertaken through the preparation of this EIR/FSS as provided in Section 7.0. Table 1.1 notes the subcatchments draining the Subject Property and the areas/percentages of the Subject Property lying within each subcatchment area.

Table 1.1 – Subwatershed Areas

Subwatershed	Subwatershed Area (ha)	Subwatershed Area within Subject Property (ha)	Proportion of Subwatershed within Subject Property (%)	Proportion of Subject Property within the Subwatershed (%)
FM1102	44.4	4.7	11%	6%
FM1001	395.3	60.4	15%	81%
FM1109	365.0	10.0	3%	13%
Subject Property		75.1		100%

The EIR/FSS ToR differentiate between the study area for the FSS and the subcatchment study area for the EIR. The EIR is to be completed on a subcatchment basis, while the FSS will address specific servicing requirements in support of draft plans of subdivision.

The NOCSS provides direction to the preparation of EIRs including the delineation of EIR subcatchments. Figure 7.4.2 from the NOCSS Addendum illustrates the EIR subcatchment areas. With reference to this figure (included at the end of this section) and direction from the ToR, the appropriate study areas for this EIR/FSS are:

- EIR Subcatchment Area is defined to be the FM1001 subcatchment, focusing on the area south of Highway 407; and,
- FSS Study Area is defined to include the Subject Property, which consists of the lands owned by bclMC Realty Corp.; however, sufficient details have been provided for the 407 West Employment Area.

The EIR Subcatchment Areas and the FSS Study Area for the Subject Property are shown on Figure 1.2.

The ToR recognizes that ownership or draft plan boundaries will not follow subcatchment boundaries and allow for the assessment of portions of subcatchments where reasonable. The ToR recognizes that where the proposed development is within the majority of the EIR subcatchment with minor portions outside:

- Consideration will be given to minor adjustments in subcatchment boundaries with the conditions that the adjustments would not put undue restrictions on the servicing of adjacent subcatchments and demonstrate no negative impacts to flooding, erosion and the NHS; and,

-
- If no change in subcatchment boundary is proposed, consideration is to be given to how development in the adjacent subcatchment is to be serviced. Conceptual drainage patterns are to be developed and profiles generated to ensure that the area can be serviced.

This EIR/FSS has addressed the subcatchment and draft plan requirements for the small portions of the Subject Property located within the FM1102 and the FM1109 subcatchment areas, without preparing complete EIRs for these subcatchment areas. With respect to the FM1102 subcatchment area, the portion of the Subject Property within this subcatchment is relatively small (4.7 ha), comprising approximately 11% of the entire subcatchment area. With respect to FM1109 subcatchment area, the portion of the Subject Property within this subcatchment is relatively small (10.0 ha), comprising approximately 3.0% of the entire subcatchment area. This EIR/FSS focuses on the FM1001 subcatchment and provides discussion of subcatchments FM1109 and FM1102 to the extent required.

This EIR/FSS consistently uses the following terms when referring to various land areas:

- the “Subject Property” referring to the bclMC Realty Corp. land holdings managed by QuadReal Property Group (previously managed by Bentall Kennedy (Canada) LP);
- the “FSS Study Area” referring to the Subject Property;
- the “EIR Subcatchment Area” referring to the FM1001 subcatchment area; and,
- the “Study Areas”, referring to both the EIR Subcatchment Area and the FSS Study Area.

As required by the EIR/FSS ToR, land uses as proposed by the Town’s NOWSP for lands adjacent to the FSS Study Area are recognized and considered in planning, transportation and servicing analyses. As such, land use and development assumptions have been made to facilitate the preparation of this EIR/FSS. The land use and development assumptions for purposes of analysis reflect best practices and procedures for undertaking such planning, transportation and servicing analyses. The adjacent lands are designated Employment District and Natural Heritage and Open Space in the NOWSP.

1.3 Study Team

A multidisciplinary study team lead by WSP Canada Group Limited (WSP) (formerly MMM Group Limited) has studied the environment and servicing of the Study Areas. The team and their responsibilities include:

WSP Canada Group Limited (formerly MMM Group Limited):

- lead EIR consultant addressing limits of development, study integration, team/study management and coordination of EIR/FSS report preparation;
- lead FSS consultant addressing municipal servicing, stormwater management and site grading;
- aquatic habitats;
- terrestrial ecology;
- geology and hydrogeology;
- hydrology and fluvial geomorphology; and,
- municipal planning matters and preparing the draft plan of subdivision.

Waters Edge:

- fluvial geomorphological and erosion threshold assessment.

Exp. Consulting:

- geotechnical and slope stability analysis.

1.4 References

Included in Appendix A1.2 is a complete list of references, studies, guidelines and documents which have been reviewed in preparation of this EIR/FSS.

Environmental Implementation
Report / Functional Servicing Study
for 14 Mile Creek West and the Lazy
Pat Farm Property

Study Areas

LEGEND

-  Subject Property
-  407 West Employment Area
-  Subcatchment Area Boundaries
-  EIR Subcatchment Area (FM1001)
-  FSS Study Area


Scale

1 : 15,000

0m1002003004005001km



Client	Prepared by
	
Date	Proj. No.
June 2017	09M-00013-01 (1409222-001)
Aerial Photo	
© DigitalGlobe 2010, Google 2009	Figure 1.2



2.0 Natural Heritage System Framework



2.0 Natural Heritage System Framework

2.1 Natural Heritage System Components

The 'Natural Heritage System Area' designation of the NOWSP reflects the components of the Natural Heritage and Open Space System and is intended to protect, preserve, and where appropriate, enhance the natural environment. OPA 289, the Town's NOCSS and the NOCSS Addendum provide policies and/or directions with respect to the protection and management of the North Oakville West Natural Heritage/Open Space System. The NOCSS is divided into four sections, which follow the four phases of a subwatershed management approach, they include Characterization, Analysis, Management Strategy and Implementation.

The Management Strategy outlines requirements with regard to lands restricted from development, lands with development limitations or constraints, stormwater management, input to land use policies and servicing requirements. The Implementation Plan outlines the implementation requirements for the recommended management strategy, studies needed in subsequent stages of the development process, environmental reporting requirements, agency responsibilities, and the approval process with the Town, the Region and CH, and, where applicable, the Ministry of Natural Resources and Forestry (MNRF) and Fisheries and Oceans Canada (DFO).

With respect to the Subject Property and the EIR Subcatchment Area, OPA 289, NOCSS and the NOCSS Addendum identify various environmental features to be protected and/or studied further during the preparation of the EIR/FSS. As illustrated on Figure NOW3 from OPA 289 (Figure 2.1), the components of the Natural Heritage System (NHS) that are located within the EIR Subcatchment Area, and related subcatchment areas on the Subject Property include the 'High Constraint Stream Corridor Area' and 'Medium Constraint Stream Corridor Area', and features designated as 'Other Hydrological Features', which includes Low Constraint Stream Corridors, Hydrologic Features "A" and Hydrologic Features "B" and topographic depressions.

These natural heritage components are further addressed through Section 5.0 of the EIR/FSS.

- **High Constraint Stream Corridor Areas (Red Streams)** – include certain watercourses and associated riparian lands, including buffers measured from stable top-of-bank and meander belts, including the 15 metre allowance measured from the Regional Storm floodplain. They must be protected in their existing locations for hydrological and ecological reasons in accordance with the NOCSS. High Constraint Stream Corridor Areas located on the Subject Property, as identified in the NOCSS include Reach 14W-12 located north of Dundas Street to the confluence with Reach 14W-16; and Reach 14W-11 (High Constraint Stream Corridor Requiring Rehabilitation), along the eastern property boundary. The High Constraint Stream Corridor reaches and associated riparian lands will be protected and enhanced, where feasible.

Section 5.0 of the EIR/FSS addresses the character, designations, management and protection of these High Constraint Stream Corridors within the EIR Subcatchment Area.

-
- **Medium Constraint Stream Corridor Areas (Blue Streams)** – include certain watercourses and associated riparian lands, including buffers measured from stable top-of-bank and meander belts, including the 7.5 or 15 metre allowance measured from the Regional Storm floodplain. They must be protected for hydrological and ecological reasons, but may be deepened and/or relocated and consolidated with other watercourses provided the watercourse feature and function of the watercourse is maintained in accordance with the NOWSP (S. 8.4.7.1 e)). In addition, Federal, Provincial and Conservation Authority regulations must be adhered to, and the relocated and/or consolidated watercourses must be designed using natural channel design principles.

The Medium Constraint Stream Corridor Areas include Reach 14W-16, Reach 14W-14, Reach 14W-14A, and Reach 14W-11A. The NOWSP provides policies for the relocation of Medium Constraint Stream Corridor Areas. The Development Concept proposes modifications to the drainage network, specifically these Medium Constraint Stream Corridors and are discussed further in Sections 5.0 and 6.0.

Sections 5.0 and 6.0 of the EIR/FSS address the character, designations, management, alteration and protection of these Medium Constraint Steam Corridors within the EIR Subcatchment Area.

The boundaries of the High Constraint Stream Corridor Areas and Medium Constraint Stream Corridor Areas are to be maintained as generally shown on Figure NOW 3 from OPA 289 (Figure 2.1); however, minor modifications have been considered to reflect differences in scale and levels of detail during the preparation of the EIR.

There are no Core Preserve Areas or Linkage Preserve Areas located on the Subject Property. The protection and management of these Core Preserve Areas and Linkage Preserve Areas within the 407 West Employment Area are subject to the NOWSP and NOCSS and are to be further evaluated through EIR/FSS for these respective subcatchment areas.

In addition to the High and Medium Constraint Stream Corridor Areas, there are a number of other hydrological features that also form part of the Natural Heritage and Open Space System to the extent that they are maintained after development occurs. These features include Low Constraint Stream Corridors, Hydrologic Features “A” and Hydrologic Features “B”, as described below:

- **Low Constraint Stream Corridors (Green Streams)** – while the streams do not need to be maintained, the function of the watercourse must be maintained in accordance with the NOCSS, and Federal, Provincial and Conservation Authority regulations. Low Constraint Steam Corridor Area (Reach 14W-13) is removed; however, the function of the watercourse is maintained within the relocated channel. The removal of this reach is consistent with the NOWSP policies for Low Constraint Stream Corridor Areas.
- **Hydrologic Features “A”** – where a Hydrologic Features “A” is located within a Medium Constraint Stream Corridor which is to be moved or rehabilitated, it is intended that the Hydrologic Features “A” will be reconstructed in the relocated/rehabilitated stream corridor such that the form and function is retained or enhanced. There are three Hydrologic Features “A” located on the Subject Property, including features within Reach 14W-14, Reach 14W-16 and the existing Farm

Pond (Reach 14W-14A). These features have been considered through the detailed hydrological and hydrogeological assessment as part of the EIR/FSS.

- **Hydrologic Features “B”** – are not associated with the NHS, and may be relocated and consolidated with other wet features, wetlands or stormwater management (SWM) facilities, provided the hydrologic function of the feature is maintained. There are three Hydrologic Features “B” located on the Subject Property. These features have been considered through the detailed hydrological and hydrogeological assessment as part of the EIR/FSS.
- **Topographic Depressions** – Topographic depressions do not form part of the NHS; however, NOCSS (Figure 6.3.15) identifies topographic depressions, ponds and pits that must be addressed as part of the SWM system design. Constructed ponds do not have to be included in the assessment of depression storage. These topographic depressions have been considered through the drainage and SWM assessment as part of the EIR/FSS, and the analysis has demonstrated that the SWM facilities volumes compensate for the hydrologic influence of the existing depression areas.

2.2 Permitted Uses in the Natural Heritage System

Section 8.4.7.3 of the NOWSP identifies the potential permitted uses within the NHS. Permitted uses within the NHS Area designation shall include only legally existing uses, buildings and structures, and fish, wildlife and conservation management. Development or land disturbances shall generally be prohibited. In accordance with S. 8.4.7.3 b), exceptions are permitted subject to the satisfaction of the Town, in consultation with the Region and CH, to accommodate such uses as:

- required flood and stream bank erosion controls;
- fish, wildlife and conservation management;
- to accommodate stormwater outfalls;
- the relocation of deepening of Medium Constraint Stream Corridor Areas; roads and related utilities;
- expansion of existing water and wastewater services;
- trails, interpretive signage or similar passive recreation uses; and
- SWM facilities,

These uses would be subject to S. 8.4.7.3 c) v), and in accordance with the directions of the NOCSS and any related EIR, and Federal, Provincial and Conservation Authority regulations.

SWM facilities established in accordance with the directions of the NOCSS may be permitted within the NHS Area, as outlined in Section 8.4.7.3 c) v), provided, the number, location and size of the SWM facilities have been identified through the EIR/FSS, and provided that generally such facilities:

“be limited where located in or adjacent to High and Medium Constraint Stream Corridor Areas, which are not located within Linkage Preserve Areas as designated conceptually on Figure NOW 3 [from OPA 289], to areas:

- *outside the 100 year floodline;*
- *outside the meanderbelt allowance which is the meanderbelt plus the factor of safety;*

-
- *outside the erosion/access allowance measured from the meander belt or stable top-of-bank, except that some overlap of the access required for the SWM facility and the erosion/access allowance may be permitted in accordance with the directions established in the NOCSS, and to the satisfaction of the Town and CH;*
 - *outside the confined valley; and,*
 - *provided that there is no loss of flood storage or conveyance”*

The NHS designation on the Subject Property does not comprise Core Preserve or Linkage Preserve Areas. Stream Corridor Reach 14W-12 is identified on Figure NOW 3 from OPA 289 as High Constraint Stream Corridor, and the human-made Farm Pond (Reach 14W-14A) is identified as a Medium Constraint Stream Corridor and a Hydrologic Feature ‘A’.

The EIR/FSS has determined the size and configuration of the SWM facilities and supports the use of the existing Farm Pond (Reach 14W-14A) as a SWM facility. The SWM facilities are proposed to be located outside of the 100 year floodline; outside of the Regional Storm floodline; outside the meanderbelt allowance which is the meanderbelt plus the factor of safety; outside the erosion/access allowance; outside the confined valley, and outside the 30 metre setback. The EIR/FSS demonstrates that there is no loss of flood storage or conveyance.

The Draft Plan of Subdivision delineates the SWM blocks to ensure sufficient area for the detailed design of the SWM facilities and all of the ancillary features such as sediment dewatering areas, and maintenance access. Furthermore, as outlined in the EIR/FSS, from a fisheries perspective the existing Farm Pond (Reach 14W-14A) appears to have a negative effect on downstream aquatic habitat and its removal and reconfiguration as a SWM facility would provide aquatic benefits.

Environmental Implementation
Report / Functional Servicing Study
for 14 Mile Creek West and the Lazy
Pat Farm Property

Figure NOW 3: Natural Heritage
Components of Natural Heritage and
Open Space System including Other
Hydrological Feaures

LEGEND

Subject Property

Secondary Plan Area Boundary

Core Preserve Area

Core Preserve Area

Linkage Preserve Area

High Constraint Stream Corridor


Medium Constraint Stream Corridor

Other Hydrological Features

Low Constraint Stream Corridor

Hydrologic Features "A"

Hydrologic Features "B"



Client

 QuadReal

Prepared by



Date

June 2017

Proj. No.

09M-00013-01
(1409222-001)

Figure 2.1

3.0 Land Use



3.0 Land Use

3.1 Development Concept Plan

The proposed land uses for the Subject Property consist of a range of employment uses and associated Natural Heritage and Open Space uses, in accordance with the Region's and Town's land use and planning directions for the 407 West Employment Area. The development concept envisions the creation of an office and business park with prestige employment uses adjacent to Highway 407, due to increased visibility along this major Provincial Highway. Limited employment-related commercial and service/retail uses, including office uses (i.e., identified as Mixed Employment (Service/Office)) are envisioned at the major road intersections along the Dundas Street corridor to serve the employment area. Furthermore, limited employment-related commercial and service/retail uses may be accommodated internal to the 407 West Employment Area at major intersections, as part of an employment or office building. It is proposed that more general industrial uses, such as mixed warehousing and office uses be accommodated internal to the business park.

Figure 3.1 illustrates the concept plan for the Study Area based on the direction of the Town's NOWSP. The concept plan for the Study Area is generally consistent with the Town's NOWSP and Master Plan and incorporates modest revisions to the proposed road network based on further study. The road pattern follows a modified grid pattern which responds to the existing environmental and site conditions while encouraging accessibility and a viable transit network throughout the 407 West Employment area. The conceptual road network identified in the NOWSP does not provide a sufficient network to facilitate the appropriate development of the 407 West Employment Area, based on more detailed study undertaken through this EIR/FSS. WSP (formerly MMM) has provided various comments to the Town in relation to the NOWSP road pattern, and based on these discussions with the Town it was recognized that the road network is conceptual and may be further refined, this is further supported by the policies of the NOWSP. Modifications to the road network have been proposed to: minimize the impact on the existing GE Facility site and operations, by shifting Avenue One to the south; minimize the impacts on the NHS by shifting the Burnhamthorpe Road alignment north of the High Constraint Stream Corridor and existing Farm Pond on the Subject Property, and modifying the road alignments to accommodate appropriate access to larger sized employment blocks, particularly to the north of the planning area.

The concept plan accommodates three intersection locations with Dundas Street West, including the existing intersections with Valleyridge Drive and Colonel Williams Parkway. A new intersection with Dundas Street is proposed adjacent to the western boundary of the Subject Property to provide access to the Subject Property and adjacent lands to the west, this new intersection is approximately equal distance between Tremaine Road and the eastern extent of the NHS on the Subject Property.

The proposed road alignments have been identified in order to minimize the number of crossings and the impacts to the NHS, particularly the Burnhamthorpe Road Extension which has been shifted further north to avoid crossing the existing High Constraint Stream Corridor, and is proposed outside the Reach 14W-12A High Constraint Stream Corridor, as identified in the NOWSP. The road crossings through the NHS will be designed to minimize disruption to the watercourses, through appropriate road crossing construction practices, and minimize encroachment into Redside Dace Habitat (i.e., the Burnhamthorpe Road Extension), as discussed further in Section 5.0.

Two major east/west road corridors are proposed as identified in the NOWSP to accommodate access from Tremaine Road to Regional Road 25 (Bronte Road). The proposed road network through the Subject Property provides flexibility for multiple road alignment options through adjacent properties. The southern east/west road aligns with the proposed New North Oakville Transportation Corridor (Burnhamthorpe Road Extension) proposed on the east side of Bronte Road. The Burnhamthorpe Road Extension west of Bronte Road will be under the jurisdiction of the Town. While the intersection locations for Burnhamthorpe Road are fixed at the intersection with Bronte Road and where it enters the Subject Property, the alignment of the Burnhamthorpe Road Extension between these intersections is flexible and may be modified through subsequent planning work on the adjacent lands. The spacing and locations of these intersections is consistent with the NOWSP and aligns with the planning work being undertaken for the Dundas/Tremaine Secondary Plan area in the City of Burlington and the New North Oakville Transportation Corridor EA.

The alignment of Avenue Two is generally consistent with the NOWSP and extends north and to the west of the NHS, to avoid crossing Medium Constraint Stream Corridor Reach 14W-16. The alignment of Avenue Two has been revised following further review and discussion with the Town and CH in order to minimize the number and extent of stream crossings while providing an efficient road pattern which supports the development of the employment area, in addition to addressing landowner coordination issues related to the Avenue Two road location and alignment.

The alignment of Avenue One was designed to minimize the length of required road crossings from that identified in the NOWSP, and minimize impacts to the existing GE Facility. West of the GE Facility, Avenue One shifts to the north, as it traverses the Subject Property, to provide sufficient access to the northern portion of the Subject Property and facilitate suitably sized employment blocks.

Avenue Three aligns with the existing intersection at Dundas Street and Colonel Williams Parkway, and will facilitate access to the Subject Property and the GE Facility, through a new road designed and constructed to the Town's standards. Furthermore, by shifting Avenue Three to the west and onto the Subject Property, the road alignment provides for more suitably sized future employment blocks, particularly on the GE lands fronting the east side of Avenue Three.

The development concept plan delineates the proposed Natural Heritage and Open Space System based on the Town's NOWSP and NOCSS, which has been further refined for the Subject Property based upon the recommendations of the EIR/FSS. The NHS and adjacent SWM facilities on either side of the NHS, will provide a central focus for the business park, and accommodate pedestrian trails and passive recreational uses, integrated with the adjacent employment development. The SWM facilities will accommodate stormwater runoff within their respective subcatchment areas.

Figure 3.2 illustrates the Draft Plan of Subdivision which implements the concept plan for the Subject Property. The Draft Plan of Subdivision also identifies potential temporary right-of-ways and existing easements (driveways), which are intended to accommodate an appropriate road network and access to the Subject Property until such time as the proposed roads and intersections have been constructed on adjacent lands, where required. These temporary right-of-ways have been accommodated to facilitate the development of the Subject Property in the short-term, as the timing of development on the adjacent lands, is unknown and may not coincide with the timing of development on the Subject Property. These temporary right-of-ways are accommodated at the intersection of Avenue Two and the Burnhamthorpe Road Extension, and the intersection of Avenue Three and Avenue One. Furthermore, the Draft Plan of

Subdivision identifies a temporary cul-de-sac on Avenue One, which is intended to cross Reach 14W-22, at such time as the lands to the west of the Subject Property are developed.

The Planning Rationale Report, May 2011, prepared by WSP (formerly MMM Group Limited), concludes that the Draft Plan of Subdivision represents good and sound community planning and conforms to and implements the goals, objectives and policies of the Provincial Policy Statement, the Growth Plan for the Greater Golden Horseshoe, the Regional Official Plan, and the NOWSP.

3.2 Trail Planning

The NOWSP (S. 8.5.5.10) states that: “An extensive system of recreational trails will be developed related to the Natural Heritage and Open Space System as well as along certain public road rights of way. A conceptual major trail system which will form the basis for the development of this more extensive system is identified on Figure NOW 4. However, any proposed trail development within the Natural Heritage and Open Space System shall be subject to further study as part of the Implementation Strategy to the satisfaction of the Town, in consultation with the Region and CH. The system may be refined through the preparation of an EIR in accordance with the provisions of Section 8.8.3 a) of this Plan.”

The NOWSP, Figure NOW 4 conceptually identifies a Major Trail System along the Burnhamthorpe Road Extension, west of Bronte Road, extending to Tremaine Road, in addition to a Major Trail System within the NHS, along the main stream corridor (Reach 14W-16 and Reach 14W-12) which traverses the Subject Property. The Town has prepared the North Oakville Trails Plan, May 21, 2013 which provides more detailed guidance for trail planning in North Oakville. In addition to the Major Trail System identified in the NOWSP, the North Oakville Trails Plan (May 21, 2013) also identifies a Major Trail along Reach 14W-11A on the Subject Property and around the Core Preserve Area associated with Fourteen Mile Creek and the Zenon Forest. Figure 3.3 illustrates the conceptual trail network as identified in the NOSWP and North Oakville Trails Plan, 2013 in relation to the 407 West Employment Area Concept Plan.

Section 8.4.7.3 of the NOWSP notes that one of the potential permitted uses in the NHS is:

iv) Trails, interpretative displays or signage or other similar passive recreation uses consistent with the purpose of the applicable designation and provided that:

- *for lands in the Linkage Preserve Area designation on Figure NOW 3, such uses shall generally be located in the Linkage Preserve Area, but adjacent to the boundary of the linkage;*
- *trails shall be permitted within the setback from the edge of the Sixteen Mile Creek Valley, and may be permitted within the valley subject to the review of their impact on any environmentally sensitive features;*
- *trails in stream corridors other than the Sixteen Mile Creek shall be permitted adjacent to the valley in the buffer; and,*
- *trails in the NHS Area designation be designed and located to minimize any impact on the natural environment.*

Section 6.3.5.2 of the NOCSS states that:

“Recreational trails for pedestrian and bicycle use will require special consideration and evaluation when planning their location within the NHS. A designated trail system associated with the NHS will be the best

strategy to discourage informal trail creation (i.e., trail blazing) for the public wishing to gain access to the NHS.

The following should be considered when planning the location of future trail systems:

- *Trails should cross the NHS (cores, linkages and stream corridors) within existing and proposed road crossings;*
- *Locations where roads are flanking core areas, trails should be substituted for sidewalks provided winter maintenance is feasible;*
- *Where trail systems are proposed to cross the NHS at locations other than where a road crossing is proposed, an impact assessment will be required to ensure no negative impacts to the NHS (i.e., species migration, impacts to drainage);*
- *Trail systems requiring winter maintenance will need to be located outside the NHS to minimize disturbance (i.e., ploughing, sand and salt); and*
- *Trail systems are not permitted in stream valleys.*

The North Oakville Trails Plan (May 21, 2013) identifies the following trail facilities and their associated standards:

Cycling Facilities

The Cycling and Trails Network is shown in Figure 3.3. Bicycles are designated as a vehicle under the *Highway Traffic Act* (HTA) and as such are required to obey all of the same rules and regulations as automobiles when being operated on a public roadway. The cycling routes proposed as part of the Town's North Oakville Trails Plan (May 21, 2013) network comprise several facility types, each with its own set of minimum design parameters. These are generally consistent with the Ministry of Transportation (MTO) and the Transportation Association of Canada (TAC) guidelines for the design of on-road facilities and standards for signing the on-road cycling system.

The cycling component of the Town's North Oakville Trails Plan (May 21, 2013) network for the 407 West Employment Area consists of multi-use trails and signed bike routes. For roadways labelled as Regional Bicycle Facility in the North Oakville Trails Plan (May 21, 2013), the type of bicycle facility will need to be determined by the Region; however, the following has been assumed for the boundary Regional roadways based on both the ATMP and the North Oakville Trails Plan (May 21, 2013):

- A 3.0 metre asphalt multi-use trail in the boulevard on Bronte Road between Dundas Street and Avenue One;
- A 3.0 metre asphalt multi-use trail in the boulevard on Dundas Street; and,
- A signed bicycle route on Tremaine Road.

Within the Subject Property and adjacent lands within the NOWSP area, all bicycle facilities are proposed to be on-road signed bicycle routes.

The purpose of designating a signed only bicycle route is to promote a road for cycling because it is deemed to be well suited for cycling; it may provide an important connection between destinations, or it is a preferred route identified by cyclists. In the case of signed on-road bicycle routes, the travel lane is shared

by motorists and cyclists. These are roads where traffic volumes and vehicle speeds are relatively low. Under these conditions, cyclists can share the road with motor vehicles and there is no need to create a designated space for cyclists. Bicycle route marker signs located at intersections and at regular intervals aid users with wayfinding.

On-road signed bicycle routes are proposed along Burnhamthorpe Road between Bronte Road and Tremaine Road, and along all the Avenues within the 407 West Employment Area. These proposed on-road bicycle routes are to be accommodated within the Town's Avenue/Transit Corridor (22.0m ROW) – Employment Area. The proposed bicycle facilities provide connections to bike lanes along Burnhamthorpe Road, east of Bronte Road, and along Colonel William Parkway, south of Dundas Street. The proposed on-road signed bicycle routes within the Subject Property and adjacent lands of the 407 West Employment Area also connect to planned bicycle facilities on the boundary Regional boundary roads.

It is anticipated that bicycle facilities crossing the Regional boundary roads will be provided at signalized intersections, and where applicable, these crossings are to be designed and implemented in accordance with recommendations of the Town's Active Transportation Master Plan.

Major Trails

The development proposal outlines the proposed Natural Heritage and Open Space System based on the Town's North Oakville Trails Plan and NOWSP Transportation Plan. The central open space system and adjacent SWM facilities will accommodate pedestrian trails and passive recreational uses, integrated with the adjacent employment development. As shown in Figure 3.3 Major Trails are proposed around the Zenon Woodlot/Core area, located east to the Subject Property, as well as, along the west side of the main stream corridor (Reach 14W-16 and Reach 14W-12) which traverses the Subject Property from Dundas Street West to the northwest corner of the 407 West Employment Area.

Major Trails are off-road, soft surface pathways used primarily by pedestrians, although cycling is not restricted. Major trails will be typically 2.1 – 2.4 metres wide, with a compacted limestone screenings surface, and asphalt paving on slopes greater than 5%. Where possible, trail design/layout shall promote the greatest level of accessibility possible. Signage should be provided for recreational cyclists and pedestrians. Major trails within the NHS will not receive regular winter maintenance. Mid-block crossings are to be minimized, with roadway crossings occurring where possible at signalized or stop-controlled intersections.

As identified in the North Oakville Trails Plan, Figure 3 provides an illustration of a typical Major Trail cross-section (Type A) which is supported by the trail design guidelines outlined in Section 3.5.

Figures 5.7 and 5.8 illustrates the proposed Major Trails in relation to the NHS and natural heritage features. The on-road trails will follow the proposed road network thereby minimizing the number of watercourse crossings. The impact assessment of these on-road trail crossings will be included in the impact assessment for said road crossings.

The Major Trails have principally been located along the margins of the NHS to minimize encroachments to the actual natural features and maintain the alignment within the existing disturbed areas (i.e., agricultural fields). As indicated, where the trail system crosses through the NHS other than at a road crossing, an impact assessment will be required. Within the 407 West Employment Area, these occurrences are limited

to the proposed Major Trails along the Highway 407 corridor and there is the potential that an impact assessment(s) will be required for the majority of these areas to comply with this requirement. Within the Subject Property, the greater part of the Major Trail system does not cross through the NHS, but instead follows the margins. The exception to this is a section of trail along the Highway 407 corridor within the realigned portion of Reach 14W-11A, as this reach will be realigned there is no existing feature (or setback) present in the proposed trail location and as such, the design of the realigned channel will take into account the trail through this section. The siting of the trails within the NHS of the Subject Property will be undertaken once the stream corridor limits have been agreed upon. This will be undertaken in consultation with the MNRF, and CH as stipulated in NOCSS (Section 6.3.5.2).


The potential impacts (and permitting) for the remaining Major Trails proposed in the EIR lands will be assessed by their respective property owners.

The NOWSP permits trails within stream corridors, other than Sixteen Mile Creek, which are adjacent to the valley and located within the buffer. Trails in the NHS designation are to be designed and located to minimize any impact on the natural environment. In addition to the trail design guidance in the North Oakville Trails Plan, the following provides general guidance where the proposed trail system interfaces with the NHS:

- The trail will only cross the stream corridors along a proposed road crossing;
- The trail will be aligned through the NHS to avoid sensitive natural features and habitats;
- Where trails are proposed in the vicinity of a watercourse, they will be located outside of the valleys in the stream corridor setbacks;
- Walking access should be restricted to a properly sited and established trail;
- The trail alignment through the NHS should be delineated in the field with specific consideration to vegetation cover, slope, and drainage, taking advantage of openings and avoiding sensitive natural features and habitats;
- Boardwalks or viewpoints adjacent to sensitive features or SWM facilities may be appropriate;
- The trail should avoid areas where there are trees that have a tendency to drop excessive debris, to droop or to break under heavy snow loads or wind;
- Where vegetation is dense, access can be provided by thinning the lower branches, but maintaining the stem and root structures;
- If there are sloping areas, the trails should not result in a concentration of surface runoff down the slope in order to avoid erosion. Trails along steep sloping areas should be avoided;
- The trails should not be lit where they traverse natural communities. Where walkways/trails approach or skirt natural areas, they could be lit strategically, and of a parks scale with fixtures low to the ground (e.g., bollard height). The lighting should be focused on the trail. There should be little or no sky-lighting effect due to the environment-friendly design (cut-off refractors);
- Fencing should be avoided around the trails. If bolstering of the trail alignment is required, it should occur through plantings of appropriate native indigenous vegetation, comprising species that produce dense growth and 'unfriendly' characteristics, such as thorns. As well, the plantings should be designed and implemented to promote natural succession, help control invasive species, provide for wildlife habitat and be native to the area;
- Over the long term, the establishment of unauthorized trails that may develop through excursions from the built trails, should be addressed through dense plantings and physical barriers, if necessary;

- Prior to construction, the limits of construction activity need to be established. Rutting and compaction of the terrain and scarring of the vegetation beyond the limits of construction should not occur;
- During construction, the smallest size of equipment should be used (specialty narrow width loader/backhoe) to avoid compaction and damage of the existing root zone; and,
- A regular program of inspection and maintenance should be detailed.

Jan 26, 2017 - 8:45am
14W-2222-001.PDF - 407 West Employment Area Mapping/DRAFT PLAN/70800A/Para 3.1 - Area Concept Plan-70810.dwg - Job1147



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

407 West Employment Area Concept Plan

LEGEND		Area	
		Hectares	Acres
Land use on Lazy Pat Property	Employment (Specific land use to be determined)	94.1	233
	Mixed Employment (Service/Office)	6.1	15
	Light Employment	16.4	41
	General Employment	17.3	42
	Park	0.3	1
	Open Space	72.7	180
	Stormwater Management	15.6	38
	Planned 407 Transitway	12.3	30
	Roads	16.2	40
		251.0 ha	620 ac

- 407 West Employment Area
- Subject Lands

- Notes:
- For the purposes of our analysis we have made land use, natural heritage and storm water sizing and location assumptions for the entire 407 West Employment Area
 - Right-of-way requirements for future 407 Transitway to be determined
 - The Natural Heritage System on lands owned by others is conceptual, as shown in the North Oakville West Secondary Plan, and is subject to further study.

Scale
1 : 7500

Client



Prepared by



Date

June 19, 2017

Project No.


09M-00013-01
(1409222-001)

Aerial Photo

© DigitalGlobe 2010, Google 2009

Figure 3.1

Jun 20, 2017 - 14:56pm
I:\Projects\2009\14-09222\001\POI - 407 West Employment Area\mapinfo\DRIFT PLAN\70820\Figure 3.3 - Trails-Plan-170820.dwg - Job 1147



Environmental Implementation
Report / Functional Servicing Study
for 14 Mile Creek West and the
Lazy Pat Farm Property

407 West Employment
Area Concept Plan
Trails Plan (Conceptual)

LEGEND

- Major Trails
- Multi-Use Trail (Off-Road / In Boulevard)
- Regional Bicycle Facility
- Signed Bicycle Route (On-Road)
- Park
- Open Space
- Stormwater Management
- Planned 407 Transitway
- Roads
- 407 West Employment Area
- Subject Lands

- Notes:
- For the purposes of our analysis we have made land use, natural heritage and storm water sizing and location assumptions for the entire 407 West Employment Area
 - Right-of-way requirements for future 407 Transitway to be determined
 - The Natural Heritage System on lands owned by others is conceptual, as shown in the North Oakville West Secondary Plan, and is subject to further study.

Scale
1 : 7500



Date
June 19, 2017

Project No.
09M-00013-01
(1409222-001)

Aerial Photo
© DigitalGlobe 2010, Google 2009

Figure 3.3

4.0 Hydrogeology and Geology



4.0 Hydrogeology and Geology

4.1 Introduction

The Subject Property is approximately 75.1 ha in area, of which approximately 53.8 hectares is proposed for development. The ground at the Subject Property generally slopes from the northwest to the southeast from a topographic high of about 160 masl at the north boundary to approximately 142 masl in the main watercourse (FM1001/Reach 14W-12) where it passes under Dundas Street West. In general, the lands at the Subject Property are gently undulated, with elevation changes between the crests of the rises down to the watercourses of the order of 5 to 8 m.

The property is bordered by the following existing land uses as illustrated on Figure 4.1:

- Agricultural lands to the southwest, with Bronte Creek located approximately 1 km to the southwest of the western property line;
- Highway 407 and agricultural/forested lands to the northwest;
- An industrial facility (General Electric) and vacant/agricultural and forested lands to the northeast; and,
- Residential development to the southeast.

A quarry owned by Hanson Brick Ltd. is located approximately 1 km to the northwest of the Subject Property. The quarry is located to the north of Highway 407 and west of Tremaine Road.

Three subwatersheds cross the Subject Property, identified as subwatersheds FM1109, FM1001 and FM1102 in the NOCSS. Subwatershed FM1001 (also identified as the West Branch of Fourteen Mile Creek) drains the majority (approximately 81%) of the Subject Property (approximately 60.4 ha of the total 75.1 ha site area), contains three watercourse (Reach 14W-13, Reach 14W-14 and Reach 14W-16) and a small dug pond and Farm Pond (Reach 14W-14A), all of which eventually converge and exit the Subject Property at the southeast through a single main channel (Reach 14W-12).

Subwatershed FM1109 (Central Branch of Fourteen Mile Creek, Reach 14W-11 and Reach 14W-11A) drains about 10.0 ha of the Subject Property area along the eastern and north-eastern portions of the Subject Property, and the watercourse flows across the northeast corner of the property.

The smallest of the three subwatersheds, FM1102 drains about 4.7 ha of the total property area at the extreme southwest corner. There is no defined channel through the Subject Property within this subwatershed but two shallow “swales” were observed in a moist to standing water condition in early May 2009 and in a dry condition in April 2010. No evidence of flowing water was observed in this subwatershed during the course of our investigation. A small pond is located on a farm property that is not part of the Subject Property and water from this pond drains under Dundas Street West through a culvert located to the west.

The present land use over the tablelands on the Subject Property and adjoining lands is primarily agricultural. The farm in the past had been used to raise pigs but this use was discontinued more than 20 years ago. Within the watercourse valleys vegetation is generally comprised of tall grasses, weeds and shrubs.

The future development on the Subject Property will be fully serviced with municipal water and sewers. The development lands are designated for employment uses and will consist of industrial and commercial uses. Two SMW Facilities will be constructed on the Subject Property, which will treat, approximately 56% (Pond 3) and 26% (Pond 2) of the total property area following development. The remaining area is green space.

A hydrogeological evaluation of the Subject Property was carried out by WSP (formerly MMM Group) according to the Town ToR for EIR and FSS carried out in North Oakville. The stated purpose of the EIR is to characterize and analyze the natural heritage features and functions, and to determine and address the potential impacts of a proposed development application, including servicing requirements on the natural heritage system. The ToR further indicate that the EIR be carried out on a subwatershed basis and that only one EIR will be permitted per subwatershed even if multiple property owners (developers) were proposing development within the same subwatershed. The expectation was that investigative works were not only to be carried out directly on the Subject Property, but also within the subwatershed catchment as a whole to characterize the entire natural heritage system.

The hydrogeological evaluation included interpreting regional geology and site-specific geology and hydrogeology, based on fieldwork carried out by WSP at both on-site and off-site locations between May 2009 and April 2017. A detailed breakdown of fieldwork activities is provided in Section 4.1.2.

4.1.1 Subwatersheds

The Subject Property is located within three subwatershed catchments identified in the NOCSS (Figure 4.1). The upper reaches of all three subwatersheds are defined by the crest of the Trafalgar Moraine that forms the topographic high ground to the northwest of the Subject Property. In Table 4.1 below, it is clear that the majority of the Subject Property are currently drained by the central subwatershed (FM1001) and that the Subject Property contains about 15% of the total overall area of this subwatershed. Conversely, the Subject Property only comprises about 3% of subwatershed FM1109, and about 11% of subwatershed FM1102. With further regard to FM1102, the small proportion (4.7 ha) of the Subject Property contained within this subwatershed also makes up only a very small proportion of the total area of the future employment lands to the west of the Subject Property. This hydrogeological investigation; therefore; focuses on subwatershed FM1001 although some discussion of subwatersheds FM1109 and FM1102 is provided.

Table 4.1 – Subwatershed Areas

Subwatershed	Subwatershed Area (ha)	Subwatershed Area within Subject Property (ha)	Proportion of Subwatershed within Subject Property (%)	Proportion of Subject Property within the Subwatershed (%)
FM1102	43.9	4.7	11%	6%
FM1001	395.3	60.4	15%	81%
FM1109	365.0	10.0	3%	13%
Subject Property		75.1		100%

4.1.1.1 Subwatershed FM1001

As discussed above, Subwatershed FM1001 is the main subwatershed found at the Subject Property, draining approximately 81% of the Subject Property. This subwatershed is identified as the West Branch of Fourteen Mile Creek, and in the study, area is comprised of a main channel (Reach 14W-16 and Reach 14W-12) with two smaller watercourse (Reach 14W-14 and Reach 14W-13) that all join on the Subject Property. The topography within the overall subwatershed slopes from northwest to southeast from a topographic high of about 185 masl at Number Two Sideroad to approximately 142 masl where the watercourse crosses under Dundas Street West. The land cover of the subwatershed area is mostly open or agricultural (90%), with about 8% of the total subwatershed area covered in forest (Figure 4.2). The remaining 2% area is considered impervious, comprised mainly of the Highway 407 pavement and the existing extent of the Hanson Brick quarry, which will expand over time as operations continue.

4.1.1.2 Subwatershed FM1109

Subwatershed 1109 is located east of Subwatershed FM1001 and this subwatershed is known as the Central Branch of Fourteen Mile Creek. This subwatershed drains a small portion of the Subject Property, primarily via a defined channel at the northeast corner (Reach 14W-11 and Reach 14W-11A) and through a swale, which drains a portion of the Subject Property near its east property line (Figure 4.2). The topographic relief of this entire subwatershed ranges from approximately 190 masl along the crest of the moraine to the northwest to about 150 masl along Dundas Street West. Approximately 23% of the overall subwatershed area is presently forested, 74% is interpreted as agricultural/open ground cover, and the remaining 3% is considered impervious (Highway 407 and the GE facility make up most of this).

4.1.1.3 Subwatershed FM1102

Subwatershed FM1102 is located to the west of Subwatershed FM1001 and is the smallest of three subwatersheds passing through the Subject Property. No defined channels were observed in this subwatershed on-site, other than two wide, gentle swales affected by agricultural activities (e.g., furrowing through cropping). These swales were found to contain pockets of stagnant/ponded water at the times of all site visits beginning from May 2009. The topography of this small subwatershed ranges from about 170 masl at the western limit of the subwatershed to about 152 masl along Dundas Street West. The current land use of the area is predominantly agricultural (90%) and forested (9%) with only a minor percentage (1%) of imperviousness.

4.1.2 Work Program

The work program for the hydrogeological investigation was designed to address the requirements outlined in the ToR, including:

- Review of background information pertinent to the subwatersheds, including areas beyond the Subject Property limits;
- Field investigations, including:
 - Site visits, initial site inspection and quarterly visits;
 - Drilling boreholes and installing monitoring wells. Streambed mini-piezometers and staff gauges were also installed at on-site locations;
 - Soil sampling and grain size analyses of selected samples;
 - Quarterly groundwater level monitoring, including “continuous” monitoring using data loggers at selected monitoring wells located at both on-site and off-site locations;
 - Estimating watercourse flows at the time of the quarterly site visits;
 - Groundwater and surface water sampling; and,
 - Single well hydraulic conductivity testing and shallow percolation testing.
- Assessing site conditions, including:
 - Characterizing the local geologic and hydrogeologic conditions;
 - Identifying groundwater discharge areas and evaluating surface water base-flows;
 - Establishing surface water-groundwater interactions;
 - Preparing pre-development and post-development water balance analyses at the Subject Property and the overall subwatersheds;
- Analyzing and assessing the potential impacts of the development; and,
- Providing recommendations for the mitigation of any potential impacts.

4.2 Regional Physiography and Geological Setting

4.2.1 Regional Geology and Hydrostratigraphy

The Subject Property and surrounding area are situated in the South Slope physiographic region identified by Chapman and Putnam (1984). The Trafalgar Moraine, a subtle topographic ridge that was formed during the retreat of the Lake Ontario ice lobe 12-13,000 years ago, extends from western Mississauga across the northern part of Oakville and is found to the north and west of the property marking the boundary between the South Slope and the Peel Plain physiographic region to the north. The till plain on which the subject property lies is comprised of reddish coloured Clay-Silt Halton Till which is locally derived from the underlying bedrock.

The underlying bedrock in the area is Upper Ordovician red Shale and interbedded Limestone of the Queenston Formation. It is encountered at shallow depth and is reported in the MOE water well records as red shale with limestone, at depths between 3 to 27 metres below ground surface (mbgs). It is exposed at

surface along the steep valley walls of Bronte Creek to the west, and is exposed at surface at the lower reach of the central watercourse (Reach 14W-12) passing through the Subject Property alongside Dundas Street West. On a regional basis the bedrock surface is interpreted to be dipping from the northwest to southeast, generally following the regionally topographic slope, mapped with a surface elevation of approximately 165 to 170 masl in the vicinity of the Trafalgar Moraine to approximately 145 to 150 masl along Dundas Street (Ontario Department of Mines, 1964).

An infilled bedrock valley is identified through interpretation of the water well record logging at wells located east of the subject property, generally below the watercourse draining FM1109 (Reach 14W-11 and Reach 14W-11A, Central Branch of Fourteen Mile Creek, (Figure 4.2)). Bedrock elevations in this “valley” are interpreted between 120 to 130 masl to the east and south of the Subject Property and buried sand and gravel deposits are logged between the surficial tills and the bedrock in this section (water well records are found in Appendix 4-1). Farther north, by Burnhamthorpe Road, the valley bottom elevations are interpreted at about 140 to 145 masl, and low permeability till and/or clay deposits are logged from surface to rock.

Drawing 4.1 (appended to this report) presents the hydrogeological cross-sections A-A', B-B' and C-C' identified on Figure 4.2. These cross-sections were prepared from geological information recorded in the MOE water well records, supplemented with borehole data from WSP investigations in 2009 and data from the Hanson Brick Quarry studies.

Figure 4.3 presents the interpreted bedrock and shallow (till) based groundwater contours. The bedrock contours are based on both water well records and on and off-site borehole data, while the shallow contours are based primarily on borehole monitoring data. On this figure, groundwater in the bedrock is seen to generally flow from northwest to southeast with deflections created by the Bronte Creek valley to the west, and the infilled bedrock valley to the east, which leads to a west to east bedrock groundwater flow at the Subject Property. The regional horizontal gradient within the bedrock is approximately 0.009, increasing locally to 0.013 to 0.015 where the flow is being deflected towards the infilled bedrock valley.

The shallow groundwater system is controlled by the topography of the land declining from roughly 180 masl at the upper limits of Watershed FM1001 (at Number 2 Sideroad) down to approximately 145 masl at the point where the main FM1001 channel passes under Dundas Street West. On a watershed basis, the horizontal gradients in the shallow system are on the order of 0.01 to the southeast. Further discussion on groundwater levels is provided in Section 4.3.2.3.

The Halton Till and the Queenston Shale are poor aquifers due to their fine-grained nature and low permeability and are capable of providing only limited quantities of groundwater to water wells. In terms of existing groundwater usage, within the jurisdiction of the CH, approximately 75% of all wells are completed into the bedrock, which indicates that the surficial overburden deposits of Halton Till are not a significant source of groundwater in the area (Singer et al, 2003). Most wells in the study area are completed into the bedrock, except for wells in the bedrock valley. Wells drilled into the bedrock valley, south of Highway 407, are completed in the buried sand and gravel deposits above the shale bedrock.

The bedrock in the area is also described as a poor aquifer due to poor pore space interconnections in the shale. The Queenston Formation shale does not fracture easily or dissolve, which limits its effective porosity. The upper 3 to 5 m of the bedrock is weathered, and is where most of the available yield is observed. The reported geometric mean averages of the specific capacity and Transmissivity for this formation are 1.5

l/min/m and 2.7 m²/day, respectively (Singer et al, 2003). The bedrock is therefore considered a poor aquifer with yield capacities barely enough to satisfy individual domestic water needs.

As reported in Singer et al (2003), 92% of all wells completed within the Queenston Shale (across Southern Ontario, not only Halton Region) are reported as providing “fresh” water. Salty water is reported at 5% of these wells and the remaining 3% of wells are reported with either mineralized or sulphurous water. Water quality from the shale is considered highly variable, ranging from good to poor. Water quality from 12 samples were presented in the Singer report, and indicated the water is hard (mean hardness of 472 mg/L), has high levels of sodium and chloride (averages of 88 and 123 mg/L respectively), and an average concentration for sulphate of 251 mg/L.

4.2.2 Topography and Drainage

The Subject Property and surrounding area has moderate relief (between 190 to 130 masl on a regional basis, 160 to 142 masl relief across the Subject Property) with the ground generally falling from the west-northwest to east-southeast. The area is referred to as part of the South Slope physiographic region by Chapman and Putnam (1984). The Trafalgar Moraine, a subtle topographic ridge that extends from western Mississauga across the northern part of Oakville, lies to the north and northwest of the property.

The local drainage network is generally oriented in a west-southwest to east-northeast direction. The Subject Property is predominantly drained by subwatershed FM1001, which has four channels (Reach 14W-12, Reach 14W-16, Reach 14W-13 and Reach 14W-14). Subwatersheds FM1109 and FM1102 drain the eastern portion and the extreme south-western corner of the Subject Property, respectively. These three subwatersheds are located in what can be described as a bevelled till plain with local relief provided by creek valleys, which are locally incised in the order of 5 to 10 m. Significant watercourses, such as Bronte Creek to the west are incised deeply into the underlying bedrock (bedrock exposed), with steep side slopes and relief in the order of 20 to 30 m relative to the table lands.

4.3 Hydrogeological Evaluation

4.3.1 On-Site and Off-Site Investigations

WSP carried out hydrogeological field investigations across the Subject Property and at off-site locations to the north and west of the Subject Property commencing in the late spring of 2009. Off-site field work was also carried out within subwatershed FM1001, the focus of this EIR.

WSP's initial hydrogeological site visit took place on May 5, 2009. During this visit, hydrogeologists from WSP staked out 12 on-site borehole locations (MMM-09-1 to MMM-09-12), installed 7 mini-piezometers (MP-01 to MP-07) within two of the sub-watercourse systems that cross the Subject Property (FM1001 and FM1109) and measured water levels at three of four monitoring wells MW-1 to MW-3 (MW-4 was reported by the farmer on the Subject Property to have been destroyed) installed on the Subject Property by Trow Associates Inc. (Trow, see Section 4.3.1.3). Estimates of stream flows and field parameters such as pH, temperature, electric conductivity and concentration of total dissolved solids were measured in the watercourses at each of the mini-piezometer locations. Monitoring wells associated with the Hanson Brick Quarry site to the northwest of the Subject Property were observed following this site visit during a drive by of the local area.

A total of 16 boreholes were drilled at 12 locations within the Subject Property to depths of between 2.3 and 16.6 mbgs (metres below ground surface) in June 2009 (MMM-09-01 to MMM-09-12). Eleven (11) additional boreholes were drilled at eight off-site locations in November 2009 to depths ranging from 3.6 to 15.6 mbgs. Off-site property access was obtained from the Diocese of Hamilton (MMM-09-13 to MMM-09-15) and from the local municipalities and the Region of Halton (MMM-09-16 to MMM-09-20) for drilling within the road allowances. Borehole and monitoring well locations are presented on Figure 4.3 and Figure 4.4.

Soil samples from the overburden were collected using continuous sampling techniques. At selected intervals, split spoon samples were obtained from the upper portion of the continuous sample intervals. The sampling technique was changed to bedrock coring upon auger refusal at borehole locations where a greater depth was required. Water levels in the boreholes on the completion of drilling were recorded and monitoring wells were installed at each borehole.

The monitoring wells were constructed with 51 mm diameter Schedule 40 PVC screen and riser, equipped with O-rings at the threaded joints. Screens were between 0.5 to 3.0 m in length and a sand pack was installed around the screen, extending 0.3 m above the top of the screen. A bentonite seal was placed from the top of the sand pack to about 0.3 m below grade. A protective lockable steel casing and 0.3 m of concrete at surface completed the installations. Seven of these monitoring locations were constructed as nested wells with both a shallow and deeper monitoring well to ascertain vertical groundwater gradients.

Borehole logs for all boreholes, including stratigraphic descriptions, sampling intervals and monitoring well details, are contained in Appendix 4-2. Grain size analysis results from these boreholes are presented in Appendix 4-3.

4.3.1.1 Supplemental Farm Pond Investigation

Additional monitoring wells and mini-piezometers were installed around the periphery of the large human-made Farm Pond (Reach 14W-14A) in July 2011 as part of an investigation to confirm if this Farm Pond was receiving groundwater. WSP staff installed a staff gauge within the Farm Pond and three mini-piezometers (MP-21, MP-22, and MP-23) at the edges of the Farm Pond on July 4, 2011. Three new monitoring wells (50 mm diameter PVC riser and screen) were constructed in mid-July 2011 by EXP Services Inc. on behalf of WSP at two locations along the west side of the Farm Pond and identified as MMM11-21, MMM11-22 (nested). These wells are located to the west and southwest of the Farm Pond (borehole logs are included in Appendix 4-2). Data loggers were installed at the staff gauge in early July 2011 and at the three new monitoring wells in late July 2011. A data logger had been installed at monitoring well MMM09-02 (located to the east of the Farm Pond) in March 2011 in anticipation of this supplemental study.

A drive-point mini-piezometer nest (MP-24) was installed near the upstream limit of the Farm Pond on October 22, 2013 at a location agreed to with CH's hydrogeologist at a site meeting on October 10, 2013. This mini-piezometer nest is located to the northwest of a topographic rise that separates the Farm Pond from Reach 14W-12A, with the edge of the Farm Pond, as defined by the average Farm Pond water level elevation of 148.7 masl, situated approximately 65 m southeast of the mini-piezometer nest. Two mini-piezometers were installed, the shallower piezometer was screened between 0.31 and 0.44 mbgs, and the

deeper piezometer was screened between 1.19 and 1.28 mbgs. Data loggers were installed in both piezometers¹.

Additionally, four boreholes drilled by EXP Services Inc. along the main Reach channel (Reach 14W-12) for a slope stability investigation included piezometers (EXP report dated November 18, 2011 and entitled "*Slope Stability Analysis Report, 14 Mile Creek, Pigott Farm Land, Oakville, Ontario*") and these piezometers were also included in the monitoring for this study (the borehole logs are included in Appendix 4-2).

4.3.1.2 Quarterly Monitoring

Quarterly site visits were scheduled to monitor the Subject Property and off-site monitoring locations over spring, summer, fall and winter conditions. During such visits, manual water level readings were taken at the monitoring wells and mini-piezometers, data loggers were downloaded and when there was flowing water present (and not frozen), flow estimates were obtained in the watercourses at staked locations identified as FMP-1 to FMP-6. These site visits were ideally scheduled to follow periods of dry weather (greater than 3 to 5 days following a rain event), although this was not always possible. Flow measurements were supplemented with stream water levels at staff gauges locations SG-1 and SG-2.

Additional investigative work carried out by WSP at the time of the regularly scheduled monitoring visits included water quality sampling and hydraulic conductivity testing at selected monitors.

4.3.1.3 Investigations by Others

An earlier study was carried out on the Subject Property and additional lands to the north of Highway 407 in 2001, and three of the four monitoring wells installed from this program were still available for use from 2009 to present. This earlier field work was carried out on behalf of Beutel Goodman Real Estate Group and was undertaken at the property by Trow to document the geotechnical and environmental conditions at these lands. The report examined two parcels of land separated by Highway 407 and identified as Parcels A and B. Parcel A coincides with the Subject Property currently under consideration for development. Parcel B was located north of Highway 407 extending north to Burnhamthorpe Road, with an area of about 23 ha. No work was carried out by WSP for this work program on the lands identified as Parcel B in the 2001 Trow reports.

Trow's prior on-site investigations consisted of the following:

- Drilled forty-five (45) geotechnical boreholes (MW-1 through MW-4, and BH-1 through BH-41) to depths ranging between 1.6 to 6.1 m below grade. Four groundwater monitoring wells were installed at the locations identified as MW-1 to MW-4 (MW-4 could not be located in 2009 and was reported by the previous owner as destroyed years ago). Shale bedrock was reported at 16 of the 45 borehole locations, generally those boreholes located along the south and west portions of Parcel A (the Subject Property under current investigation);
- Excavated forty-eight (48) shallow test pits to depths ranging 1.0 to 2.3 m. None of these test pits was reported having encountered the shale bedrock;

¹ The data logger at MP-24S, a very shallow monitor (0.44 m deep), was removed for the winter on December 16, 2013 to prevent damage to the unit from freezing. The data logger was re-installed at MP-24S on April 30, 2014 for the spring to fall seasons.

- One aspect of the Trow work plan was to investigate the potential for contamination near three USTs (Underground Storage Tanks) that had contained pig manure and one UST used for fuel storage. Soil and groundwater samples from the boreholes, monitoring wells and private wells located on the property were submitted for analysis and all met the relevant criteria of the time for the proposed commercial/industrial land use with full municipal servicing.

Copies of the available borehole logs, test pit logs and location plan from the Trow report are also included in Appendix 4-2.

Several hydrogeological investigations were carried out by Golder Associates Ltd. (Golder) on behalf of Hanson Brick in support of their Tremaine Quarry, located to the northwest of the Subject Property. Information from these investigations relevant to the hydrogeological interpretation of the Subject Property was examined. Copies of these reports, including annual monitoring reports up to November 2009 were obtained from those on file at the Regional Municipality of Halton.

The off-site field investigation programs carried out for Hanson Brick by Golder since 2002 consisted of the following:

- Construction of 11 on-site monitoring well nests (MW-1 to MW-11), with a minimum of a shallow monitor completed in the overburden till, and a deep monitor screened deep within the shale bedrock. Six nest locations also include a monitor screened within the upper shale, and 4 nest locations include a monitor screened across the till/shale bedrock interface;
- Construction of three off-site 150 mm diameter drilled test wells, located within the road allowances for Number 1 Side Road/Burnhamthorpe Road West and Tremaine Road. These wells were drilled and tested as part of a Class Environmental Assessment to determine the feasibility of providing a source of water communal water supply system for local residents;
- Static water level monitoring collected on a quarterly basis between 2002 and 2008, and monthly thereafter. The 2008 water level monitoring program included 11 private wells and monitoring of the 11 on-site monitoring well nests and the 3 test wells located on the road allowances. Most of the on-site monitors and all of the 11 private wells were equipped with data-loggers;
- In-situ hydraulic conductivity testing of the overburden and bedrock was carried out at most of the monitors at the 11 monitoring well nests, with the exception of two of the shallow overburden wells;
- Groundwater sampling at the 11 on-site monitoring well nests and at 10 private wells.

WSP staff did not access nor monitor any of the Hanson Brick wells during this study and used the publicly accessible reported data for those wells.

4.3.2 Site Geology

WSP's drilling programs confirm the surficial soils encountered within the Subject Property and the EIR Sub-catchment Study Area (FM1001) are comprised of clay-rich Halton Till, underlain by Queenston Shale.

Topsoil generally ranged from 0.1 to 0.3 m thickness at most borehole locations. Thicker topsoil was noted at on-site boreholes MMM-09-4 and MMM-09-10, on the order of 0.5 to 0.6 m thickness. Both of these locations are near to existing watercourses (e.g., valley bottoms).

Generally, the soils at ground surface below the topsoil layer were classified as a brown to reddish brown stiff to very hard Clayey Silt Till, some sand, occasionally classified as Sandy Silt Till, with shale fragments. At six of the borehole locations², thin deposits of differing soils were logged between the topsoil and till. These deposits were generally similar in composition as the underlying till (e.g., Clayey Silt, to Silt with some sand and with till-like appearance, extending to depths between 0.5 to 1.4 m below grade) and are possibly representative of soils disturbed by farming activities. At MMM-09-4, located next to Reach 14W-11 in sub-watershed FM1109, a deposit of Silty Sand to Sandy Silt (to 1.4 m depth) overlays the till.

Fracturing within the till was evident at most boreholes, with the shallower depths being highly fractured and weathered, and with fracture frequency noted to decrease with depth. Fractures were observed up to extend downward to between 4 to 6 m depth from the logging of the soil samples. Fractures near surface were observed to have a greyish white infilling of a Silt-Clay composition, or were identifiable through rusty to black oxidation staining.

The till deposits were logged to the underlying shale bedrock at the boreholes where the bedrock, or weathered bedrock was encountered or assumed through auger refusal. At many of the boreholes, the transition from shale/weathered shale to till was quite gradual.

The geological stratigraphy at the off-site drilling locations (MMM-09-13 to MMM-09-20) was similar though as locations progressed northward and the ground elevation increased the shale bedrock was less likely to be encountered.

The shale bedrock was identified as red Queenston Shale, with zones of green banding or green inclusions visible within the cores. The upper surface of the bedrock was weathered, with the weathered depth of the shale bedrock at the on-site boreholes generally extending beyond the lower completion depths of the boreholes. At three locations, the weathered depth of shale was logged to between 0.6 to 1.7 m from the top of the bedrock surface³. At MMM-09-15D (off-site location) the shale bedrock was still identified as weathered to 12.3 m depth (bottom of hole), with a highly weathered zone at approximately 5 to 6 m depth reported at this location. The RQD (Rock Quality Designation) of the shale bedrock was generally found to range from 29% at (poor rock mass quality) to 89% (good rock mass quality).

At the Subject Property, the surface of the bedrock was noted to decline in elevation from the southwest to the north-northeast⁴. Bedrock along the western property line was encountered at approximately 150 masl

² MMM-09-2 to MMM-09-5 inclusive, MMM-09-9, and MMM-09-12

³ MMM-09-1 (1.5 m), MMM-09-6 (1.7 m), and MMM-09-10 (0.6 m)

⁴ This includes information from the borehole logs prepared by Trow in their 2001 work on the property.

elevation. Towards the southeast corner of the Subject Property, where the main watercourse exits the property and passes under Dundas Street West, the bedrock surface is encountered at around 145 masl, and is in fact exposed at surface within the main stream channel alongside Dundas Street. The shale bedrock is located close to the watercourse channel bottoms up to the west-central parts of the Subject Property, being identified within 0.8 m of the channel at MMM-09-10, and approximately 1.6 m from the channel bottom in the vicinity of MMM-09-9 and MP-07.

At the northeast corner of the Subject Property, the bedrock was not encountered at either MMM-09-4 (borehole terminated at 146.3 masl) or at MMM-09-5D (borehole terminated at 142.8 masl). These on-site boreholes are the ones located in closest proximity to the buried bedrock valley identified in mapping and water well records.

4.3.2.1 Grain Size Analyses

Following installation of MMM-09-1 to MMM-09-20 monitoring wells, ten soil samples were submitted to Thurber Engineering Ltd. (Thurber) for a grain size analyses. The results of these grain size analyses were reviewed and used to provide estimates of hydraulic conductivity and soil classification for use in the water balance analysis. The grain size curves are found in Appendix 4-3.

Table 4.2 presents the location and depth of soil samples that were tested for grain size distribution and the estimated hydraulic conductivity. The estimates of hydraulic conductivity presented in Table 4.2 were obtained based on grain size results using the Hazen approximation:

$$K = 0.01 \times C d_{10}^2 \text{ (m/sec)}$$

Where:

K = bulk hydraulic conductivity (m/sec);

d_{10} = grain size at which point 10% of the soil passes the sieve (mm); and

C = a constant generally set at 1 for these units.

Table 4.2 – Hazen Estimates of Hydraulic Conductivity

BH ID	Sample ID	Depth (mbgs)	Soil Description	d ₁₀ (mm)	Hazen K ~0.01 x d ₁₀ ² (m/sec)
MMM-09-01D	S2	1.5 – 1.7	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-05D	S3	2.7 – 2.8	Clayey Sandy Silt (TILL)	<0.001	< 1.0X10 ⁻⁸
MMM-09-08	S1	0.9 – 1.1	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-09	S1	1.0 – 1.1	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-11	S1	1.0 – 1.2	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-12	S3	2.5 – 2.7	Clayey Silt (TILL), trace sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-13	S1	0 – 1.2	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-17	S4	5.5 – 5.6	Sandy Silt (TILL), some clay	<0.001	< 1.0X10 ⁻⁸
MMM-09-18D	S1	0.9 – 1.2	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸
MMM-09-19D	S4	3.7 – 3.9	Clayey Silt (TILL), some sand	<0.001	< 1.0X10 ⁻⁸

From Table 4.2, the Till deposits are estimated by the Hazen approximation to have hydraulic conductivities less than 1x10⁻⁸ m/sec⁵. These are reasonable estimates for unweathered till soils, but will underestimate the apparent (or bulk) permeability of the surficial zone for these soils. The bulk hydraulic conductivities for the shallow soils are expected to be greater as the preferential horizontal movement of water will be through the fractures found in the upper, weathered zones of these soils, and alongside creek valleys where erosion of the original deposit also provides some additional fracturing caused by stress relief.

Table 4.3 – Tri-Linear Soil Classification

BH/SA	Description	Percent			Soil Classification
		Sand	Silt	Clay	
MMM-09-01D	Clayey Silt (TILL), some sand	26	45	28	Clay Loam
MMM-09-05D	Clayey Sandy Silt (TILL)	29	42	28	Clay Loam
MMM-09-08	Clayey Silt (TILL), some sand	26	43	31	Clay Loam
MMM-09-09	Clayey Silt (TILL), some sand	22	52	26	Silty Loam
MMM-09-11	Clayey Silt (TILL), some sand	27	44	29	Clay Loam
MMM-09-12	Clayey Silt (TILL), trace sand	12	60	28	Silty Clay Loam
MMM-09-13	Clayey Silt (TILL), some sand	27	44	29	Clay Loam
MMM-09-17	Sandy Silt (TILL), some clay	28	52	20	Silty Loam
MMM-09-18D	Clayey Silt (TILL), some sand	24	45	31	Clay Loam
MMM-09-19D	Clayey Silt (TILL), some sand	29	47	23	Medium Loam

Note:

Percentages expressed in the table above are based on the proportions of Clay, Silt and Sand sized particles, excluding Gravel content

⁵ Hazen estimates of hydraulic conductivity were not used to classify the soil type for use in the water balance calculations.

The tri-linear soil classifications obtained through the grain size analyses were used to derive the soil classification for estimating infiltration input into the water balance analysis (along with published soils mapping of the site (see Section 4.4.3.1). The percentage composition of soils was categorized as percentages of sand, silt, and clay and compared against classifications in a tri-linear soil classification chart. The results are presented on Table 4.3. The predominant soils found at shallow depth are Clayey Silt Till (and typically classified as Clay Loam). The tri-linear soil classifications range between Silty Clay to Medium Loams. On average, Clay Loam was considered representative of the soils found near surface for input into the water balance.

4.3.2.2 In-Situ Permeability Testing

Hydraulic conductivity testing was carried out at nine WSP monitoring well locations in December 2009, January 2010 and October 2010⁶ to provide estimates of the in situ hydraulic conductivity of the deposits across the Subject Property and the FM1001 subwatershed. The monitoring well locations were selected on the basis of providing data from locations across the subwatershed, and for representative soil types, and at both shallow and deeper depths.

At six of the nine tested monitors, the hydraulic conductivity was anticipated to be quite low, and recovery was monitored using data loggers installed at those locations (see Section 4.3.2.3 for details of the loggers)⁷. Manual measurements were taken at MMM-09-9 and both wells at the two monitors at location MMM-09-10 as these wells recovered quickly (less than 10 minutes each).

The hydraulic conductivity testing was generally carried out by extracting a volume of water in the monitoring well using either a polyethylene bailer or dedicated *Watterra* tubing and foot-valves. In the case of testing carried out at MMM-09-10, a slug with a known volume was used to displace the water and a falling and rising head test was carried out. In all cases, the recovery of the water levels in the well was measured over time until they had recovered to within approximately 80% of the original water level.

The recovery data was analysed with Aquifer Test Pro (Version 4.2) using the Hvorslev (1951) approach and the results of the hydraulic conductivity testing are presented in Table 4.4⁸. These values are considered representative of horizontal hydraulic conductivity in the immediate vicinity of the well. It is anticipated that the vertical hydraulic conductivities with depth will be an order of magnitude lower than these values.

The measured hydraulic conductivities within the shallow zones of the Till deposits (i.e., 1.5 to 4.5 m depth) were generally one to two orders of magnitude greater than the conductivities estimated using the Hazen approximation from grain size analyses for the Till (see Section 4.3.2.1). The horizontal hydraulic

⁶ MMM-09-04, MMM-09-09, MMM-09-15S, and MMM-09-17 (December 2009); MMM-09-19S, MMM-09-19D, and MMM-09-20 (January 2010); MMM-09-10S and MMM-09-10D (October 2010).

⁷ Rising head recovery monitoring using data loggers at these locations indicated that recovery of the water levels in these wells over several hours (MMM-09-04, MMM-09-15S) to several days (MMM-09-17, MMM-09-19S, MMM-09-20). The recovery at monitor MMM-09-19D continued on the order of one month.

⁸ The Hvorslev analyses are presented in Appendix 4-4.

conductivities in the weathered shale were measured on the order of 10^{-6} m/sec, and are expected to decrease with depth as the effects of weathering and fracturing becomes less pronounced⁹.

Table 4.4 – In-Situ Permeability Testing Summary

Monitoring Well	Screen Interval (mbgs)	Description	Hydraulic Conductivity (m/sec)
MMM-09-09	1.8 – 2.3	Clayey Silt Till	9.0×10^{-6}
MMM-09-10S	1.6 – 2.1	Weathered Shale	6.4×10^{-6}
MMM-09-10D	6.2 – 7.7	Weathered Shale	4.4×10^{-6}
MMM-09-15S	1.5 – 4.4	Shaley Till to Weathered Shale	1.8×10^{-7}
MMM-09-04	3.0 – 6.0	Sandy Silt to Silty Sand Till, Clayey Silt Till and Sandy Silt Till	4.4×10^{-9}
MMM-09-17	2.9 – 5.9	Clayey Silt Till and Sandy Silt Till	3.9×10^{-9}
MMM-09-19S	3.2 – 5.9	Clayey Silt Till	4.8×10^{-10}
MMM-09-20	4.2 – 7.2	Clayey Silt Till	3.0×10^{-9}
MMM-09-19D	13.6 – 15.1	Clayey Silt Till	9.8×10^{-11}

Notes:

The calculated horizontal hydraulic conductivity may be underestimated due to effects such as smearing of the borehole wall during drilling. This can reduce the ability of water to be transmitted across the perimeter of the borehole and so may result an underestimate of the hydraulic conductivity.

The geometric mean horizontal hydraulic conductivity of the upper till/weathered shale is calculated at about 3×10^{-6} m/sec (using the first four results in the table above).

The geometric mean horizontal hydraulic conductivity for the deeper till deposits is calculated to range from 3.7×10^{-9} m/sec (MMM-09-04, MMM-09-17, and MMM-09-20) to 2.2×10^{-10} m/sec (data from MMM-09-19 nest only). Vertical hydraulic conductivity is further assumed to be $1/10^{\text{th}}$ the horizontal hydraulic conductivity.

4.3.2.2.1 Percolation Testing

Two percolation tests were performed at locations identified as PT-1 and PT-2 on October 18, 2010. Percolation Test PT-1 was located nearby to the monitoring well nest at MMM-09-10 and PT-2 was carried out in the vicinity to mini-piezometer location MP-04.

The percolation test holes were between 160 to 300 mm diameters and were dug out to a minimum depth of 0.2 m into the till below the base of the overlying topsoil. Each hole was pre-soaked by filling it with water and allowing the water to infiltrate completely prior to the start of the test. If necessary following pre-soaking, silt and sediment were removed from the bottom of the hole and the hole was cleaned to its original depth. Water was then poured into the hole until the water level was approximately 0.15 m above the base of the hole. A small board was placed across the top of the hole and a reference point was marked on the board over the center of the hole. All the measurements were taken from that reference point with a measuring tape. The distance from the top of the board to the surface of the water was measured and recorded at consistent time intervals.

⁹ Hydraulic conductivity measurements from the Hanson Brick monitors (Golder Associates. November 2009) show the hydraulic conductivity (geometric means) of the shale bedrock decreasing with depth, from an order of magnitude of 10^{-7} m/sec at the overburden/bedrock interface to 10^{-9} m/sec at depths greater than 30 mbgs – see summary table and plot in Appendix 4-4.

Plotted results of the percolation tests at PT-1 and PT-2 are presented in Appendix 4-4. Percolation testing yielded T-times of 2 to 4.4 min/cm in the Clayey Silt Till at these two locations. These T-times correlate to hydraulic conductivities in the very upper weathered zone of the Till at locations PT-1 and PT-2 on the order of 10^{-3} to 10^{-5} m/sec, or to an infiltration rate equivalent (used in the MOE Storm Water Design Manual, 2003) of between 135 to 300 mm/hour. These results were not used in the water balance calculations¹⁰.

These results, while higher than would be anticipated for a clay-rich Till, are considered useful however for illustrating the effect of weathering and fracturing on increasing the bulk hydraulic conductivity of these types of soils at very shallow depth. The bulk hydraulic conductivity of the clay-rich Till will decrease with depth as the soils become less exposed to the effects of surface weathering. We note that site grading activities will remove essentially all of this upper weathered zone of the Till soils in the developable land parcels, either through removal at cut areas, or from compaction of engineered fill in the low areas. The resulting exposed surficial soils after site grading will be low conductivity clay-rich soils that will not be conducive to mitigating infiltration.

4.3.2.3 Groundwater Level Monitoring

Groundwater level measurements at the monitoring wells and mini-piezometers have generally been carried out on a quarterly schedule since the installation of the on-site monitors in June 2009. On-site and off-site quarterly monitoring has been typically scheduled to occur roughly during the months of January, April, July and October¹¹. The complete results of groundwater level monitoring at the Subject Property are tabulated on Tables SWL-1 through SWL-2 found in Appendix 4-5. This table also includes water levels from the previously installed Trow monitors MW-1, MW-2 and MW-3, which are included in the WSP monitoring program.

Groundwater levels were also continuously monitored at selected wells using pressure transducers (data loggers). WSP staff installed *Schlumberger* Mini-Diver DI501 data-loggers at on-site and off-site monitoring wells beginning in June 2009. Table 4.5 identifies the locations and date ranges over which time data loggers have been installed. A *Schlumberger* Mini Baro-Diver DI500 was also installed at the Subject Property to provide barometric compensation of the data. The loggers were suspended from the tops of the monitors by steel cables and were set to record water level fluctuations at hourly intervals.

The data from each data logger and the baro-logger were downloaded during the quarterly monitoring visits. Figures SWL-1 through SWL-20-2 in Appendix 4-5 present plots of the spot level and continuous water level measurements at all locations with data loggers¹². The data logger plots for the monitoring wells (Figures SWL-7 through SWL-20-2 inclusive) include the spot water level measurements and generalized stratigraphy and well construction details at the boreholes, and where available nearby watercourse channel invert elevations and mini-piezometer spot data measurements. Farm Pond water levels are also shown for comparison to the groundwater elevations at the monitors closest to the Farm Pond (MMM-09-2, MMM-11-21 and MMM-11-22).

¹⁰ Data from the tri-linear soil classifications and published soils mapping were used in the water balance calculations (see Section 4.3.2.1).

¹¹ Monitoring at the off-site locations was discontinued following the February 2011 event.

¹² The data loggers at the off-site wells north of Highway 407 were removed in February 2011. Two of these data loggers were then installed at MMM-09-02, and at MMM-09-06-D.

Table 4.5 – Data Logger Locations

Monitoring Well	Figure Reference	Start Date	End Date
MMM-09-1S	SWL-7	June 19, 2009	July 27, 2011
MMM09-1D	SWL-7	December 12, 2015	April 4, 2016
MMM-09-2	SWL-16	February 18, 2011	still installed
MMM-09-4	SWL-8	June 19, 2009 December 12, 2015	July 27, 2011 April 4, 2016
MMM-09-6S/D	SWL-15	February 18, 2011	still installed
MMM-09-9	SWL-9	June 19, 2009	July 27, 2011
MMM-09-10S/D	SWL-10	June 19, 2009	still installed
MMM-09-15S	SWL-11	November 11, 2009	February 17, 2011
MMM-09-17	SWL-12	November 18, 2009	February 17, 2011
MMM-09-19S/D	SWL-13	November 17, 2009	February 17, 2011
MMM-09-20	SWL-14	November 18, 2009	February 17, 2011
MMM-11-21	SWL-17	July 27, 2011	still installed
MMM11-22S/D	SWL-18	July 27, 2011	still installed
Farm Pond	SWL-19	July 5, 2011	November 28, 2012
		July 7, 2013	still installed
MP-24S/D	SWL-20-1, SWL-20-2	October 29, 2013	still installed

Notes:

The data loggers at MP-24D and MP-24S were intended to be removed from the mini-piezometers during the 2013-14 winter season to prevent damage to the units from freezing. In 2013, the logger at MP-24D could not be retrieved as it was already frozen in place but the logger at MP-24S was successfully removed for the winter season. Both of these loggers were removed over the winters of 2014-15 and 2015-16 but left in place over the winter of 2016-17. During the winter of 2014-15 both loggers were installed at MMM-09-10 to check their operation against the logger already installed at MMM-09-10 (both were fine). During the winter season, these two loggers were temporarily installed at MMM-09-1D and MMM-09-4.

Groundwater levels exhibit a seasonal pattern from the spring time highs of late March/early April to late season lows at the end of the growing season (late September/early October). On the basis of the quarterly spot measurements at all on-site monitors, the maximum recorded fluctuations in static water levels at the monitors varied from 0.4 to 2.6 m (average of 1.6 m) at monitors located some distance from the watercourses. This range was smaller at the monitors located in the low lying lands next to the watercourses, from about 0.3 to 1.7 m declines observed over the study period (average of about 1.0 m)¹³. The lower magnitude in seasonal fluctuations observed at monitors located next to the watercourses is expected as watercourse valleys act as boundaries to the shallow groundwater system. Figure 4.5 and Figure 4.6 present interpreted groundwater levels at the Subject Property for spring and summer conditions.

The range in seasonal groundwater fluctuations was also examined at most of the data-logger equipped wells¹⁴. The seasonal range at these wells, with their continuous data sets, when compared to the corresponding ranges obtained from spot measurements at these same wells, was found to be about 0.1 to 0.7 m higher at monitors close to the watercourse (average 0.4 m), and from 0.2 to 0.7 m at monitors located away from the creeks (average 0.5 m). It is therefore not considered unreasonable based on these

¹³ On-site monitoring wells MMM-09-04, MMM-09-06S/D, MMM-09-07, MMM-09-09, MMM-09-10S/D, MMM-09-14, MMM-09-17, and EXP-1 to EXP-4 are located nearby to the watercourses. The remaining on-site wells were considered to be included in the other category described above.

¹⁴ MMM-09-19D that experienced very slow recovery of water levels is excluded from this discussion.

observations to conclude that the seasonal groundwater level fluctuations observed from 2009 to 2017 can range in average from between approximately 1.4 and 2.1 m (low ground and higher ground).

Vertical gradients are available from the eight monitoring well nests. At six of the nests, all located some distance from the watercourses; consistent downward hydraulic gradients were recorded¹⁵. At monitoring well nest MMM-09-01 and MMM-11-22 downward gradients ranged respectively between 0.00 to 0.24 and 0.04 to 0.18 respectively. At MMM-09-01 the downward gradients were observed to increase above 0.10 when the shallow water levels at this location rose in response to rain or snow melt events. At the other five monitors, the measured downward gradients were more pronounced and ranged from 0.34 to 0.81 (MMM-09-18), up to 1.07 to 2.02 (MMM-09-05)¹⁶.

Upward vertical gradients have been generally recorded at the well nest at MMM-09-10, ranging from 0.001 to 0.09¹⁷ (refer Figure SWL-10 in Appendix 4-5). The vertical gradient at the well nest constructed at MMM-09-6 varies depending on the season. Downward gradients are generally observed during the spring season, and reverses to an upward gradient during the summer and fall (July to December typically) as the shallow groundwater levels in the till drain and decline below the groundwater level of the bedrock (refer to Figure SWL-15 in Appendix 4-5). These two nests are located on the Subject Property next to the central watercourse (Reach 14W-14) and the deeper monitors are screened in the shale bedrock. In addition, at monitoring well MMM-09-09 (also screened in the upper shale) which is located close to the main branch of the FM1009 watercourse, the groundwater levels are often recorded above the stream channel bed elevation at mini-piezometer MP-07 (located about 40 m away). The data logger plots for MMM-09-09 and the MMM-09-10 nest indicate the groundwater levels at these locations are above the stream bed elevation over much of the year, declining at or below the channel during the summer season in particular (refer to Figures SWL-9 and SWL-10 in Appendix 4-5).

These findings imply that minor groundwater discharge from the bedrock aquifer is occurring at the Subject Property across both the main channel (Reaches 14W-12, 14W-16) and the central watercourse channel (Reach 14W-14) over much of the year. The volume of bedrock groundwater discharge over Reach 14W-14 (central Reach to FM1001) is insufficient to maintain base flow during the summer months as witnessed by the dry channel conditions during the summer season. Similarly, bedrock discharge into the main channel system is also insufficient to maintain baseflows based on on-site observations of isolated pools of water in the lower reaches and no flows observed at the mid to upper reaches during summer seasons.

Data collected from groundwater monitors and mini-piezometers alongside the easternmost channel of FM1009 (Reach 14W-13) and the Reach to FM1109 at the eastern part of the Subject Property (Reach 14W-11 and Reach 14W-11A) do not indicate bedrock groundwater contributions into these channels, and the interpreted bedrock groundwater contours (see Figure 4.5 or Figure 4.6) are below the channel bed elevations (Reach 14W-13's channel bed declines from 153.9 to 149.0 masl, and Reach 14W-11A declines from 154.9 to 151.3 masl on the Subject Property). Reach 14W-11A is considered to be losing water into the ground over most of the year (refer to Figure SWL-8 in Appendix 4-5).

¹⁵ Monitoring Well Nests MMM-09-01, MMM-09-05, MMM-09-15, MMM-09-18, MMM-09-19, and MMM-11-22.

¹⁶ Early data at some of these monitors is not included in these summaries because the calculated vertical gradients were not accurate (as one or both of the nested wells were still recovering).

¹⁷ A downward gradient of 0.05 was manually recorded at this location on one occasion, July 5, 2011.

The data logger plots also illustrate rapid rises in the shallow groundwater following notable precipitation events and snow-melts, followed by a decline towards pre-event water levels over a two to three week length of time. These observations are consistent with an environment comprised of generally low hydraulic conductivity materials (till and/or clayey silt soils in the overburden and shale in the bedrock). Weathering of the surficial zone (approximately the upper 3-5 m) results in an enhanced bulk permeability of these soils due to the presence of fractures and other openings. This allows the upper zone to more readily receive, and transmit water, with rapid increases in water level due to events such as snow melts (clearly visible in the data logger equipped wells (Figures SWL-7 to SWL-18 in Appendix 4-5), which is then followed by a lowering of the water table as the upper zone drains. With depth, the effects of weathering and the frequency of fractures decreases and the permeability of these till and clayey silt soils becomes lower.

4.3.2.4 Findings of the Supplemental Farm Pond Investigation

An investigation was carried out at the Farm Pond (Reach 14W-14A) to characterize groundwater interactions at the large human-made Farm Pond at the centre of the Subject Property. Aerial photography from 1935 shows no evidence of a Farm Pond at this location but rather the continuation of Reach 14W-14 passing through the present day Farm Pond location before joining with the main channel to the south. According to the farmer living on the property, the Farm Pond was constructed shortly before the Hurricane Hazel storm event in October 1954.

The supplemental Farm Pond investigation study commenced in February 2011 when the surface water elevation of the large Farm Pond at the centre of the Subject Property was surveyed by WSP surveyors (February 10, 2011) and with the installation of a data logger at monitoring well MMM-09-02 (February 18, 2011). As noted earlier, three monitoring wells were constructed at two locations to the southwest of the Farm Pond in mid-July 2011, and a staff gauge was installed in the existing Farm Pond along with three mini-piezometers that were installed along the periphery of the Farm Pond in early July 2011.

Data loggers were installed at the staff gauge in early July 2011 and at the three monitoring wells in late July 2011 (MMM-11-21 and MMM-11-22S/D). WSP hydrogeological staff carried out water level monitoring visits and data logger uploads at these monitors between July 2011 and mid-April 2017¹⁸.

Plots of the water level fluctuations at each of the above monitors (and MP-24, see below) are provided in Appendix 4-5 on Figures SWL-16 to SWL-20-2¹⁹ as are hydrogeological cross-sections plotted through the centre of the Farm Pond (see Figure 4.4, and Figures HG1 through HG3 which are provided in Appendix 4-

¹⁸ WSP staff discovered that the Farm Pond staff gauge was missing in January 2012 (top of T-bar visible at ice surface) and that the data logger (direct read cable with interface at the shore) could not be uploaded (no connection/signal). It is suspected that the staff gauge was sheared off the T-Bar by ice-heave, and at time of a subsequent thaw event sank into the Farm Pond. An estimate of the ice level was made based on the height of the visible T-Bar above the ice. The data logger was recovered, the staff gauge was repaired, and the logger was reinstalled at this location on July 18, 2012. The data logger was found again to be at the bottom of the staff gauge in October 2012 (direct read cable was sheared) and recovered on November 28, 2012. A new Farm Pond gauge installation was set up nearby to MMM-11-21 in July 2013 and Farm Pond level monitoring reinitiated. This location was again found to have been damaged by ice action in the winter of 2013-14 and a fourth installation was made nearby to MMM-11-21 in April 2014.

¹⁹ Data logger plots with 5 m vertical intervals are also provided in Appendix 4-5.

5). Farm Pond levels range between 1 to 2 m higher than the groundwater at the nearby wells during the summer and fall seasons, and from about 0.5 to 1.2 m higher during the winter and spring seasons²⁰.

The data collected up to the end of 2012 indicated the Farm Pond was losing water into the ground but there remained questions from CH about the potential for groundwater discharge into the Farm Pond at its upstream end where no monitors were immediately located. WSP staff met on-site with CH's Hydrogeologist in early October 2013 and it was agreed to construct a shallow drive-point mini-piezometer nest at the upper (west) end of the Farm Pond and install data loggers at these stations. The purpose for this new nest was to provide a data point location at the upstream end of the Farm Pond to monitor and confirm the previously reported conclusions about the groundwater input into the Farm Pond.

The two drive-point piezometers were installed towards the upstream (west) end of the Farm Pond on October 22, 2013 and the mini-piezometers were screened at depths of 1.19 and 1.28 m below grade (MP24-D), and 0.31 and 0.44 m below grade (MP-24S)²¹. Following the installations, WSP staff manually surveyed the elevations of the new piezometers and also re-surveyed the elevations of the pre-existing wells and mini-piezometers in the immediate vicinity of the Farm Pond²² to ensure all elevations at these monitors were using a consistent datum.

Figures SWL-20-1 and SWL-20-2 (Appendix 4.5) graphically present the data logger plots of water level fluctuations at the two mini-piezometers with pond levels also shown for comparison. Table 4.6 below provides a summary of the observations seen in the data over the past 3.5 years broken out by dates.

Table 4.6 – Mini-Piezometer MP-24 Observations

Date Range	MP-24S	MP-24D
Oct. 22 - Nov. 24, 2013	Water level fluctuations similar to Farm Pond, but slightly lower.	Water level fluctuations do not behave similar to Farm Pond, remain slightly above grade, and above Farm Pond level.
Nov. 24 - Dec. 13, 2013		Recorded water levels behave oddly with some random spikes not seen at the pond. Data during the winter then generally mimicked what was observed at the Farm Pond, until March 18, 2014. Believed to be due to freezing of mini piezometer (see main discussion).
Dec. 13, 2013 - Mar. 18, 2014	Logger removed for winter.	Sudden change in response at the logger (believed to be from ice melting in the mini-piezometer), but response at the logger for the
Mar. 18 - Apr. 30, 2014		

²⁰ The narrowing of the difference between the Farm Pond and groundwater elevations during the winter and spring seasons is due to recharge of the shallow groundwater system. On average, the groundwater levels recorded at the Farm Pond monitors are between 1.1 and 1.6 m higher than the Farm Pond.

²¹ As explained in Section 4.3.1.1, this mini-piezometer nest was installed just beyond the upper limit of the Farm Pond (as defined by its average water level) and to the northwest of a topographic high point in Reach 14W-12A.

²² The top of pipe elevation of MMM-09-2 was used as a benchmark for this survey and elevations were then re-surveyed at MMM-11-21, MMM-11-22S/D, MMM-09-10S/D, the Farm Pond logger station and MP-21, MP-22, MP-23, and MP-24S/D. The elevations presented in Tables SWL-1 and SWL-2 reflects these resurveyed top of pipe elevations.

Date Range	MP-24S	MP-24D
Apr. 30 - Nov. 26, 2014	Water level fluctuations similar to Farm Pond but lower. Responses to rain events match those at the Farm Pond and declines afterward are similar to a point, and then decline at a faster rate.	remainder of the year was very abnormal, exhibiting delayed responses (see Figure SWL-20-1 in the appendices). Logger was thought to have been damaged.
Nov. 26, 2014 - Apr. 27, 2015	Logger removed and installed at MMM-09-10 for winter to confirm its operation against the logger installed at that well. Logger is operating normally.	Logger removed and installed at MMM-09-10 for winter to confirm its operation against the logger installed at that well. Logger is operating normally. Logger is not damaged as originally surmised.
Apr. 27 - Jul. 20, 2015	Water levels at both mini-piezometers nearly identical, and nearly identical to Farm Pond, at or slightly below Farm Pond levels.	
July 20 - Oct. 25, 2015	Water levels at the mini-piezometers decline below Farm Pond levels and then dry out.	
Oct. 25 - Dec. 23, 2015	Water levels at the mini-piezometers and the Farm Pond rise rapidly in response to a rainfall event and water levels at the mini-piezometers then are nearly identical and closely mimic those at the pond, generally at or slightly below the pond levels, although they show greater immediate responses to rainfall events than recorded at the Farm Pond.	
Dec. 23, 2015 - Apr. 4, 2016	Logger removed for winter and temporarily installed at MMM-09-1D.	Logger removed for winter and temporarily installed at MMM-09-4.
Apr. 4 - Apr. 14, 2016	Water levels at both mini-piezometers nearly identical and at or slightly below the Farm Pond levels, with similar responses to precipitation events.	
Apr. 14 - Jun. 8, 2016	Water levels at both mini-piezometers are near identical and their responses are similar to those observed at the Farm Pond, but are lower, on the order of 0.1 to 0.2 m lower.	
Jun. 8 - Nov. 4, 2016	Water levels at both mini-piezometers are near identical and they decline and then become dry over the summer. Two short term responses to rainfall events were seen between Sep. 27 - Oct. 9 and Oct. 27-28 that were not seen at the Farm Pond location (likely because Farm Pond location was dry during the same period).	Water levels at both mini-piezometers are near identical and they decline and then become dry over the summer. Logger stopped recording on Aug. 26, 2016 and was returned to the office on Oct. 14 in order to upload its data.
Nov. 4 - Nov. 24, 2016	Water levels at the mini-piezometers are near identical, exhibiting a peak response to a rainfall event followed by a decline (MP-24S becomes dry). There is no response observed at the Farm Pond, likely as the Farm Pond station is dry (above the Farm Pond water level) and thus changes in water level at the Farm Pond are not recorded.	Logger reinstalled on Nov. 4. Water levels at the mini-piezometers are near identical, exhibiting a peak response to a rainfall event followed by a decline (MP-24S becomes dry). There is no response observed at the Farm Pond, likely as the Farm Pond station is dry (above the Farm Pond water level) and thus changes in water level at the Farm Pond are not recorded.
Nov. 24 - Dec. 26, 2016	Water levels at the mini-piezometers are nearly identical, and recorded well above the Farm Pond level, which begins to show response (gradual increase) beginning Dec. 2, until a precipitation event on about Dec. 26 where both Farm Pond levels and mini-piezometer levels show a marked increase.	
Dec. 26, 2016 - Apr. 18, 2017	Water levels at the mini-piezometers are nearly identical, and nearly identical to Farm Pond, at or slightly above Farm Pond levels.	

4.3.2.4.1 *Atypical Responses of Data Logger at MP-24D (November 18, 2014 to November 26, 2014)*

The readings collected from the logger at MP24-D over the first year of monitoring exhibited odd behaviour as can be seen on Figure SWL-20-1. The upper part of the mini-piezometer was found to be solidly frozen on December 16, 2013 and the logger could not be removed for uploading data, and the unit was left in place through the winter²³. The data recorded by this unit between roughly November 23, 2013 and March 18, 2014 exhibited a number of large and sudden spikes in recorded water levels that do not correlate with changes in water levels at the Farm Pond (see Figure SWL-20-1), although for much of the winter season the water levels recorded at MP-24D mimicked the Farm Pond levels²⁴. The data during this 4 month period also shows significantly more variability (i.e., noise) than the data before or after this time frame. A sudden 61 cm decline in water pressure was recorded over a 1-hour period on March 18, 2014 after which the data displayed a more stable looking trend, which matched up with the manual measurement taken on April 30, 2014. We therefore do not consider the data collected at MP-24D during this 4 month winter period to be reliable given the strange behaviour observed. The sudden spikes in pressure readings at the MP-24D data logger appear to correlate to air temperature changes that fall below freezing, particularly in the earlier part of the winter season, and we are of the opinion that the behaviour is related to pressure build-up within the mini-piezometer due to surface freezing and expansion of ice within the pipe.

For the remainder of 2014, the data provided by the data logger installed at MP24-D continued to show odd behaviour in the water level fluctuations at the mini-piezometer. The recorded water level fluctuations at the mini-piezometer did not follow the pattern observed at MP24-S, where water level fluctuations were seen to quickly respond to rainfall events in a like manner to the responses at the Farm pond. Instead, the water level responses recorded by the MP24-D data logger appeared to be delayed and highly averaged.

The data logger was thought to have been possibly damaged from having been left installed over the winter of 2013-2014 and it was removed on November 26, 2016 and installed for the winter season at MMM-09-10 so that a comparison in its response could be made against that well's data logger. A review of the winter data collected at MMM-09-10 indicated that the MP24-D logger was operating correctly and it was re-installed at the mini-piezometer on April 27, 2015. All subsequent data collected at MP-24D by this data logger indicates near identical water level fluctuations to MP24-S in a pattern that resembles those seen at other monitoring wells across the property.

4.3.2.4.2 *Discussion of MP-24 Results*

Over the roughly 3.5 year period of study at location MP-24 (MP-24D discussions exclude data from the 1 year period discussed in the preceding section), the groundwater levels at the 2 mini-piezometers have generally been closely matched to the water level fluctuations observed at the Farm Pond and are therefore considered to be controlled by precipitation and the water level fluctuations at the Farm Pond and adjacent channel. The average difference between the water level at MP-24S has it at 1 mm (-0.001 m) below the

²³ It had also been intended to remove this unit from the mini-piezometer over the winter months but this could not be done because of the frozen condition.

²⁴ The Farm Pond levels were frequently higher than the ground elevation at the mini-piezometer suggesting the area was also inundated with surface water following precipitation events.

Farm Pond level (range of -0.32 to +0.71 m²⁵) and at MP24-D, water levels at the mini-piezometer were on average 4mm below Farm Pond level (-0.004 m) with a range of -0.84 to +0.69 m. Water levels at the mini-piezometers have been recorded above grade only at times when the Farm Pond level has also been recorded above the grade at the MP-24 monitoring station (grade is approx. 148.8 masl).

We also wish to note that, as the Farm Pond levels decline during the summer season, the Farm Pond edge also recedes to the southeast, moving further away from the mini-piezometer station and therefore; comparisons between water elevations at the mini-piezometer and the Farm Pond as an indicator of groundwater seepage potential relative to the Farm Pond levels become less significant.

The data collected to date at MP-24D indicates that the gradients at this location vary between upward (towards the Farm Pond/channel) and downward (from the Farm Pond/channel into the ground) with an average gradient calculated at +0.001 (downward). This is not unexpected as this monitor is sited in the area where groundwater gradients by the water course system were predicted to change from upward (i.e., to the northwest such as observed at MMM-09-10) to downward (as seen at all the monitors around the Farm Pond to the southeast).

Figure HG-4 (Appendix 4.5) shows the interpreted limits of the potential for seepage towards the upstream (west) end of the Farm Pond. The seepage limits are based on where the interpreted groundwater contours (from April 30, 2014 data) intercept the topographic contours and extends approximately 35 m further east of Station MP-24. This potential seepage area is generally located beyond the proposed limits of Farm Pond construction highlighted by the yellow line shown on the figure, and based on topographic contours, is also located below the topographic rise between the channel and the Farm Pond (see Figure HG-4) that indicates seepage is directed into the channel and will not reach the Farm Pond except under short-term conditions when there is flow from the channel into the Farm Pond (e.g., after rain events).

The data collected since 2011 at the data loggers at the monitoring wells have shown the Farm Pond levels are always higher than the static water levels at the groundwater monitors surrounding the Farm Pond itself, and downward gradients were generally recorded at the mini-piezometers²⁶ along the edges of the Farm Pond. The monitoring data from MP-24 indicates there is potential for a very small amount groundwater input beyond the upstream end of the Farm Pond entering Reach 14W-12A. Between October 22 and November 22, 2013 the groundwater elevations recorded at MP24-D (see Figures SWL-20-1 and SWL-20-2) ranged from 17 cm below the Farm Pond level (following a surface runoff event into the pond) to 12 cm higher than the Farm Pond water elevation (October 29), and from April 27, 2015 to April 17, 2017 have ranged from between 82 cm below Farm Pond levels to 69 cm above the Farm Pond levels²⁷. To date the maximum upward gradient at this location relative to the Farm Pond (excluding data between November 23, 2013 and November 26, 2014) has been measured at about -0.215²⁸, with an overall average of +0.001, a very slight

²⁵ The peak high difference at both mini-piezometers occurred on October 25, 2015 over a 2 hour period when water levels at the mini-piezometers and the Farm Pond rose dramatically over a short period of time in response to a rain event. This large difference quickly declined as Farm Pond levels recorded at the Farm Pond logger station continued to rise.

²⁶ At site visits when the mini-piezometer and/or Farm Pond were not dry or frozen. Mini-piezometers MP-22 and MP-23 were identified as plugged by accumulated silt and cleaned out in early September 2013.

²⁷ As identified earlier, the data collected after November 23, 2013 through the winter of 2013-2014 and up to November 26, 2014 at the mini-piezometer exhibited strange behaviour and was not considered reliable.

²⁸ Upward gradients are expressed as negative values, downward gradients as positive values.

downward gradient²⁹. In contrast, downward gradients are present at the monitoring wells located around the perimeter of the main area of the Farm Pond where groundwater has always been measured at lower elevation than the water in the Farm Pond (on average at the monitors, between 1.1 and 1.7 m below the water level in the Farm Pond, or downward gradients from the Farm Pond towards the monitors on the order of +0.042 to +0.118).

Given the larger surface area of the eastern part of the Farm Pond, and the larger outward gradients identified in that area, losses of water from the Farm Pond back into the ground will be significantly greater than any potential groundwater inflows originating near the upstream end of the Farm Pond, which as noted earlier, are to the northwest of the Farm Pond alongside Reach 14W-12A, and would discharge into this reach and not into the Farm Pond itself. As the hydraulic conductivity of the clay/silt soils found across the site and at the Farm Pond is on the order of 10^{-7} to 10^{-8} m/sec (very low), the quantity of groundwater entering into Reach 14W-12A and/or the Farm Pond will be low. The new monitoring station data therefore refines but does not change the understanding of the function of the Farm Pond, which is that it is maintained by surface water inflows and not by groundwater contributions.

In conclusion, surface water level data from the Farm Pond as well as groundwater data from surrounding monitors indicate that the Farm Pond does not receive groundwater inputs in sufficient quantities to affect the water level of the Farm Pond, nor to lead to appreciable discharges into the adjacent channel at the top end of the Farm Pond. Flows from the Farm Pond is associated with surface water inputs that fill the Farm Pond following rain events, and then drains back out to the watercourse network afterward. Groundwater elevations at the surrounding monitoring wells showed the water level at the Farm Pond is consistently on the order of 1 to 2 m higher elevation than the groundwater, and therefore; the Farm Pond loses water into the ground rather than receiving groundwater inputs³⁰. The very minor groundwater discharge potential that is present near the upstream end of the Farm Pond (calculated at 110 m³/year, see Section 4.4.4.7) and that enters Reach 14W-12A is far outweighed by the losses back into the ground over the much larger area of the Farm Pond to the east, where the greater downward head differences are recorded.

4.3.2.5 Stream Base Flow Measurements

Estimates of the flows within the watercourses traversing the Subject Property were carried out by WSP staff during site visits between May 2009 and February 2011. Measurements were taken at consistent locations at each Reach, generally at the mini-piezometers and flow monitoring points (MP-1 to MP-7 and FMP-1 to FMP-4, refer to Figure 4.4 for these locations³¹). The flow estimates were generally carried out, if possible,

²⁹ The gradients presented above have been calculated using the lateral and vertical distances from the edge of the Farm Pond (average Farm Pond water elevation 148.7 masl) or edge of watercourse (e.g., MMM-09-10) to the centroid of the well screen.

³⁰ Groundwater elevations at a monitoring well nest located approximately 100 m upstream of the Farm Pond inlet (MMM-09-10 alongside Reach 14W-14) indicate groundwater elevations at that location to range between about 0.5 and 1.0 m higher than the surface water levels in the Farm pond located downstream of this station (further note that during the summer season, groundwater elevations at these monitors would typically decline the base of the channel, so inputs to the channel are not year-round). The data from this monitoring well nest and the wells around the Farm Pond indicated that the area where the potential for groundwater inputs changed to surface water losses would be located near the upstream end of the Farm Pond. The data collected at MP-24D supports this as the groundwater levels have been recorded close to ground surface at this location.

³¹ FMP-3 is located at the central Reach of the FM1001 watercourse at the southeast corner of Tremaine Road and Number 1 Sideroad.

following 5 days of dry weather, with some exceptions when precipitation events conflicted with staff scheduling.

The measurements were carried out by visually identifying a consistent length of channel and measuring the time for a small floating object to travel from the upstream end to downstream end of the measured length of this reach. A minimum of five to six timed runs were obtained (using the stop-watch function on a GPS) and an average flow velocity was calculated. Runs where the floating object were caught on an obstruction or otherwise prevented from travelling down channel unhindered were ignored and the run was repeated. Saturated channel cross-sectional areas were obtained at the upstream and downstream ends of the length under consideration and an average area was calculated. This allowed for an estimate of total flow at the watercourse. Frictional losses along the channel sidewalls and along the substrate were ignored and thus the calculated flow volumes are recognized to be potentially over-estimated.

Stream flow measurements pertinent to each watercourse are summarized in Table 4.7 below. Flow estimate calculations are also provided in Appendix 4-5. Table 4.7 also presents estimated base flow contributions from groundwater based upon the monthly water balances carried out for this study³².

The watercourses within the Subject Property and EIR Sub-catchment Study Area were generally observed in flowing conditions during the late fall through to the late spring, although wintertime observations often found the watercourses as completely frozen, or frozen with some flow observed below the ice. In the summer months, the watercourses, particularly the central and eastern watercourse to FM1001 (Reach 14W-13 and Reach 14W-14) and the watercourse for FM1109 (Reach 14W-11 and Reach 14W-11A) are observed to be non-flowing. The main channel for FM1001 (Reach 14W-12 and Reach 14W-16) was observed on the Subject Property during the summer and late summer months with little to no flow, and pooled or standing water. These summertime pockets of water along the lower stretches of the watercourse are likely from a combination of minor groundwater discharge from the bedrock system, and remnants of storm flows collected in depressions along the stream channel.

It is also noted that, based on interpretation of aerial photography, that ditching along both sides of Highway 407 appears to be conveyed directly into the watercourses passing through the Subject Property, without benefit of SWM facilities. One other source of water within Reach 14W-12 and Reach 14W-16 (FM1001) is from quarry discharge at the Hanson Brick operation to the north of Highway 407.

Groundwater and precipitation entering the quarry is reported to be intermittently pumped into a settling pond and discharged into this watercourse. In 2008, a total volume of approximately 44,500,000 litres was pumped from the quarry into this watercourse, at an average rate of 1,078 litres/minute. This is equivalent to an average of about 13 hours discharge per week into this watercourse, which would not be noticeable during fall to spring conditions, but which would lead to additional water to this stream during the summer period when the watercourses are intermittent.

³² The monthly water balance methodology and pre-development infiltration estimates are presented beginning in Section 4.4.2 of this report.

Table 4.7: Summary of Stream Flow Observations

Monitoring Location	Easting	Northing	5-May-09	29-May-09	19-Jun-09	24-Sep-09	9-Nov-09	18-Nov-09 and 20-Nov-09
5-Day Preceding Weather Description			20 to 25 mm rainfall recorded at Pearson and Oakville Weather Stations on April 30, and additional 1 mm combined over May 1 and 2. May 2 to 5 no precipitation.	Wet weather. May 27-28, 30 mm combined recorded at Pearson, 15 mm combined recorded at Oakville. An additional 3 - 4 mm of rain recorded at both stations on May 29	Rain Event June 16, 12 to 15 mm recorded at Pearson and Oakville over June 16 to 17, bulk falling on the 16th.	3 to 4 mm rain recorded at Pearson and Oakville combined on September 21 and 23 (Pearson only). Previous to these minor events, there was no precipitation recorded after August 28-29 at either station.	3 to 4 mm precipitation recorded at each weather station over November 4 and 5.	Zero precipitation recorded at Pearson or Oakville from November 4-5. Significant Precipitation Event beginning approx. 0500 hours at Oakville/Pearson on the morning of November 19, precipitation ending at 0300 hours on the 20th - 14 mm at Pearson
Subwatershed FM1001	Est'd Base Flow Rates from Water Balance -->		1,127 to 457 LPM (April and May)	457 to 27 LPM (May and June)	27 LPM (June)	0 to 52 LPM (Sept and Oct)	52 to 184 LPM (Oct and Nov)	184 LPM (Nov)
Easternmost Tributary (14W-13)								
FMP-4	597523	4809561				Downstream of FMP-4 standing water in pockets - no flow	Standing water in channel, no flow	
Central Tributary (14W-14)								
FMP-3 (Corner of Burnhamthorpe and Tremaine)								No defined channel - water observed flowing in rivulets from concrete bridge/culvert. Water was bright green with algae. Some flow from west through culvert that crosses Tremaine Road
MP-06	597348	4809417.944	Mini-piezometer is situated in water but area is spread out with Reed Canary Grass, flow is present but spread out over wide area - no flow estimate possible. Temperature = 14.8C (Air Temp = 22.5C @ 2:00 PM) Conductivity = 873 uS, pH = 7.81					
MP-03/FMP-5	597808	4809266.198	Watercourse flowing. Flow estimated at approx. 365 LPM	Flow estimated at 43 LPM		Channel dry		
Main (Westernmost) Tributary (14W-16/14W-12)								
MP-07	597541	4809149.703	Watercourse flowing but no suitable location for flow estimate found during first visit. Temperature = 16.9C (Air Temp = 16.0C @ 2:20 PM) Conductivity = 1,050 uS, pH = 7.95	Watercourse flowing. Flow estimated at 445 LPM.				
FMP-1 (upstream of SG-1)	597618	4809131						
Staff Gauge #1 (Upstream of small (West) Pond)	597677	4809113.09	Flow estimate downstream of MP-07 immediately upstream of small pond outlet (flowing) into main channel (roughly where SG-1 was later installed). Flow estimated at approx. 450 LPM. Temperature = 20.1C (@ 2:40 PM) Conductivity = 404 uS, pH = 8.51			No flow, standing water observed. Temperature = 20.0C (Air Temp = 26.2C) Conductivity = 862 uS, pH = 7.05	Flow estimated at 106 LPM	
MP-04/FMP-06	597972	4809088.192	Watercourse flowing. No suitable reach for flow estimate. Temperature = 14.3C (Air Temp = 16.0C @ 10:55 AM) Conductivity = 710 uS, pH = 8.78	Water flowing, flow estimated at 268 LPM.	Water flowing, flow estimated at 645 LPM - precipitation event recorded 2-3 days prior	Channel dry at MP-04. At farm bridge downstream of MP-04, no flow also observed in channel, standing water only in pools.		
Staff Gauge #2 (by Dundas Street)	598345	4809063.452	Flow in Main Channel by Dundas Street - channel is in bedrock so no opportunity to install mini-piezometer. Flow estimated at approx. 1,020 LPM - same order of magnitude as water balance estimate. Temperature = 18.9C (time approx. 3:00 PM) Conductivity = 853 uS, pH = 8.45			Standing water - no discernible flow		Nov. 18 - Ponded water observed in main channel with no discernible flow. Nov. 20 - Flow measured in channel, estimated at approximately 1,635 LPM (after rainfall)
Subwatershed FM1109 (14W-11A/14W-11)	Est'd Base Flow Rates from Water Balance -->		107 to 44 LPM (April and May)	44 to 3 LPM (May and June)	3 LPM (June)	0 to 5 LPM (Sept and Oct)	5 to 18 LPM (Oct and Nov)	18 LPM (Nov)
MP-01	597409	4809839.704	Watercourse flowing. Not an ideal location for an estimate but estimated flow rate was approx. 220 LPM - same order of magnitude as water balance estimate. Temperature = 15.8C (@ 1:05 PM) Conductivity = 700 uS, pH = 8.11	Flow estimated at 128 LPM.		Channel dry at mini-piezometer - standing water observed in low spots - no flow. Temperature = 20.1C (Air Temp = 26.1C) Conductivity = 2987 uS, pH = 6.07	No flow, pooled water in places	
FMP-2 (located between MP-01 and MP-02)	597608	4809788					Channel approximately 1.0m wide intermittent damp to wet areas approx. 0.02m depth. No measureable flow.	
MP-02	597769	4809665.798	Minor/slow/diffuse flow observed - could not be estimated. Temperature = 19.2C (Air Temp = 18.2C @ 12:30 PM) Conductivity = 745 uS, pH = 8.04	Watercourse flowing. Flow estimated at 247 LPM.		Channel dry	No flow, pooled water in places	
Subwatershed FM1102								
Tributary FM1102 (Tributary passing through SW part of Site)	597989	4808801	No defined channel (ploughed field) and no culvert passing under farm lane to direct flows. Stagnant/ponded water in furrows. Temperature = 21.4C Conductivity = 460 uS, pH = 7.97					
Other Water Features								
Large Pond (21 m to the west of MMM-09-2)			Temperature = 18.9C Conductivity = 630 uS, pH = 8.11					
MP-05 (Small ponded area on hill-top)	597514	4809671.167	Ponded area on crest of hill. Temperature = 21.4C (@ 1:30 PM) Conductivity = 185 uS, pH = 7.98			Dry	Channel dry at mini-piezometer - standing water observed in low spots - no flow. Pooled water 2.5 m west of MP location	
Comments regarding FM1001/FM1109			Flow estimates at the downstream end of FM1001 (14W-12) by SG-2 (1,020 LPM) is of the same order of magnitude order of magnitude estimated by water balance (between 430 to 1,060 LPM). Flow estimates at MP-01 (FM1109/14W-11A) are also the same order of magnitude (though a bit higher) as estimated by the water balance	Measurements obtained at the end of the month, so flow as would be predicted by the water balance is anticipated somewhere between the average rate for May and June. Estimated flows within FM1001 are of the same order of magnitude but higher than the average for May and June. At FM1109, at least an order of magnitude higher than predicted. Weather was wet however so measured flows should be higher than predicted by water balance.	Flows measured at FM1001 an order of magnitude higher than would be predicted by water balance, but measurement was obtained about three days after rain event. These higher flows may also coincide with a discharge event at the Hanson Brick Quarry located upstream of the site.	Both FM1001 and FM1109 were dry or pooled with no flow which is consistent with September estimates of the water balance which predicts no flow.	FM1001 (14W-16) entering site flow estimated at 106 LPM, on the same order of magnitude as predicted by the water balance. FM1109 - no discernible flows, pooled water, but water balance estimates low flows of 5 to 17 LPM	At downstream end of FM1001 (by Dundas Street), no discernible flow was observed on Nov. 18, but two days later after approximately 1-day rainfall event, flow at the same station was estimated at 1,635 LPM.

Notes:
5-day Preceding Weather observations, focussed on precipitation are presented at the top of the table for Oakville and Pearson Airport weather stations. The Pearson data is complete, the Oakville data, while closer to the site does have missing data.
The 5-day weather observations are also colour coded (shaded) per the following:

Stream flow estimates were made by measuring the time for a floating object to traverse a measured length of watercourse, of generally consistent cross-sectional profile and straight alignment. An average time was calculated using between 3 to 6 measurements. As flow velocity was thus obtained. The area of this typical cross-sectional saturated profile (or a weighted average of multiple profiles along the length of run) was calculated and this, combined with the flow velocity were used to arrive at an estimated flow rate in the channel. The calculated flow is considered an overestimation as it does not account for lower flows due to friction along the water/channel bed interfaces.

For the purposes of checking the water balance model against estimated stream flows (described above), the monthly water balance volumes of groundwater infiltration was assumed to be converted fully stream base flow. Estimates (presented in LPM) for the entire subwatershed FM1001, and a portion of the tributary to FM1109 that passes through the northeast corner of the site area from the water balance calculations are identified in **bold blue** text. Where estimates were obtained towards the beginning or end of a month, a range of the calculated average monthly base flows is presented. Measurements made towards the middle of the month are correlated against the estimated base flow calculated for the month. The water balance calculations are based on long-term averages and variations in actual precipitation from these averages will affect results. Furthermore a portion of infiltrating water will be directed to the deeper system, though this is estimated at less than 10%. Most of the infiltrating groundwater is anticipated to flow horizontally through the upper weathered/fractured zone, discharging as this layer drains into watercourses within a 1 to 2 month timeframe.

Considered dry preceding 5-days and suitable for base flow estimates	Precipitation recorded within 5 days	Significant precipitation on the day of or within 1 to 2 days before visit
--	--------------------------------------	--

Table 4.7: Summary of Stream Flow Observations

Monitoring Location	Easting		Northing	18-Dec-09	21-Jan-10	13-Apr-10	5-Aug-10	18-Oct-10 and 19-Oct-10	17-Feb-11 and 18-Feb-11
5-Day Preceding Weather Description				4.5 mm of precipitation recorded at Pearson over December 13 to 16 2.5 mm of this on December 14. Incomplete data at Oakville.	0.2 mm precipitation at Pearson on January 19, zero at Oakville over preceding 5-days.	32 mm precipitation at Pearson Over April 6 to 8 (5-7 days prior), and at Oakville, 12 mm between the 4th to the 6th, 25 mm on the 7th, and 5 mm on the 8th. No precipitation at either station April 9 to 13.	0.2 mm recorded at Pearson (July 31) and 1 mm recorded at Oakville (July 31) otherwise no precipitation at either station in the previous 5 days.	Oakville Data incomplete over 5-day interval. Pearson Airport data indicates 12.4 mm rainfall Oct 14 (and 4.2 mm Oct. 13). MMM staffer visited site late afternoon Oct. 14 to view conditions at main tributary following rain event - main channels were in flood. Quarterly site visit was 4-5 days later with no additional precipitation recorded. Flows observed over Oct 18-19 were continuing to decline from Oct. 14 rates	Minor precipitation recorded at Pearson Airport (1.4 mm) or Oakville (2.6 mm) in preceding 5 days. However, temperatures were generally above 0C in the preceding 5 days with snow cover melting. The maximum daily temperatures on the two days on-site at both weather stations were recorded between 10 and 11C.
Subwatershed FM1001	Est'd Base Flow Rates from Water Balance -->			359 LPM (Dec)	550 (Jan)	1,127 LPM (April)	0 LPM (July and August)	52 LPM (Oct)	1,156 LPM (Feb)
Easternmost Tributary (14W-13)									
FMP-4	597523		4809561		Watercourse was frozen, no visible flow	Flow estimated at 88 LPM.	Dry	No flow estimates made	
Central Tributary (14W-14)									
FMP-3 (Corner of Burnhamthorpe and Tremaine)					(Jan 22) Frozen, ice clear with pockets of trapped air. No flow observed.	Flow estimated at 235 LPM.		No suitable location to measure flow was available this visit, some flow was observed.	
MP-06	597348		4809417.944		Frozen.		Dry	No flow estimates made	
MP-03/FMP-5	597808		4809266.198		Frozen. No flow observed	Flow estimated at 183 LPM.	Dry	Flow estimated at 83 LPM	
Main (Westernmost) Tributary (14W-16/14W-12)									
MP-07	597541		4809149.703		Frozen, no flow observed. Clear ice.		Dry	No flow estimates made	
FMP-1 (upstream of SG-1)	597618		4809131	Flow estimated at 592 LPM	Frozen, crunchy ice over a denser ice. No flow observed.	Flow estimated at 381 LPM.	Dry	No flow estimates made	
Staff Gauge #1 (Upstream of small (West) Pond)	597677		4809113.09		Frozen. Crunchy ice over a clear denser ice. Flow observed downstream at culvert crossing.		No flow, some pooled water.	No flow estimates made	
MP-04/FMP-06	597972		4809088.192	At farm bridge downstream of MP-04, flow observed in channel - ice along edges.	Some flow observed north of concrete farm bridge, but frozen at bridge and to the south. MP-04 has been destroyed by ice. Flow estimated at 63 LPM	Flow estimated at 871 LPM.	Dry	No flow estimates made	
Staff Gauge #2 (by Dundas Street)	598345		4809063.452		Frozen, some flow under ice.	Flow observed.	No flow, some pooled water.	No flow estimates made	
Subwatershed FM1109 (14W-11A/14W-11)	Est'd Base Flow Rates from Water Balance -->			36 LPM (Dec)	496 (Jan)	107 LPM (April)	0 LPM (July and August)	5 LPM (Oct)	99 LPM (Feb)
MP-01	597409		4809839.704		Frozen. No flow observed.		Dry		
FMP-2 (located between MP-01 and MP-02)	597608		4809788	Frozen - water flowing under ice. Ice at least 2 cm thick. Clear and dense ice.	Frozen, dense ice covered with snow	Flow estimated at 100 LPM	Dry	Flow estimated at 32 LPM	
MP-02	597769		4809665.798	Frozen. Broke through ice - about 0.1 m of water. No measureable flow.	Frozen. Surface water in area frozen. Wet under ice.		Dry		
Subwatershed FM1102									
Tributary FM1102 (Tributary passing through SW part of Site)	597989		4808801						
Other Water Features									
Large Pond (21 m to the west of MMM-09-2)									
MP-05 (Small ponded area on hill-top)	597514		4809671.167		Frozen. Surface water in area frozen.				
Comments regarding FM1001/FM1109				Flow in FM1001 (14W-16) at same order of magnitude (but higher) than predicted by the water balance but also within about 3 days of a rainfall event. At FM1109, low flows are predicted by the water balance, and low flows seen but channels also ice-covered frozen.	All watercourses frozen at time of visit - water balance infiltration estimates suggest flow potential but very little opportunity to measure flow - one measurement obtained at FM1001 is an order of magnitude lower than predicted).	FM1001, flows estimated at about 870 LPM just upstream of Dundas Street, which is in line with water balance estimate of 1,060 LPM. FM1109 estimates of flow at 100 LPM, vs. 102 LPM estimated by water balance.	All watercourses dry (or pooled water in low areas) which agrees with water balance estimate (no flow)	Flows where measured are a bit higher than (but same order of magnitude) as flows predicted by water balance. Rates were noted to be declining still following a significant rain event on Oct 13-14.	Channels were in flood and flow measurements were not attempted by field staff.

Notes:
5-day Preceding Weather observations, focussed on precipitation are presented at the top of the table for Oakville and Pearson Airport weather stations. The Pearson data is complete, the Oakville data, while closer to the site does have missing data.
The 5-day weather observations are also colour coded (shaded) per the following:

Stream flow estimates were made by measuring the time for a floating object to traverse a measured length of watercourse, of generally consistent cross-sectional profile and straight alignment. An average time was calculated using between 3 to 6 measurements. As flow velocity was thus obtained. The area of this typical cross-sectional saturated profile (or a weighted average of multiple profiles along the length of run) was calculated and this, combined with the flow velocity were used to arrive at an estimated flow rate in the channel. The calculated flow is considered an overestimation as it does not account for lower flows due to friction along the water/channel bed interfaces.

For the purposes of checking the water balance model against estimated stream flows (described above), the monthly water balance volumes of groundwater infiltration was assumed to be converted fully stream base flow. Estimates (presented in LPM) for the entire subwatershed FM1001, and a portion of the tributary to FM1109 that passes through the northeast corner of the site area from the water balance calculations are identified in bold blue text. Where estimates were obtained towards the beginning or end of a month, a range of the calculated average monthly base flows is presented. Measurements made towards the middle of the month are correlated against the estimated base flow calculated for the month. The water balance calculations are based on long-term averages and variations in actual precipitation from these averages will affect results. Furthermore a portion of infiltrating water will be directed to the deeper system, though this is estimated at less than 10%. Most of the infiltrating groundwater is anticipated to flow horizontally through the upper weathered/fractured zone, discharging as this layer drains into watercourses within a 1 to 2 month timeframe.

Considered dry preceding 5-days and suitable for base flow estimates	Precipitation recorded within 5 days	Significant precipitation on the day of or within 1 to 2 days before visit
--	--------------------------------------	--

4.3.2.6 Groundwater and Surface Water Quality

Groundwater samples were collected by WSP staff at selected locations on September 24, 2009 and January 21, 2010 for background general chemistry. The samples were obtained from nine monitoring wells (MMM-09-4, MMM-09-10S, MMM-09-10D, MMM-09-11, MMM-09-15S, MMM-09-15D, MMM-09-17, MMM-09-19S, and MMM-09-19 D (See Figure WQ-1 in Appendix 4-6 for the sampling locations)). One surface water sample was collected from a water stream, where a staff gauge SG-1 was installed (also shown on Figure WQ-1). Dedicated polyethylene bailers were used for the purging and sampling of the groundwater into laboratory prepared sample bottles. The samples were then placed in a cooler with ice and transported to the laboratory (*Maxxam Analytics*) under standard Chain of Custody procedures.

Water quality sample results are provided in Tables WQ-1 and WQ-2 found in Appendix 4-6. Selected inorganic and metal parameter concentrations are plotted in Figure WQ-2 to facilitate the water quality characterization discussion. A graphical representation of cation and anion water chemistry is depicted in a Piper/Trilinear diagram, as shown in Figure WQ-3 (Figures WQ-2 and WQ-3 are also presented in Appendix 4-6). Water quality results were compared to the Ontario Drinking Water Standards (ODWS) and the Provincial Water Quality Objectives (PWQO)³³. For comparative purposes, the groundwater sample results were also grouped according to the geological unit in which the wells are screened. The groupings include monitoring well sample results screened in Halton Till, the till/bedrock interface, Queenston Shale (deep/shallow), and surface water.

As shown in Tables WQ-1 and WQ-2 and Figure WQ-2 several parameters exceed the ODWS, PWQO, or both comparative standards, from at least one location, including boron, cobalt, iron, manganese, silver, sodium, uranium, zinc, hardness, total dissolved solids (TDS), dissolved organic carbon (DOC), sulphate, chloride, and nitrate.

Water quality results were generally indicative of rural land uses, with no widespread evidence of inorganic parameter impacts at the Subject Property. Dissolved metals sample concentrations (cobalt, sulphate, magnesium, molybdenum, DOC and manganese), were higher in wells screened within the Halton Till as compared to samples collected from wells screened in the Queenston Shale. Samples collected from bedrock monitors indicated relatively higher boron concentrations as compared to collected till water quality samples.

Surface water quality samples indicate higher concentrations of conductivity, manganese and lower concentrations of DOC and sulphate as compared to the collected groundwater sample concentrations.

With the exception of MMM-09-15S, there is no marked variance in water chemistry between wells screened within the same geological unit. MMM-09-15S exhibited elevated concentrations of conductivity, sodium, chloride, and iron in comparison to other bedrock wells, indicating it may be affected by road de-icing salt from Tremaine Road.

³³ ODWS are from Table 2 (Chemical Standards) and Table 4 (Chemical/Physical Objectives and Guidelines) of Technical Support Document for Ontario Drinking Water; Standards, Objectives and Guidelines (MOE), June 2003, revised June 2006.

PWQO are from Table 2 (Table of PWQOs and Interim PWQOs) of Water Management, Policies, Guidelines, Provincial Water Quality Objectives (MOE), July 1994, and revised February 1999.

The Piper/Trilinear diagram (Figure WQ-3) shows good segregation between the till, bedrock, and surface water samples, with each grouping occupying a close-knit area within the diagram. Therefore, water from the different aquifers have a unique 'geochemical fingerprint', and can be characterized within a defined area of the Piper diagram. It is apparent from these distinct groupings that there was limited groundwater - surface water mixing at the time of sampling.

4.3.3 Local Hydrogeological Setting

The following discussion of the local hydrogeology is based on the information gathered during this investigation and from previous studies conducted on the property and elsewhere within the watersheds.

The surficial fine-grained deposit of Halton Till found throughout the study area serves to limit infiltration to the groundwater system and as a result, the local stream systems receive a little over two-thirds of their total water from surface runoff. As will be demonstrated in the water balance discussion, average infiltration in this environment is approximately 69 mm/year. Of this 69 mm/year of infiltration, on the order of 0.3 to 5 mm/year is estimated to recharge the deeper bedrock system³⁴, with the majority of the groundwater inputs to the local watercourses considered to flow laterally through the upper, weathered zone of the till. Almost 100% of this contribution occurs primarily in the period of November to May when the entire shallow system, including upgradient reaches of the channel are saturated and contributing flow to the watercourses.

The upper weathered zone of the till is estimated to have a bulk horizontal hydraulic conductivity on the order of 3×10^{-6} m/sec. This enhanced permeability permit infiltrating groundwater to travel somewhat quickly through the shallow zone towards the watercourses. During the late fall to late spring seasons, the streams are generally observed to be in flow, which is predicted by the water balance (groundwater infiltration is predicted during these periods). The higher bulk conductivity in the shallow system can also be observed through the rapid rise and subsequent steady declines in shallow groundwater elevations following precipitation and snow melt events visible in the data logger plots (Appendix 4-5).

Because of this enhanced conductivity, most (approximately 90%) of the infiltrating groundwater moves horizontally through the shallow system, and provides a source of base flow to the local streams during the late fall to late spring. During the growing season groundwater infiltration ceases (there is a water deficit and plants are active and using up water), the shallow system drains, and the watercourses become dry. Figure 4.5 and Figure 4.6 illustrate this decline in the shallow groundwater levels that lead to the reduction in base flow contribution from the spring into the summer seasons.

Towards the lower (southern) reaches of watershed FM1001 the watercourse valleys approach the underlying Queenston Shale bedrock, which is exposed at surface at the extreme southern limits of FM1001 (at the southern end of Reach 14W-12), just before it passes under Dundas Street. Minor groundwater inputs from the bedrock discharging into the main watercourse (Reach 14W-12 and Reach 14W-16) and the central watercourse (Reach 14W-14) across the entire Subject Property is interpreted from the monitoring well data. Bedrock discharge into the main watercourse is anticipated to continue up to a point roughly where this

³⁴ These estimates are based upon an average downward vertical gradient through the till of approximately 0.4, and vertical hydraulic conductivity ranging between 3.8×10^{-10} to 2.2×10^{-11} m/sec (see notes from Table 4.4). The greater vertical recharge (approx. 5 mm/year) is considered the more representative value for this system.

watercourse passes under Highway 407, and in Reach 14W-14 up to a point somewhere between the Highway and Number 1 Sideroad (see Figure 4.3)³⁵. The extent of the length of these reaches with potential bedrock discharge may become reduced somewhat by ongoing and future activities at the recently constructed Hanson Brick quarry, which is being excavated into the shale, and thus will lead to a localized lowering of the groundwater within the bedrock around the perimeter of the pit over time.

The seasonal groundwater elevation changes within the bedrock are not as highly variable as in the surficial tills, and thus its contribution of groundwater towards these two watercourse channels is considered to continue throughout the year. However, the volumetric rate of water moving towards these watercourses is low, and during the summer months, is insufficient to provide enough water to maintain flow in these watercourses, particularly in the reaches from about the mid-point of the Subject Property and to the north, where the channels have been observed in a dry state during the summer period. Over the lower reaches of the main channel there may be greater opportunity for groundwater to maintain pools in the channel as the bedrock is exposed in the channel and the watercourse is shaded somewhat by large trees.

4.4 Impacts of the Proposed Development

For the purposes of this study, the employment lands development for the Subject Property and adjacent lands to be developed was considered to be 90% future imperviousness³⁶ within the development limits. This is based on the maximum lot coverage requirement of 90% of the North Oakville Zoning By-Law, which anticipates more urban and intensive employment uses in North Oakville. Lands designated to remain in their natural state, or to be reconstructed in a natural state were assumed to be 100% pervious after development.

Under existing conditions, four watercourses currently enter the Subject Property from the west and northwest. The three reaches associated with watercourse FM1001 (Reach 14W-13, Reach 14W-14 and Reach 14W-16) converge into one main channel (Reach 14W-12) at about the middle of the Subject Property, and one watercourse (Reach 14W-11 and Reach 14W-11A) FM1109 cuts across the northeast corner of the Subject Property.

It is proposed to re-align the central and eastern reached (Reach 14W-14 and Reach 14W-13) of the main watercourse (FM1001) at the north boundary of the Subject Property, to the west and then southerly along the western property line via a new channel (Reach 14W-22) into Reach 14W-12A upstream of its confluence with Reach 14W-12. The watercourse to FM1109 that enters the property at the northeast (Reach 14W-11A) is also proposed for re-alignment (Reach 14W-23) along the northern and eastern property lines up to the point where it currently exits on the Subject Property (Reach 14W-11).

The main focus of the following impact assessment will be on the effects of the proposed development on the overall water balance, more specifically on changes to infiltration to the groundwater system. In addition to the water balance analysis, the potential impacts related to the proposed stream channel realignments will also be examined (Reach 14W-13, Reach 14W-14, and Reach 14W-11A).

³⁵ Note that across much of the identified channel reaches shown on Figure 4.3 with groundwater discharge potential from the bedrock, there are overlying Till sediments between the rock and the channels.

³⁶ Lots at 90% imperviousness. Road allowances with grassed boulevards are assumed as 70% impervious.

4.4.1 Water Balance Methodology

The MOE Stormwater Planning and Design Manual (2003) offers a method to estimate the infiltration on the site, based on a local infiltration factor "I", which is applied to the available water surplus to determine the groundwater recharge for a given area with pervious cover. The methodology considers factors such as the soil type, topography, and vegetation to arrive at the infiltration factor that is then applied against the water surplus to provide an estimate of the amount of water infiltrating into the ground. The remaining water surplus is considered runoff.

Under the post-development conditions the infiltration factor is recalculated to account for changes in soil types, vegetation and topography after development, and the infiltration and runoff at the pervious land areas are recalculated. As the land after development will have impervious surfaces that prevent infiltration, such as building footprints, roads and parking areas, the pervious area available for infiltration is reduced. Furthermore, there is limited opportunity for evapotranspiration on these impervious surfaces, other than evaporative losses from wetting and ponding of water in shallow depressions (estimated at 10% of total precipitation), and so total precipitation is applied to these surfaces instead of the water surplus.

The discussions that follow focus on subwatershed FM1001 only, which is the main system passing through the Subject Property and is the subwatershed for which this EIR is specifically addressing. The adjoining subwatersheds FM1102 and FM1109 will behave in a similar manner though the magnitude of change under post-development conditions will depend in part on the proportion of development area in North Oakville compared to the total subwatershed area in these other subwatersheds.

4.4.2 Climate and Water Surplus

The inputs used for the water balance calculations are based on information provided by Environment Canada using climate data from the Oakville Gerard meteorological station (43°26'-N 79°42'-W), for the period 1990 to 2006. This climate station is considered to be more representative of climatic conditions at the Subject Property than the Hamilton Royal Botanical Garden (HRBG) station used in the NOCSS. The Oakville Gerard station is located approximately 7 km southeast of the Subject Property, whereas HRBG is located about 17 km southwest from the Subject Property, along the edge of Hamilton Harbour. Furthermore, the Oakville Gerard station is also not located immediately adjacent to the lake (as is the case of the HRBG) and therefore will experience less climatic lake effect potential.

Environment Canada inputted their climate data into a computer model (Johnstone and Louie, 1983) to provide actual evapotranspiration and water surplus inputs for soils with different water holding capacities (WHCs). Under existing conditions the WHC of the soils at the Subject Property and surrounding areas are estimated to be 200 and 400 mm (see Section 4.4.3.1). The Environment Canada data is presented in Appendix 4-7 and is also found on Table WB-1 within this same Appendix.

The Subject Property is located in an area of temperate climate with a mean annual temperature of 9.0 C and a mean annual precipitation of 819 mm. The potential evapotranspiration estimate that was provided by Environment Canada based on the Thornthwaite approach is 656 mm per year. The mean actual evapotranspiration in the vicinity of the Subject Property (pervious areas excluding existing imperviousness runoff contributions) is 607 and 644 mm respectively for soils with WHCs of 200 mm and 400 mm (see below) reflecting periods of soil moisture deficiency. The pre-development water surplus, the water available for

infiltration and runoff, is estimated to be 198 mm per year under existing conditions across the entire subwatershed (FM1001) and 209 mm per year on the portion of the Subject Property found within this subwatershed.

4.4.3 Inputs to Water Balance

Site specific inputs used in the water balance analysis are summarized in Table 4.8 and the inputs under the post-development case are explained below. The rationale for the pre-development and post-development inputs is discussed in Sections 4.4.3.1 and 4.4.3.2.

The infiltration factors and WHCs presented in Table 4.8 are considered to be the same across all subwatersheds for the purposes of this analysis. The increase in imperviousness across the entire subwatershed also includes increased imperviousness at developable lands owned by others in North Oakville as well as increased imperviousness at the Hanson Brick quarry north of Highway 407, which will expand over time.

Table 4.8 – Watershed Specific Inputs Used in the Water Balance – FM1001

Infiltration Factor Based on Land Conditions	Pre-Development	Post-Development
Topography	0.11	0.11 to 0.13
Soils	0.12	0.12
Vegetation	0.11	0.11
Thicker Topsoil/Amendment within Development Areas	-	0.05
Sum	0.34	0.34 to 0.41
Water Holding Capacity of Soils (mm)	Pre-Development	Post-Development
	200 and 400	100, 200 and 400
Site Areas for Use in Calculations (ha)		
Subject Property Only (within FM1001)	Pre-Development	Post-Development
Pervious	60.4	20.7
Impervious	0.0	39.7
Total Area	60.4	60.4
Entire Subwatershed, including Subject Property	Pre-Development	Post-Development
Pervious	379.4	296.5
Impervious	15.9	98.8
Total Area	395.3	395.3

Notes:

The individual infiltration factors presented in this table are **weighted averages** across the entire subwatershed (bcIMC and other developer owned lands south of Highway 407 as well as the lands north of 407).

Post-development areas are based on the conceptual development plan which is subject to revision. Because site grading is expected to reduce slopes in developed lands to the order of 2%, the infiltration factor for topography increases from

0.11 to 0.13 within the developable lands only. This also includes an assumption pertaining to increased future imperviousness at the Hanson Brick Quarry lands as that operation expands.

A proposed mitigation measure is the tilling/scarifying and compost amendment of the sub-soils with placement of thicker topsoil, which is modelled to promote additional infiltration. An increase in the “cover” infiltration factor by 0.05 for the landscaped areas within the developable lots was incorporated into the water balance analyses with mitigation.

Water Holding Capacity of Soils is based values presented on Table 3 from the MOE Stormwater Management Manual (2003).

4.4.3.1 Pre-Development Conditions

The surficial soils at the Subject Property and surrounding area within the subwatersheds, as described previously, are generally comprised of Clayey Silt Till, underlain by Shale Bedrock (exposed at surface in watercourses near to Dundas Street). As described in Section 4.3.2.1, the surficial soils are best classified as Clay Loam.

Soils mapping of the Subject Property presented on Figure 4W.6.1 in the NOCSS (included in Appendix 4-7) identifies most of the Subject Property as comprised of Oneida Clay Loam (Hydrologic Soil Group D ($i_{\text{soil}} = 0.10$), ref. Table 4W.6.2 from NOCSS), with Chinguacousy Clay Loam (Hydrologic Soil Group C ($i_{\text{soil}} = 0.20$)) mapped within the natural valley features at the site. The Chinguacousy Clay Loam comprises approximately 23.7 ha of the 109.7 ha area of Subwatershed FM1001 south of Highway 407, or about 21.6% of the total area. This results in a weighted average for the i_{soil} of 0.12 and this has further been assumed to be representative of the soil conditions across the three subwatersheds.

The existing vegetation at the Subject Property is predominantly agricultural with soy beans having been planted on site in 2013. Corn is also a major local crop grown within the subwatershed areas. The soil and vegetation conditions at the Subject Property lead to a soil water holding capacity of 200 mm and 400 mm as defined on Table 3 of the MOE Stormwater Planning and Design Manual.

The pre-development infiltration factor for the Subject Property and the main subwatershed (FM1001), “i”, is calculated at 0.34 based on the following:

- Topography is considered to be hilly, $i_{\text{topo}} = 0.11$ (average slopes across the three subwatersheds is approximately 3.0%)
- Soils are considered to be a clay loam from grain size analysis, $i_{\text{soils}} = 0.12$
- Cover is predominantly cultivated land with some forest cover, $i_{\text{cover}} = 0.11$

The pervious surface area of the Subject Property within FM1001 under existing conditions is approximately 60.4 ha. Approximately 45.4 ha of this area is situated within future developable lands and will be changed following development; the remaining 15.0 ha will not be developed. Most of this 15.0 ha area (approximately 9.5 ha) will essentially remain untouched, other than from works such as road crossings and sewer outfalls. It is proposed to realign the watercourses entering the Subject Property along the north (Highway 407) property line. The central and eastern watercourses to FM1001 (Reaches 14W-14 and 14W-13) are proposed to be diverted to the west and then southerly along the property line with the Arch-Diocese lands (proposed Reach 14W-22) and into Reach 14W-12A upstream of where it joins the main channel (Reach 14W-16). Reach 14W-11A is proposed to be diverted easterly along the north property line and then to the south (proposed Reach 14W-23) to the point where it currently joins Reach 14W-11 before exiting the Subject

Property. The proposed channel realignments are shown on Figure 4.7. The approximate area of the FM1001 channel realignments (within FM1001) is 4.1 ha³⁷.

4.4.3.2 Post-Development Conditions

Future development of the Subject Property and adjacent development lands from agricultural to employment land use will change the evapotranspiration, runoff and infiltration conditions of these lands by adding hard surfaces such as roads, driveways, parking lots, sidewalks and roofs that are effectively impervious. For the purposes of the water balance analyses, the total area covered by impervious surfaces for this type of development is estimated at about 88%³⁸ over the 45.4 ha of developable area. This is equivalent to about 66% imperviousness over the full 60.4 ha of site area (within Subwatershed FM1001) with the 15.0 ha of “natural” area at 0% imperviousness included.

Post development conditions on lands northwest of Highway 407 are anticipated to remain essentially the same as the pre-development situation. These lands are currently designated Protected Countryside (Greenbelt Plan, 2005) and Agricultural in the local and Regional Official Plans. The post-development water balance on a subwatershed basis (FM1001) includes allowance for a minor increase in imperviousness in the lands northwest of the 407 that reflect a projected increase in size of the Hanson Brick Tremaine Quarry over time.

It is also noted however, that runoff from pervious areas surrounded by streets within the developed lands will eventually be directed to the stormwater management system, as it will drain onto the road network and from there into the storm sewer system. The exception would be the runoff from pervious areas abutting and draining to natural features or runoff conveyed to these features by means of mitigation such as infiltration swales.

Under the post development condition, the soil composition is expected to remain classified as a Clay Loam after site grading, as soils used for fill are expected to be obtained from the Subject Property, and the soils exposed by cutting activities are anticipated to be similar to the existing surficial soils. While compositionally the soils will remain unchanged at finished grades within the developable limits, the infiltrative benefits of weathering and fracturing will have been lost through the cut and fill activities. The vegetation following development is anticipated to be comprised predominantly of short-rooted vegetation such as grassed lawn in landscaped areas, with natural vegetation remaining as-is elsewhere where these areas are to remain undisturbed or with new plantings in areas to be created through the proposed channel realignments.

Based on Table 3 from the MOE Stormwater Management Manual (2003), Clay Loams with short rooted vegetation such as lawns are shown to have a WHC on the order of 100 mm. Therefore, under the post-development scenarios, the local climate data provided by Environment Canada for soils with a WHC of 100 mm was used to estimate the future water surplus for the developed areas of the Subject Property and surrounding development lands. With a WHC of 100 mm, the Actual ETR is reduced from 607 and 644 mm/year (pre-development conditions) to 536 mm/year at areas to be landscaped. The reduction in Actual ETR across pervious areas of the developed lands results in an estimated water surplus of about 229

³⁷ The 4.1 ha is the approximate area of the proposed channel where cuts below existing grade will be required, necessitating the removal of the upper weathered soils within this area.

³⁸ Based on 39.8 ha of developable lots and SWM's at 90% imperviousness, and 5.7 ha of internal roads and future transit way at 70% imperviousness.

mm/year compared to the pre-development surplus of 209 mm/year, over pervious areas of the property. These changes apply to the future landscaped grounds within the development lands only, or to about 5.7 ha of the total 45.4 ha of lands to be developed within the 60.4 ha total area within FM1001. On a subwatershed basis, the estimated water surplus (pervious area) rises from 198 mm/year to about 209 mm/year.

4.4.4 Water Balance

Water balance analyses were performed for the entire Subject Property area, and for the three subwatersheds that are partially located within the Subject Property. As noted earlier, discussions will be focussed upon subwatershed FM1001. Water balance analyses for the other two subwatersheds FM1109 and FM1102 are also presented in Appendix 4-7 for completeness. In addition, a pre-development water balance analysis was carried out for a portion of the FM1109 subwatershed that passes through the east corner of the Subject Property to compare observed watercourse base flows against predicted base flows from these analyses (identified on Figure 4.2). This is discussed in Section 4.4.4.1.1.

4.4.4.1 Pre-Development Water Balance

Under pre-development (existing) conditions the Subject Property is considered pervious over its full area (e.g., 60.4 ha within FM1001). The water surplus under these conditions was calculated as 209.4 mm/year (see Section 4.4.2) and the infiltration factor was calculated to be 0.33. Therefore, pre-development infiltration across the full property area and leading towards the watercourses of FM1001 is estimated at about 69.3 mm per year (41,902 m³/year), which is consistent with the reported infiltration values for these types of soils. Most groundwater recharge occurs during the spring melt period when soil moisture content is high. The remaining 140.1 mm per year (84,670 m³/year) would be available for surface run-off, most of which occurs during the spring melt period.

On a subwatershed basis, the predevelopment water balance indicates that FM1001 will receive 263,546 m³/year of infiltration (66.7 mm/year equivalent) and 637,237 m³/year (161.2 mm/year) of runoff. The subwatershed volumes reflect pre-existing imperviousness within the entire subwatershed (e.g., Highway 407, Hanson Brick quarry).

The major contribution of water to the subwatershed occurs, as expected, in the late winter and spring. Water surpluses during the majority of the growing season (June through October) are essentially zero as the ETR remains high and the soil moisture goes into a deficit. Soil moisture starts to become replenished in September/October.

The pre-development water balances for the Subject Property and the overall subwatershed are summarized on Table 4.9 and Table 4.10 (in Section 4.4.4.2); with the detailed, monthly water balance calculations presented in Appendix 4-7 on Table WB-2-FM1001.

4.4.4.1.1 Base Flow Comparisons to Pre-Development Water Balance

During the course of the site investigations, estimates of surface water flows were made at selected locations in the watercourses of FM1001 and FM1109 that passed through the Subject Property. No flow estimates were attempted at FM1102, as there was no defined channel or any measurable flow at this part of the Subject Property.

One of the requirements of the EIR and FSS TOR is to validate the pre-development water balance where possible. The water balance analyses provide monthly estimates of infiltration and runoff. For purposes of this comparison, we have assumed that monthly infiltration calculated by the water balance is representative of base flow conditions in the watercourses less 10% to allow for recharge of the deeper shale bedrock aquifer, leaving 90% of the infiltration calculated by the water balance available for base flow to the creeks.

Table 4.7 presents the watercourse base flow estimates against the water balance calculated infiltration volumes (90% as noted above), converted to equivalent flow rates at the downstream edges of the watercourses. For FM1001 (West Branch of Fourteen Mile Creek) this is at SG-2 by Dundas Street (bottom end of reach 14W-12). For FM1109, (Central Branch of Fourteen Mile Creek) only a portion of a contributing watercourse passes through the Subject Property (Reach 14W-11 and Reach 14W-11A). The upgradient portion of this Reach was identified on Figure 4.2 and a pre-development water balance analysis was carried out for this small portion of FM1109 (see Table WB-2-14W-11A in Appendix 4-7).

The water balance is based upon averages from a 16-year weather record and the calculated monthly average infiltration is being treated as a proxy for base flows to the watercourses. These monthly averages were then compared to measured estimates of channel flows (with inherent inaccuracies) that are a function of real (non long-term averaged) weather patterns. Notwithstanding the above, as can be seen from Table 4.7, the predicted stream flows and measured stream flows are in good agreement when measurements were possible without influence from rainfall or snow-melt events (e.g., February 17-18, 2011), and generally of the same order of magnitude. Thus it can be concluded that the water balance methodology used in this study is a simple, yet valid, model of the hydrogeological system in which the Subject Property is situated.

4.4.4.2 Post-Development Water Balances

In addition to the pre-development water balance, two post-development water balance scenarios were examined. The first of these scenarios examined the worst case situation with no mitigation measures applied at the Subject Property and the second scenario examined the improvements from the worst case scenario with mitigation measures employed. The post-development scenarios were compared against the pre-development case. The results for the water balance calculations are described below and summarized on Table 4.9 and Table 4.10. The detailed calculations are presented on Tables WB-2-FM1001 through WB-4-FM1001 located in Appendix 4-7.

The following assumptions have also been made to estimate the post-development water balance including recharge mitigation measures:

- Total imperviousness of the developable lots is assumed as 90%, which reflects the Town of Oakville's planned land use and maximum lot coverage requirements for more intensive employment development. Imperviousness of the road allowances with grassed boulevards is assumed at 70%, resulting in weighted imperviousness of 88%;
- There is no infiltration occurring on hard surface areas and evapotranspiration is significantly lower than that under pre-development conditions (10% as evaporation only), due to rapid runoff of precipitation;

-
- Runoff from the road network, as well as roof areas not directed to mitigation is discharged directly into the storm sewer network³⁹;
 - The characteristics of the native soils and bedrock limit the choices of suitable measures to infiltrate water into the ground at both the Subject Property and the surrounding areas. The data collected over the course of this investigation indicates the upper, weathered zone of the till soils has enhanced (secondary) permeability from fracturing. The most promising locations for infiltration-promoting mitigation measures will therefore be within areas where the native soils are to be left undisturbed by construction activities;
 - The imperviousness of the Subject Property after development is calculated at about 66% (39.7 ha) of the total 60.4 ha site area found within subwatershed FM1001. Of this 39.7 ha, roofs are assumed to account for approximately 40% of the total imperviousness or about 16.0 ha. Runoff from the roof areas may be suitable for use in mitigation measures depending upon the nature of the businesses that eventually are developed (e.g., businesses with zero to low emissions versus heavy industries with the potential to release particulate matter that collects on roofs). For the purpose of this analysis the runoff collected on the roofs has been considered usable for mitigation measures, though as noted above the opportunities to mitigate in this hydrogeological environment are limited;
 - Landscaped areas within the developable areas and the newly created natural environment areas associated with the channel realignments will have the newly exposed sub-soils tilled/scarified/ripped to 500 mm depth and amended with compost (resulting in organic content of 8 to 15% by weight / 30 to 40% by volume) prior to placing approximately 0.25 m of topsoil. This increased thickness of organic soils with additional void space will retain a greater proportion of precipitation and/or runoff over these pervious areas and therefore promote additional infiltration. Within the developable lots, this activity would be deferred to the time of individual lot development once the proposed layout of buildings and paved areas within the individual lots are known;
 - Infiltration works such as infiltration swales constructed along the periphery of areas retained in their natural state are considered viable (see Figure 4.7). By carefully constructing these measures within the undisturbed natural environment areas, they are anticipated to be capable of recharging a portion of the relatively clean roof runoff that can be directed to these swales, provided the existing surficial fractured and weathered zone of the native till soils remains intact. This will require using specified construction techniques to minimize smearing of the walls and bases of these swales, which would dramatically reduce the potential effectiveness of these measures. Constructing infiltration swales within portions of the Subject Property with engineered fill or deep cuts into unweathered and relatively unfractured soils will not be as effective for mitigating infiltration, but, if connected to infiltration swales along the perimeter of the natural features, will provide temperature moderation to the roof runoff;
 - Construction of small off-line open water wetlands within the proposed valley realignment (Reach 14W-22) that will convey the central and eastern reaches (Reach 14-W-14 and Reach 14W-13) into Reach 14W-12A and will be recharged by flood events will provide for some measure of additional

³⁹ A portion of the runoff from roofs at the central part of the Subject Property will be diverted to the small channel (14W-12A) located to the northwest of the central SWMP to maintain flows across that section of channel (see Section 7.4).

infiltration, though this will be limited somewhat by the fact that such ponds will be constructed alongside the realigned channels at lower elevations where groundwater discharge from the underlying bedrock is anticipated; and,

- Additional mitigation measures, such as vegetative swales at parking areas, landscaped infiltration ponds/wetlands, green roofs, cistern systems for grey-water use and/or landscape irrigation, etc. are specific to lot configurations, intended use, building design and so forth and should be examined during later stages of detailed design or at the time of building permit applications. For example, construction of landscaped ponds/wetlands would not appear feasible on a lot with a large warehousing facility and extensive parking facilities, but may be feasible at a lot housing a corporate headquarters facility. As such specific measures on a lot by lot basis are not identified at this time and they have not been included in the post-development water balances.

4.4.4.3 Post-Development Water Balance with No Mitigation

This first scenario, examines the worst-case condition, where there will be no mitigation measures incorporated. This assumes that all impervious area runoff (less impervious surface losses to evaporation), including roof runoff, is conveyed directly into the stormwater management system. This scenario considers that groundwater infiltration is supplied only by precipitation that falls upon pervious areas. The potential maximum loss of infiltration from the proposed development was calculated to provide a worst-case estimate of the potential impacts on infiltration due to the introduction of hard surfaces. Detailed monthly water balance calculations may be found on Table WB-3-1001 in Appendix 4-7.

Table 4.9 – Pre and Post Development Water Balance – No Mitigation

Parameters	Pre-Development		Post-Development		Change	
	mm/year	m ³ /year	mm/year	m ³ /year	m ³ /year	%
Subject Property Only (within FM1001)						
Precipitation	819.0	495,004	819.0	495,004	0	0.0%
Total AET	607.5	367,167	201.2	121,584	-245,583	-66.9%
Evaporative Losses at 10% Precipitation	0.0	0	53.9	32,552	32,552	N/A
Infiltration (MOE Methodology)	69.3	41,902	26.4	15,969	-25,932	-61.9%
Runoff (MOE Methodology)	140.1	84,670	536.8	324,428	239,757	283.2%
Entire Subwatershed, incl. Subject Property						
Precipitation	819.0	3,237,507	819.0	3,237,507	0	0.0%
Total AET	585.4	2,314,021	455.8	1,801,628	-512,393	-22.1%

Evaporative Losses at 10% Precipitation	3.3	13,022	20.5	80,923	67,901	521.4%
Infiltration (MOE Methodology)	66.7	263,546	53.0	209,312	-54,235	-20.6%
Runoff (MOE Methodology)	161.2	637,237	287.8	1,137,703	500,466	78.5%

Notes:

Evaporative losses are losses of precipitation through simple evaporation on impervious surfaces (such as from ponding at puddles).

As indicated in Table 4.9 under this worst-case scenario, the water balance method estimates a 62% reduction in groundwater infiltration from the Subject Property falling within subwatershed FM1001 while on a total subwatershed basis the reduction in infiltration is estimated at about 21%⁴⁰. On-site runoff contribution to the watercourse system is calculated to increase about 283%, or by 79% on a subwatershed basis. The change to the local groundwater recharge function assumes that all runoff from hard surfaces is conveyed to the storm sewer network. Some additional loss of groundwater flow may occur due to foundation drains and permeable backfill surrounding services, however, most of recharge loss is anticipated to be due to rapid runoff from impervious surfaces.

4.4.4.4 Post-Development Water Balance with Mitigation

A post-development water balance analysis was carried out with mitigation measures. The choice of mitigation measures was constrained by site conditions (e.g., site soils, location and orientation of natural features) and design constraints (e.g., site grading, requirements for connections to adjacent future developments). The locations of the proposed mitigation measures examined under this scenario are shown on the conceptual plan of development presented on Figure 4.7.

The improvements to recharge and runoff contributions of the following mitigation measures were examined:

- A portion of the roof runoff is collected and directed into infiltration swales located at the rear of the lots at the edge of the buffers to the NHS. Locating these swales immediately adjacent to the NHS will ensure that the functionality of these swales will not be compromised because of site grading activities on the Subject Property. These swales are also proposed alongside the “natural” areas that are to be created because of the proposed watercourse diversions. The surficial soils in those areas are expected to be deeper, less fractured soils exposed by cutting the grades, and the proposed tilling/scarifying and addition of compost amendments and topsoil within these newly created areas will provide additional infiltration potential. The locations of infiltration swales will need to be confirmed at detailed design as other factors such as final site grades must be considered in the siting of these facilities. Figure 4.8 presents the conceptual design of the proposed infiltration swales. As these swales are not designed for stormwater management purposes, they do not have to adhere strictly to the criteria specified by the MOE Stormwater Planning and Design Manual (2003) in particular a requirement that they drain in 24 to 48 hours.

⁴⁰ The overall subwatershed calculations includes, in addition, to the effects identified at the Subject Property, effects from development on lands owned by others, and from the proposed expansion of the Hanson Brick Quarry lands to the north of Highway 407.

- Published research studies by Toronto and Region Conservation Authority (Young, et al, 2013) and Credit Valley Conservation (2014) of infiltration trenches and galleries constructed in low permeability glacial tills within the Greater Toronto Area indicate that these LIDS can be effective at infiltrating water into the ground. Our review of these studies indicates that infiltration rates on average of the order of 3 mm/hour (equivalent to a percolation rate T-Time of 200 minutes/cm) have been measured at trenches and galleries constructed at sites located in Richmond Hill, Bolton, Brampton and Mississauga (2 sites). The grain size distributions of the till at these sites where reported are similar in nature to the till found at the Subject Property. The water balance calculations with respect to the infiltration swales are therefore based on this 3 mm/hour rate;
- Landscaped areas within the development lands and the newly created natural environment areas will include thicker topsoil and 0.5 m of tilling/scarifying/ripping of the sub-soils with compost amendments to promote additional infiltration. To model this effect in the water balance, an increase in the “cover” infiltration factor by 0.05 (from 0.10 to 0.15) for the landscaped areas was considered appropriate, putting this value mid-way between the factors for cultivated lands (0.10) and forested areas (0.20);

Small off-line open water wetlands are proposed within the valley of the westernmost of the two proposed channel realignments (Reach 14W-22) to address removal of wetlands in Reach 14W-13 and Reach 14W-14, as well as, the wetland and open water function of the Farm Pond (Reach 14W-14A). These wetlands would be maintained through storm flood events (surface flows) and while they have the potential to provide the additional infiltration to the shallow system, the post-development water balance does not account for any infiltration benefits from these off-line wetlands as the static water level within the underlying bedrock ranges from about 155 to 150 masl along the proposed channel realignment, and the invert of the realigned channel profile will range from about 152 to 149 masl. In order for there to be potential for vertical infiltration through the bottom of these off-line wetlands, the design water levels in these ponds would need to be higher than that of the groundwater in the bedrock.

Notwithstanding the above, these wetlands can be expected to provide some level of infiltration enhancements during the drier summer season when shallow groundwater levels in the valleys have declined somewhat due to the effects of evapotranspiration. Contributions to groundwater infiltration from these measures are not however included in the water balance calculations as a conservative assumption and the potential volumes of infiltration will also be relative to the final design sizing of these features.

Additional enhancements to the post-development infiltration at these development lands may be realized through the promotion of additional infiltration measures within the development such as wet (landscaped) ponds, bio-retention facilities, vegetated swales, etc. The feasibility of such measures is; however, a function of the individual lot configurations, proposed lot uses and site design opportunities. The infiltration contributions from these potential opportunities are anticipated to be minor because these features will likely be constructed within the limited available pervious areas. Infiltration from these undetermined mitigation measures are therefore not accounted for in the water balance calculations.

Table 4.10 summarizes the results of the water balance assessment for the Subject Property including pre-development and the post-development conditions with the implementation of mitigation measures described above. The detailed calculations are found on Table WB-4-FM1001 in Appendix 4-7.

With the proposed mitigation, the water balance method estimates the post-development groundwater infiltration at the Subject Property within FM1001 will be balanced, which is a significant improvement from the 62% loss calculated under the worst-case scenario and in consideration of the low permeability soils and proposed lot coverage at the Subject Property. This balancing of the post-development infiltration with the pre-development level exceeds the expectations of NOCSS (Sections 5.5.2, 7.4.4.2). The increase in post-development runoff generated at the Subject Property for the mitigated scenario is reduced from about 283% to 252%. Volumetrically, approximately 25,955 m³/year of potential runoff is redirected into infiltration through these proposed mitigation opportunities compared to the unmitigated scenario.

Table 4.10 – Pre and Post Development Water Balance – With Mitigation

Parameters	Pre-Development		Post-Development		Change	
	mm/year	m ³ /year	mm/year	m ³ /year	m ³ /year	%
Subject Property Only (within FM1001)						
Precipitation	819.0	495,004	819.0	495,004	0	0.0%
Total AET	607.5	367,167	201.2	121,584	-245,583	-66.9%
Evaporative Losses at 10% Precipitation	0.0	0	53.9	32,552	32,552	N/A
Infiltration (MOE Methodology)	69.3	41,902	69.5	41,923	21	0.1%
Runoff (MOE Methodology)	140.1	84,670	493.7	298,474	213,804	252.5%
Entire Subwatershed, incl. Subject Property						
Precipitation	819.0	3,237,507	819.0	3,237,507	0	0.0%
Total AET	585.4	2,314,021	455.8	1,801,628	-512,393	-22.1%
Evaporative Losses at 10% Precipitation	3.3	13,022	20.5	80,923	67,901	521.4%
Infiltration (MOE Methodology)	66.7	263,546	63.7	251,708	-11,839	-4.5%
Runoff (MOE Methodology)	161.2	637,237	277.1	1,095,307	458,070	71.3%

Notes:

Evaporative losses are losses of precipitation through simple evaporation on impervious surfaces (such as from ponding at puddles).

On a total subwatershed basis (FM1001 only), and where opportunities are present, using similar mitigation measures on development lands owned by others, about 42,395 m³/year of runoff may be redirected into the ground as infiltration. Mitigation at the Subject Property and development lands owned by others to the west is calculated to reduce overall infiltration losses by about 4.5% of the unmitigated totals⁴¹.

⁴¹ On a subwatershed basis, the total infiltration reduction across the development lands south of the 407 is calculated at approximately 47,300 m³/year without any mitigation and with mitigation, at about 4,900 m³/year on lands owned by others to the

4.4.4.5 Discussion of Water Balance Results

The preceding tables and discussion present the potential impacts and results of mitigation measures on the post-development water balance for the Subject Property within subwatershed FM1001. From the tables it can be seen that with the proposed mitigation measures it can be anticipated that impacts to recharge across the Subject Property can be fully mitigated, meeting one of the stated goals of NOCSS (to protect groundwater quantity, Section 7.4.4.2), even with the Subject Property situated within a setting where the predominant surficial soil is low permeability clayey silt till (confirming the soil conditions expected by NOCSS, Section 4W.3.2.2, Section 5.5.1, Section 5.5.2). Clayey silt till is not considered an ideal soil for constructing infiltration measures, and with an infiltration rate of 3 mm/hour as demonstrated from local conservation authority pilot projects, this balance is achieved on-site through an extensive infiltration swale network, totaling about 2.6 km in length⁴². We caution that construction activities at the Subject Property as well as placement of compacted earth fill will serve to reduce the native infiltration capacities of this clayey silt till soil and that care during construction must be taken in the immediate area of the proposed mitigation measures to prevent this from occurring.

The infiltration swales must be constructed along the edges of the watercourse valleys where weathering and stress relief of the low permeability deposits has resulted in a highly fractured upper soil zone conducive to recharge and are considered to be the most opportune locations for installing mitigation measures for infiltration. These areas will not be greatly affected by site grading which would lead to scraping and compaction and which would degrade or remove the ability of these low permeability soils to transmit water through the weathered zone (e.g., fractures)⁴³. As noted above, specific construction limitations will also be required for these measures to be successful. Heavy equipment must not be permitted to travel across the areas proposed for these devices. Construction of the swales can only be done in dry weather to avoid remoulding the soil that would effectively line the swale sides and base with an impervious smeared layer. Manual scraping and removal of smeared soils from the sidewalls and base of the swales to expose the natural fracturing should be contemplated.

The potential for effective mitigation measures elsewhere across the Subject Property is affected by the proposed site coverage where a conservative 90% imperviousness ratio has been assumed on the development lots of the Subject Property. This constraint leads to reduced lot level perviousness and reduced infiltration potential as there is simply much less available area in which to infiltrate large volumes of water. Reducing lot coverage, which would result in more pervious area and therefore higher infiltration

west of the Site (increasing the width of the infiltration swales in these lands from 1.1 m to about 1.5 m is one possible way to lead to a calculated balance for these lands). This is a 90% improvement in the total calculated infiltration losses from the redevelopment of these future employment lands (Subject Property and lands owned by others). The above stated volumes exclude infiltration reductions assumed and accounted for in the water balance from the future expansion of the Hanson Brick Quarry lands to the northwest (calculated reduction of about 6,900 m³/year at the Hanson Brick site).

⁴² 1,680 m length on the Subject Property, 950 m length on the lands owned by others to the west, within subwatershed FM1001 only.

⁴³ Excluding the proposed re-alignments that are to be constructed within unweathered till soils exposed through cuts. The exposed sub-soils within these areas are recommended to be tilled/scarified/ripped to a depth of 0.5 m and amended with compost to their improve infiltration capacity. Placement of 0.25 m of topsoil in addition to this will further provide additional moisture retention.

potential, is however in conflict with the Town's planned land use and maximum lot coverage requirements (more intensive employment development).

4.4.4.6 Discussion of the Potential for Base Flow Reductions to Watercourses

The surficial soils across the entire watershed system are comprised of low permeability Halton Till and as a result, the local stream systems receive a little over two-thirds of their total water from surface runoff with the balance derived from groundwater (based on the water balance and validated by stream flow measurements made at the Subject Property). The majority of the groundwater inputs to these watercourses is derived from the shallow till zone, and almost 100% of this contribution occurs primarily in the period of November to May when the entire shallow system, including upgradient reaches of the channel are saturated and contributing water to the streams. The NOCSS recognizes that minimizing changes (reductions) in infiltration will be difficult given the low permeability of the surficial soils found in North Oakville, estimated in the NOCSS as up to a 60% reduction in infiltration without mitigation within development limits (ref. Section 5.2.2 of the NOCSS).

The proposed mitigation measures are concentrated along the perimeter of the natural environment areas, which focuses this infiltration towards the watercourses where it will emerge from the embankments and mimic shallow groundwater discharge. In order to allow a uniform and sustained level of baseflow to be maintained in the Reach 14W-12A channel, a Redside Dace identified watercourse, additional mitigation measures will be incorporated. During Interim Development Phase 1B, flows from rooftops of the proposed buildings (2.56 ha) together with runoff from the part of the existing area (7.68 ha) will bypass the proposed SWM Pond 3 and be diverted directly to Reach 14W-12A by a storm sewer system. Under Interim Phase 2 and the Ultimate Development Conditions, flows from rooftops of the proposed buildings (5.12 ha) will be diverted to Reach 14W-12A directly in order to allow a uniform and sustained level of baseflow to be maintained in the subject receiving watercourse. Please refer to Section 7.4 (Development of GAWSER Hydrological Model) and Section 7.6 (Hydrologic Flow Regimes Analysis) for more details.

The development, with the incorporation of mitigation measures described above will result in a balance in infiltration across the Subject Property area for FM1001. This infiltration balance is calculated for the Subject Property as a whole over the year. As illustrated on Figure 4.9, the predicted monthly distribution of the infiltration at the Subject Property leads to potential for base flow increases to the three watercourses after development (Reach 14W-12, Reach 14W-22 (realigned) and Reach 14W-16) over a 7-month period (June to December, by between 18 to 48 litres/minute) along with potential for base flow reductions at the during a 3-month period (February to April⁴⁴). The daily base flow reduction over this 3-month time period is calculated to range from 67 to 128 litres/minute⁴⁵ across the combined three watercourse at the Subject Property. These are considered minor reductions as:

- The watercourses will continue to receive contributions from the upgradient areas (north of Highway 407), which are not planned for urban development and are not expected to undergo major land use changes, with the exception of the expansion of quarrying at the Hanson Brick property to the northwest. These upgradient areas are on the order of 2.6 times the catchment area of the future

⁴⁴ Calculated infiltration is approximately balanced in January (97%) and May (96%) at the Subject Property.

⁴⁵ This is based on daily averages calculated by the monthly water balance for each of the 3 months.

development lands south of Highway 407⁴⁶ and therefore these reductions will be small compared to the overall flow received from upgradient land areas. These are calculated by the monthly water balance to range between 800 and 1,200 litres/minute of upstream base flow during the same February to April timeframe. The calculated base flow reductions at the Subject Property also occur over the part of the year where the natural system is fully saturated and thus upgradient flow contributions will be at their greatest during the year; and,

- Baseflow at the lower reaches will also be further augmented at watercourse channel 14W-12A from runoff from about 5.12 ha of rooftop area under the ultimate built out condition. This water will enter the watercourse system to the north of the central SWM Facility (via Reach 14W-12A).

Figures 4.9 and 4.10 graphically presents the monthly and cumulative infiltration calculated using the water balance methodology for the pre-development and post-development with mitigation scenarios across the FM1001 within the Subject Property (Figure 4.9) and for the overall subwatershed (Figure 4.10). As discussed in Section 4.3.3 of this report, approximately 90% of the infiltration is considered to flow laterally towards the watercourses providing base flow, the balance recharging the shale bedrock. Figure 4.9 shows that the calculated monthly infiltration under post-development conditions at the Subject Property ranges between 53 to 64% of the pre-development values between February and April and for the overall subwatershed during this same time interval, from 83 to 86%. Infiltration both on the Subject Property and for the overall subwatershed over the period between June and December is calculated to be higher than the pre-development conditions and may lead to a slight lengthening of the period when baseflow contributions to the watercourses do occur at the Subject Property. The net effect is that overall balance is achieved and that additional infiltration will be directed towards the on-site watercourses during the summer and fall months when the channels have little to no baseflow than currently is the case. During the wetter late-winter and early-spring periods, although the calculated post-development infiltration is reduced from the existing condition, this also occurs during the time of the year when the area is expected to be fully saturated from snowmelt and other runoff. The net effect to the lower reaches of FM1001 is considered positive given the potential for additional water during the summer and fall months.

FM1109 Reach 14W-11 and Reach 14W-11A that traverses the Subject Property at the northeast corner is interpreted to lose water to the ground over much of the year, because of the nearby influence of a buried bedrock valley located to the east. Nonetheless, the water balance predicts an overall calculated increase in infiltration at the Subject Property within this subwatershed of approximately 45% (refer to Tables WB-2-1109 and WB-4-1109 in Appendix 4.7). During the period between February and April, the potential reductions in shallow base flow contributions to this reach are calculated between 4 to 13 litres/minute. We note that this is an overestimate as data collected at the site indicate this stream generally loses water into the ground.

As identified earlier in this report, the existing channel reaches for the main and central watercourses of FM1001 (Reach 14W-16, Reach 14W-14, and Reach 14W-12) are below the interpreted bedrock groundwater levels and so there is minor upward flow of groundwater from the underlying bedrock and intervening till soils towards these channels. These bedrock contributions are small and are insufficient to maintain flow in this watercourse during the summer months (watercourses were observed in dry to pooled

⁴⁶ Future development lands to the south of Highway 407 total approximately 109.7 ha (28%) of the total FM1001 subwatershed area.

conditions during both the 2009 and 2010 summer seasons). The bedrock contributions are; however, expected to remain consistent after development.

The proposed realignment of Reach 14W-13 and Reach 14W-14 into a combined Reach 14W-22 alongside the western property line of the Subject property will not result in reduced groundwater inputs from the bedrock into this watercourse system. Under existing conditions, Reach 14W-13 is not interpreted to receive groundwater inputs from the bedrock except at its point of convergence with Reach 14W-14 as its' channel inverts decline from approximately 154 to 149 masl while the interpreted bedrock groundwater elevations (spring conditions, see Figure 4.5) decline from roughly 153 to 148 masl. Reach 14W-14 on the other hand is interpreted to receive bedrock groundwater inputs over its entire on-site length down to the point where it joins with Reach 14W-12A. The channel invert declines from about 154 masl at the northwest corner of the Subject property to about 148.5 masl where it joins up with Reach 14W-12A, while the interpreted bedrock groundwater drops from 155 to 148 masl over this same distance. On average, the groundwater levels at the bedrock are interpreted at between 0.5 and 1.0 m above this Reach's channel bottom during the spring condition. Reach 14W-14's total channel length (existing) is approximately 801 m (see Table 6.24).

Under post-development conditions, the proposed Reach 14W-22 channel inverts will decline from approximately 153.8 masl at the northwest corner of the Subject Property down to about 149.3 masl where it converges with Reach 14W-12A upstream of that reach's confluence with Reach 14W-12. The interpreted bedrock groundwater levels along the proposed channel alignment drops from about 155 to 149 masl. This places the spring bedrock groundwater level, or from between 0.4 m below to about 1.9 m above the proposed channel invert, at an average of about 1.1 m above the channel. The total length of channel interpreted to be below the bedrock groundwater is 1,143 m, which includes 157 m length of Reach 14W-14 that is to remain undisturbed at the upstream end, a 206 m length of proposed Reach 14W-21 (western portion) that diverts upstream flows from Reach 14W-13 into this channel, and the 780 m length of proposed Reach 14W-22 (see Table 6.24).

Therefore, considering the length of proposed channel below the bedrock water table (1,143 m) is about 43% longer than the existing length at Reach 14W-14 (780 m), and the upward head differential is also greater at the proposed channel (-0.4 to +1.9 m, +1.1 m average) compared to +0.5 to +1.0 m, bedrock groundwater contributions into the proposed channel realignment should exceed the existing condition. This is in addition to the calculated infiltration balance in the shallow system with the use of infiltration swales.

As described elsewhere, Reach 14W-11 and Reach 14W-11A, located in watershed FM1109, loses water into the ground. The existing channel bottom is also located between approximately 5 and 7 m above the interpreted bedrock groundwater levels and therefore does not receive any bedrock inputs from within the Subject Property. The proposed realignment (Reach 14W-23) along the north and east property lines will not alter these conditions and therefore no change is expected in the bedrock contributions to this reach after the realignment.

4.4.4.7 Potential Groundwater Seepage Area Near Upper End of the Farm Pond

As discussed in Section 4.3.2.4, there is potential for minor groundwater inputs beyond the upstream end of the Farm Pond in the vicinity of monitor MP-24 as our interpretation of the data indicates this seepage enters Reach 14W-12A to the northwest of the Farm Pond and the topographic channel high between MP-24 and the Farm Pond, meaning that this seepage does not flow to the Farm Pond except during runoff events when

the channel flows temporarily raise the Farm Pond levels. The data collected to date at this monitoring nest indicates that the groundwater levels at the two mini-piezometers are closely matched to the surface water level fluctuations of the Farm Pond and are considered to be influenced by precipitation and the changes in surface water levels at the Farm Pond that are induced by these precipitation events. The gradients at this location vary between upward and downward with the water levels at the mini-piezometers being on average, 0.001 and 0.004 m lower than the water levels recorded at the Farm Pond (MP-24S and MP-24D respectively). The upstream end of the Farm Pond therefore is located nearby to an area where groundwater gradients to the water course system are predicted to change from upward (i.e., to the northwest towards MMM-09-10) to downward (the monitors around the Farm Pond to the southeast). The top end of the central SWMP is to be constructed near this area (see Figure HG-4, Appendix 4.5), and the limits of the Farm Pond work is located beyond the predicted extent of the minor seepage area which extends about 35 m east of MP-24.

While these temporal groundwater inputs are predicted to be quite small, should they be impacted by the construction of the SWM facility, they will be replicated in the post-construction condition. A 40 m length of infiltration swale is proposed to the north of the central SWM facility and is expected to easily make up for any losses of minor groundwater discharge presently found at the upstream end of the Farm Pond in the vicinity of MP-24. Infiltration input from this length of trench is calculated at 620 m³/year of water⁴⁷.

An estimate of the groundwater discharges to the edge of the watercourse (Reach 14-12A) within the SWM facility Block⁴⁸ was made using a simple Darcy calculation:

$$Q = kiA \text{ (m}^3\text{/year)}$$

Where:

K = bulk hydraulic conductivity (m/year) = 94.6 m/year (3×10^{-6} m/sec, Section 4.3.3);

i = hydraulic gradient (dimensionless, m/m) = 0.0332 (average of all upward gradients relative to the Farm Pond recorded to date at MP-24D, excludes all negative (downward) gradients in the calculation);

A = Area of seepage face (m²) = 70 m² (assumed 70 m total length with 1 m seepage face along banks of Farm Pond and channel); and,

It is assumed that upward seepage potential is present over a 6 month time period

For these calculations we have assumed a 1 m seepage face over 70 m length of shoreline (35 m either side of Farm Pond/channel to the east of MP-24), an area that could be affected by the construction of the central SWM facility. Monitoring station MP-24, as noted, has gradients that vary between inward and outward, and therefore seepage potential to the east of this monitor is expected to be even less as the lands transition to the those with a downward gradient. We have also only considered the time when upward seepage potential may exist (assumed 6 months) and have applied the average of all upward gradients recorded to date (0.00

⁴⁷ Pro-rated based on annual calculated infiltration of 25,129 m³/year over 1,620 m total proposed length of trenches (Table WB-4-1001).

⁴⁸ The area to the west is designated as NHS and will not be disturbed and thus is not considered in the calculation. As described in Section 4.4.4.6, groundwater base flow contributions from the removal of Reach 14W- 14 is predicted to be increased by the creation of Reach 14W-22 which will be constructed deeper into the bedrock water table, and results in a longer length of channel that intercepts the bedrock groundwater table.

to 0.215, average 0.0332) over a 6 month period. The hydraulic conductivity for the soils used in the equation is 94.6 m/year, equivalent to 3×10^{-6} m/sec obtained from field testing as reported earlier in this report.

Based on the above stated factors, an upper limit of seepage potential in this area that may be lost due to construction of the Farm Pond is calculated at 110 m³/year. This is not an unreasonable figure given the nature of the native soils (clays and silts with a low hydraulic conductivity) and limited area in which such seepage may occur. The calculated infiltration at the 40 m infiltration swale of 620 m³/year will make up for this potential loss by a factor of about 5.6 times⁴⁹. Additionally, baseflow at the Reach 14W-12A located in this same area will be further augmented with controlled rooftop runoff measures described earlier in this report.

4.4.4.8 Dewatering Potential

Extensive construction dewatering is not anticipated across the majority of the Subject Property other than for removal of minor seepage into excavations. Dewatering related to building construction will be in large part a function of the proposed building designs. Minimal dewatering would be expected for buildings with slab-on-grade foundations whereas buildings constructed with basements and/or underground parking may require more extensive groundwater removal.

The excavations of the SWM facilities will be mainly within the Clayey Silt Till found at surface across the entire subwatershed, but are also anticipated to be partially completed into the underlying Shale Bedrock. As noted in Section 4.2.1, the Shale is weathered in the upper 3 to 5 m, and is considered the local aquifer, albeit a poor aquifer with low yields. Because the SWM facilities are expected to be constructed fully within low permeability till deposits and in places into the upper weathered zone of the bedrock, some dewatering during construction is anticipated. Groundwater entering the SWM facilities excavations through localized sand seams within the till or from the upper weathered zone of the shale are expected to be managed through passive drainage and pumping through filtered sump pumps. Clay liners will be necessary where the SWM facilities intercept the Shale Bedrock and at localized sand seams within the Till, and the native soils are likely suitable for this purpose⁵⁰. Additional geotechnical drilling investigations should be considered at the proposed SWM facilities to better characterize the expected conditions and dewatering potential during detailed design.

The development will be serviced with municipal water and sewers. The sewer services are expected to be mainly located in the till soils and as such, no dewatering other than local sump pumping for construction of sewer services, is anticipated. Granular pipe bedding backfill material used for buried services may become a preferential flow path for percolated surface water and groundwater. Anti-seepage collars should be installed at regular intervals to prevent continuous groundwater flow along the backfill. The frequency of collar installation will depend on final grade elevation, slope of services and thickness of granular pipe bedding.

⁴⁹ The 620 m³/year of water to be provided by the infiltration trench could conceivably offset a loss of seepage across a total seepage face length of 175 m, or seepage along the shoreline of the watercourse/Farm Pond extending about one quarter of the Farm Pond length to the east. However, as noted elsewhere in this report, the extent of this potential seepage area is limited to the immediate vicinity of monitoring station MP-24, as strong downward gradients from the Farm Pond into the underlying clay/silt soils are present at monitoring wells to the east.

⁵⁰ Subject to confirmation by a geotechnical engineer.

Based on the proposed concept plan (refer to Figure 4.7) three watercourse crossings, with buried services (e.g., water, sewer) are proposed within FM1001, with two of these crossings located on the Subject Property. It is understood that the crossings will be carried out using trenchless techniques that will preclude the need for trenching across the existing watercourses. Access pits would need to be constructed at each side of the watercourse and removal of minor groundwater seepage from these pits may be required.

Scheduling excavations for the late summer, if practical, will further serve to reduce groundwater seepage into excavations as this is the time of year when groundwater levels are typically at their lowest. In particular, scheduling the channel crossing works for the late summer when these channels are observed in dry condition is recommended, as this will minimize potential for localized impacts to aquatic life. It is further recommended that the service crossing of the proposed realigned channel be completed at the time of construction of the new channel. In this one location, simple trenching can be used, provided the work is carried out before the realigned channel becomes operational.

Dewatering volumes are not anticipated to exceed 50,000 litres/day. However, dewatering potential is dependent upon a number of factors such as the proposed depth and size of excavations, the time of year and groundwater elevation. It may be later determined that a Permit to Take Water (PTTW) or Environmental Activity and Sector Registry (EASR) from the Ministry of Environment and Climate Change will be required. The need for this permit would be identified at detailed design. The application requirements for a PTTW or EASR requires the applicant to address how much water will be withdrawn, over what time period, where it will be discharged to, the water quality discharge parameters that are to be met, the expected zones of influence and effects on natural features and other users, among other things. Monitoring and mitigation measures would also be required and would be identified in the application. PTTW and EASR applications are submitted after detailed design and in advance of the construction works.

4.5 Conclusions and Recommendations

The Subject Property and the three subwatersheds that traverse the property are located in a hydrogeological environment that is not particularly favourable towards mitigation of infiltration losses (ref. NOCCS Sections 5.5.2 page 5-11, 7.4.4.2, page 7-22). The surficial fine-grained deposits of Halton Till found throughout the study area serves to limit infiltration to the groundwater system (69 mm/year) and as a result, the local stream systems receive a little over two-thirds of their total water from surface runoff (141 mm/year). Almost all of the groundwater base flow into the watercourses occurs over the period of November to May, when the entire shallow system, including upgradient reaches of the channel are saturated and contributing water to the streams. The watercourses are observed in a dry to ponded condition during the summer months as predicted by the water balance, and the comparisons of measured stream flows to estimates from the water balance methodology are reasonable.

The lower reaches of the FM1001 watercourses (generally to the south of Highway 407) are interpreted as receiving minor groundwater contributions from the Queenston Shale bedrock based on water level monitoring carried out at the Subject Property. However, the rate of influx of bedrock groundwater is low, and during the summer months, is insufficient to provide enough water to maintain flow in these watercourses, observed in the summer months as dry to pooled condition. Groundwater inputs from the bedrock in the realigned watercourses after development are however expected to increase compared with the pre-development levels. Over the lower reaches of the main channel there may be greater opportunity for

bedrock-based groundwater to maintain pools in the stream channel as the bedrock is exposed in the channel and the watercourse is shaded somewhat by large trees.

The channel section of the FM1109 (Reach 14W-11 and Reach 14W-11A) passing through the northeast corner of the Subject Property is interpreted from collected site data to be losing water to the ground, due to the nearby influence of a buried bedrock valley to the east. The large Farm Pond at the central portion of the Subject Property is also shown to be maintained almost entirely by surface water inflow rather than from groundwater contributions on the basis of the comparison of the measured surface water levels at the pond against the groundwater elevations at monitoring wells constructed around the Farm Pond.

Both upward and downward gradients have been recorded at the mini-piezometer nest (MP-24) located near the upstream end of the Farm Pond. Therefore some minor groundwater contribution to adjacent channel (Reach 14W-12A) may be occurring at times of the year, but the limits of the seepage area is interpreted to be to the northwest of the upper end of the Farm Pond (see Section 4.3.1.1, and Figure HG-4, Appendix 4.5). Even should this seepage make its way towards the Farm Pond, given the larger surface area of the eastern part of the Farm Pond, and the larger outward gradients identified in that area, losses from the Farm Pond will be significantly greater than the potential groundwater inflows from near the upstream end of the Farm Pond.

The 40 m length of infiltration swale proposed to the north of the central SWMP is expected to make up for the potential minor losses of groundwater discharge presently found at the upstream end of the Farm Pond by MP-24. Additionally, baseflow at the lower reaches will also be further augmented at Reach 14W-12A from runoff from about 5.12 ha of rooftop area under the ultimate built out condition. This water will enter the watercourse system to the north of the central SWM facility (via Reach 14W-12A).

The upper weathered zone of the till, with an estimated bulk horizontal hydraulic conductivity on the order of 3×10^{-6} m/sec therefore provides the bulk of the groundwater inputs to the local watercourses, but on a seasonal basis over about seven months of the year. The enhanced permeability of this upper zone permits infiltrating groundwater to travel somewhat rapidly through the shallow zone towards the watercourses and it is these conditions that provide the most promising potential mitigation opportunities at this site.

However, these opportunities are of limited extent as:

- The Town of Oakville's land use policies and maximum lot coverage requirements for more intensive employment development dictate 90% of the lots proposed for actual development are assumed to be covered with impervious surfaces, either asphalt/concrete or building envelope, leaving very little pervious area within the developable portion of the Subject Property;
- Significant site grading is proposed within the developable lands, where the tops of the gentle ridges at the Subject Property will be removed by cut and these materials will be placed and compacted in the lower lying lands to raise grades. This will lead to most of the surficial soils within the developable zone consisting of deeper unweathered deposits and reworked and compacted layers of the clayey silt till. These soils will therefore have significantly less transmissive ability to convey large quantities of water at any mitigation devices proposed within the developable lands. This can be improved by tilling/scarifying/ripping the sub-soils (0.5 m depth) and amending them with compost prior to placing topsoil (0.25 m).


Therefore, the most promising opportunity for mitigating against infiltration losses at the Subject Property is along the edges of the existing valley lands where the naturally weathered and fractured surficial till soils will remain undisturbed by construction and will retain their ability to convey water laterally towards the watercourses. It is along these lands that infiltration swales receiving primarily clean roof runoff are proposed, and such infiltration measures are calculated to reduce the on-site infiltration deficit from approximately 62% with no mitigation, to a balance with the pre-existing conditions with the use of the infiltration swales. The balancing of the post development infiltration with existing conditions exceeds the expectation of NOCSS. Post-development base flow during the period between June and December is predicted to be at or above the existing base flow contributions, which includes the dry summer season, where a slight increase in infiltration is provided to the groundwater system from the proposed mitigation measures.

The following recommendations are provided:

- Construct infiltration swales along the edges of the NHS and direct clean roof runoff into these swales and allow it to infiltrate into the ground. These will consist of narrow swales filled with clear stone and amended soils constructed at the rear of developable lots (see Figure 4.8). Clean surface runoff from landscaped areas can be directed towards these swales via vegetated filter strips. No runoff from roads and parking areas are to be directed into the infiltration swales;
- Construction of the swales should only be done in dry weather to avoid remoulding the soil and effectively lining the swale sides and base with an impervious smeared layer. Manual scraping and removal of smeared soils from the sidewalls and base of the swales to expose the natural fracturing should be contemplated;
- Additional investigative techniques such as percolation testing at the proposed infiltration swale locations should be carried out during detailed design to confirm the infiltration rates of the surficial soils along the alignment of the proposed swales, and this information be used in refining the sizing of the swales. It is further recommended that a short length of swale be installed during the detailed design stage and tested to confirm its suitability for its intended purpose;
- Grading at the Subject Property should be, if possible, designed to moderate runoff and enhance recharge characteristics subject to the Town's standards for lot grading;
- Grade the rear/side landscaped grounds on lots adjacent to the natural features (reach valleys) towards these features. This recommendation is also applicable to the SWM facility blocks, where as much of the block area as feasible should be graded towards the valleys rather than back into the SWM facilities;
- Steps to minimize post-development reduction in the infiltrative capacity of the low permeability till soils should be implemented where feasible. These steps are more pertinent to the parts of the Subject Property where minimal site grading is anticipated and they include:
 - Scheduling site grading and heavy construction activities during the drier summer months to reduce the potential of lowering the permeability of these materials while they are in a wet state;

-
- Where possible, designating areas that should see a minimum of construction traffic. In particular heavy construction equipment must be kept away from the crests of the slopes by the valley lands (along the rear lot lines of the abutting lots), where infiltration swales are proposed;
 - Scarify and till the upper 0.5 m of soil within the proposed channel realignments to amend these soils with organic matter and/or placement of thicker topsoil cover (0.25 m) to provide for water storage. This should also be done at the landscaped areas within the development lands. There will be a substantial volume of topsoil at the property after grading and this material can be re-used at the site:
 - However, within the future development lots, it is recommended to defer this mitigation measure to the time when each lot is individually developed and the landscaped areas are known;
 - Additional mitigation measures, such as vegetative swales at parking areas, landscaped infiltration ponds/wetlands, green roofs, cistern systems for grey-water use and/or landscape irrigation, etc. are specific to lot configurations, intended use, building design and so forth and should be examined during later stages of detailed design or at the time of building permit applications. For example, construction of landscaped ponds/wetlands would not appear feasible on a lot with a large warehousing facility and extensive parking facilities, but may be feasible at a lot housing a corporate headquarters facility;
 - Construct trench plugs at intervals along sewers and buried service trenches to prevent high permeability conduits from intercepting and redirecting groundwater away from discharge areas across the Subject Property;
 - Construction of the watercourse crossings should be scheduled if possible during late summer to take advantage of the typically lower groundwater elevations during this season, and will reduce groundwater seepage into the pit excavations required for the trenchless techniques envisioned. The watercourses at the Subject Property have been observed to be in a generally dry condition during the summer and scheduling this work at this time will minimize potential for localized impacts to aquatic life and would potentially limit dewatering during construction;
 - The service crossing proposed at the realigned channel should be completed at the time of construction of the new channel (before it comes into service) and in such case can be constructed using standard trenching methods;
 - Dewatering volumes are not anticipated to exceed 50,000 litres/day. However, dewatering potential is dependent upon a number of factors such as the proposed depth and size of excavations, the time of year and groundwater elevation. It may be later determined that a Permit to Take Water (PTTW) or an Environmental Activity and Sector Registry (EASR) from the Ministry of Environment and Climate Change will be required;

- The SWM facilities may be excavated into the Shale Bedrock, and where bedrock or sand seams within the Till are encountered, a clay liner will be required. Additional geotechnical drilling investigations should be considered at the proposed SWM facilities to better characterize the expected conditions and dewatering potential during detailed design;
- Off-site monitoring wells alongside the road allowances are recommended for decommissioning (well locations MMM-09-16 to MMM-09-20 inclusive). These monitors will need to be decommissioned as per the requirements of O.Reg. 903 (as amended);
- Continued baseline monitoring of water levels at the on-site wells is recommended. Monitors presently constructed on the bclMC property and other adjacent developer owned lands are recommended to remain in place for future monitoring in support of these developments until such time as they are no longer needed, in which case they will also need to be decommissioned as per the requirements of O.Reg. 903 (as amended). Monitors completed to shallow depth that will be completely removed by site grading will not require decommissioning since following site grading there will be no potential contaminant pathway left in place at such locations; and,
- Groundwater monitors presently constructed within natural environment areas should be retained for long-term, post development monitoring. Additional monitors may be required to replace existing monitors to be removed by development.



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Site Location

Legend

- Municipal Boundaries
- Subject Property
- Subcatchment Areas
- Watercourse



Client

Prepared By


Date June 2017

Project No. 09M-00013-01

Scale as Shown

Figure: 4.1

J:\1442 Projects by Job Number\2009\14-09222-001-HG1 Bertall Lands\050 Mapping\MXD\Report\Figure 4.1 Site Location.mxd



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Surficial Geology

Legend

- Buried Bedrock Valley (Inferred from Water Well Records)
- Approximate Extent of Hanson Brick Tremaine Quarry Lands
- Subject Property
- Watercourse
- Waterbody
- Cross-Section
- Topographic Contour (5m Interval) (Based on OBM mapping)
- MOE Water Well Locations
- Subcatchment Areas
- (See text in section 4.4.4.1.1 of the report for explanation)

Surficial Geology

- Queenston Formation (Shale Limestone)
- Halton Till
- Peel Pond Glaciolacustrine Silt and Clay Deposits
- Modern Alluvial Deposits

Scale

0

0.5


1

2

Kilometers

Client	Prepared By
Date	Project No.
June 2017	09M-00013-01
Scale as Shown	Figure: 4.2
© Queen's Printer for Ontario	

J:\1442 Projects by Job Number\2009\14-09222-001-HG1 Bertall Lands\050 Mapping\MXD\Report\Figure 4.3 Interpreted Shallow and Bedrock Groundwater Contours.mxd



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Interpreted Shallow and Bedrock Groundwater Contours

Legend

- Interpreted Shallow Groundwater Contours
- Interpreted Bedrock Static Water Levels
- Monitoring Locations
 - MMM Monitoring Well
 - TROW Monitoring Well
 - Lazy Pat Farm Well
- Potential Areas with Groundwater Discharge from the Bedrock
- Buried Bedrock Valley
- Subject Property
- MOE Water Well Locations
- Watercourse
- Waterbody
- Subcatchment Areas
- Approximate Extent of Hanson Brick Tremaine Quarry Lands

Locations Not Monitored by MMM

- Hanson Brick Monitoring Well
- Hanson Brick Test Wells

Note: Interpreted bedrock groundwater contours are based on the MOE water well record data along with upper levels from MMM and Hanson Brick monitors.



Date June 2017

Project No. 09M-00013-01

Scale as Shown

© Queen's Printer for Ontario

Figure: 4.3

Environmental Implementation
Report / Functional Servicing Study
for 14 Mile Creek West and the Lazy
Pat Farm Property

On-site Monitoring Locations


Legend

- Pond Logger (July 2013 - Present)
- Pond Logger (July 2011 - November 2012)
- Lost / Destroyed Mini-Piezometers
- EXP Monitoring Well (2011)
- MMM Monitoring Well (2009/2011)
- Mini-Piezometer
- TROW Monitoring Well (2001)
- Lazy Pat Farm Well
- Flow Monitoring Points
- Staff Gauge
- Surface Water Sampling Location at SG-01
- Supplemental Pond Study Cross Section
- Watercourse

Topographic Contours

- 5 m Interval
- 1 m Interval
- Subject Property

Note: FMP-3 is located offsite at the southeast corner of
Tremaine Road and Number 1 Sideroad



Date June 2017


Project No. 09M-00013-01

Scale as Shown

Figure: 4.4

J:\1442 Projects by Job Number\2009\14-09222-001-HG1 Bertall Lands\050 Mapping\MXD\Report\Figure 4.4 On-site Monitoring Locations.mxd

J:\1442 Projects by Job Numben\2009\14-09222-001-HG1 Betail Lands\050 Mapping\MXD\Report\Figure 4.5 Static Water Levels - Spring.mxd



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Static Water Levels - Spring

Legend

Monitoring Locations


- MMM Monitoring Well
- Mini-Piezometer
- TROW Monitoring Well
- Lazy Pat Farm Well
- Interpreted Shallow Groundwater Contours
- Interpreted Bedrock Groundwater Contours
- Interpreted Zone For Potential Bedrock Groundwater Contribution to Watercourses
- Watercourse

Topographic Contours


- 5 m Interval
- 1 m Interval
- Subject Property

For the nested wells: The upper value represents the shallow monitor and the lower value represents the deep monitor. The value in brackets represents the vertical gradient at the nest. Positive (+) values indicate downward flow, negative (-) values indicate upward flow.

Based on April 2010 levels. Data for MMM 09-15D is based upon Jan. 2010 levels as April 2010 values were depressed and not fully recovered from groundwater sampling in Feb. 2010.



Client	Prepared By
	
Date	Project No.
June 2017	09M-00013-01
Scale as Shown	Figure: 4.5
© Queen's Printer for Ontario	



Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Static Water Levels - Summer

Legend

Monitoring Locations

-  MMM Monitoring Well
-  Mini-Piezometer
-  TROW Monitoring Well
-  Lazy Pat Farm Well
-  Interpreted Shallow Groundwater Contours
-  Interpreted Bedrock Groundwater Contours
-  Interpreted Zone For Potential Bedrock Groundwater Contribution to Watercourses
-  Watercourse


Topographic Contours

- 5 m Interval
 1 m Interval
 Subject Property

Notes:

CNL - Could Not Locate

For the nested wells: The upper value represents the shallow monitor and the lower value represents the deep monitor. The value in brackets represents the vertical gradient at the nest. Positive (+) values indicate downward flow, negative (-) values indicate upward flow based on August 2010 levels.



Client



Prepared By	
-------------	--



Date June 2017

Project No.	09M-00013-01
-------------	--------------

Scale as Shown

© Queen's Printer for Ontario


Figure: 4.6

Concept Plan and
Mitigation Opportunities

LEGEND

- Potential Infiltration Swales (1.1m wide)
- Potential Infiltration Swales (1.3m wide)
- Roof Area to Swale - Allocated Area in Hectares for Roof
Runoff to be Conveyed to the Infiltration Swales
- Sub-catchment Areas

Note: Mitigation opportunities are identified Bentall owned lands (FM1001 and FM1109) and lands owned by others (FM1001 only)




Date
June 2017

Proj. No.
09M-00013-01
(1409222-001)

Aerial Photo
© DigitalGlobe 2010, Google 2009

Figure 4.7



NOTES:

- 1) CONFIRMATION OF LOCATION AND SIZING OF THESE FACILITIES TO BE CARRIED OUT AT DETAILED DESIGN THROUGH ADDITIONAL FIELD INVESTIGATIONS AND PERCOLATION TESTING.
- 2) INFILTRATION SWALES TO BE CONSTRUCTED AT REAR OF LOTS ADJACENT TO NATURAL ENVIRONMENT FEATURES WHERE FLAT-BOTTOMED INFILTRATION SWALES CANNOT BE BUILT.
- 3) CLEAN SURFACE RUNOFF DIRECTED TOWARDS THE INFILTRATION SWALES SHALL BE FROM LANDSCAPED AREAS ONLY (NO DRIVEWAY/PARKING LOT RUNOFF) AND SHALL BE DIRECTED TO THE INFILTRATION SWALES VIA SHEET FLOW THROUGH VEGETATED FILTER STRIPS

**Environmental Implementation
Report / Functional Servicing
Study for 14 Mile Creek West
and the Lazy Pat Farm Property**

Conceptual Infiltration Swale

N.T.S.

 **QuadReal**




Date: June 2017


Project No: 09M-00013-01-HG1




Figure 4.8

**Figure 4.9: Monthly and Cumulative Infiltration - bclMC Lands within FM1001
Pre-Development and Post-Development**




**Figure 4.10: Monthly and Cumulative Infiltration - FM1001 Subwatershed
Pre-Development and Post-Development**





LEGEND



NOTES:

- MANUAL WATER LEVELS FOR MMM AND TROW MONITORING WELLS WERE MEASURED ON APRIL 13, 2010
- MMM AND TROW WELLS WERE PROFESSIONALLY SURVEYED

Environmental Implementation Report / Functional Servicing Study for 14 Mile Creek West and the Lazy Pat Farm Property

Hydrogeologic Cross-Sections A-A', B-B' and C-C'

Horizontal 1 : 10000 Vertical 1 : 1000



JUNE 2017

Project No. 09M-00013-01
(1409222-001)

Drawing 4.1

5.0 Natural Environment



5.0 Natural Environment

5.1 Introduction

5.1.1 Study and Site Overview

The North Oakville Secondary Planning Areas includes a number of watercourses that outlet to Sixteen Mile Creek or directly to Lake Ontario. These watercourses include Joshua's Creek, Morrison Creek, Munn's Creek, Shannon Creek, Osenego Creek, Fourteen Mile Creek, Taplow Creek, Glenn Oak Creek, and Sixteen Mile Creek. Generally, the existing land uses in the North Oakville Secondary Planning Areas are a mixture of agriculture, recreation (golf course and riding stable) and rural residential uses that are dissected by a local and regional road network. The North Oakville Secondary Plans designate the lands for a variety of residential, employment, commercial, institutional, recreational and natural heritage, and open space uses. The Subject Property is located within the NOWSP and more specifically, the 407 West Employment Area, which is planned to accommodate a variety of employment uses.

Within the catchment areas associated with the Subject Property the land use consists principally of active agriculture. The agricultural areas are intermixed with a variety of natural features of varying sizes and sensitivities. Generally, the notable natural features include the Oakville-Milton Wetlands & Uplands Candidate Life Science Area of Natural and Scientific Interest (ANSI), North Oakville – Milton Wetlands – West Provincially Significant Wetland (PSW) Complex, Trafalgar Moraine Candidate Provincially Significant Earth Science ANSI, Halton Region Significant Woodlands, as well as, features identified in the NOCSS including Core #1 and Linkage to Core #2, Stream Corridors associated with Fourteen Mile Creek including watercourses supporting Redside Dace (*Clinostomus elongatus*) and Hydrological Features. These catchment areas and often the natural features, are traversed by a series of roads including Burnhamthorpe Road, Regional Road 25 (Bronte Road), Highway 407, Dundas Street and Tremaine Road.

5.1.2 Study Objectives and Scope of Work

The objective of this study is to satisfy the requirements for an EIR/FSS for the QuadReal Lazy Pat Lands located north of Dundas Street, East of Regional Road 25 (Bronte Road), South of Highway 407 and west of Tremaine Road, in the Town of Oakville hereafter referred to as the "Subject Property" (Figure 1.1).

The NOWSP and the NOCSS identify the requirement to prepare an EIR to "*...characterize and analyze the natural heritage features and functions (of the Subject Property) and to determine and address the potential impacts of the proposed development application, including servicing requirements, on the Natural Heritage System*" as defined in the NOCSS. The North Oakville Environmental Implementation Report and Functional Servicing Study Terms of Reference (Town of Oakville, 2007) defines the scope of work required for completion of an EIR.

Table 5.1 summarizes the EIR requirements identified in the ToR, and how this report addresses the requirements.

In this report, we also review and assess: natural heritage provisions of the Provincial Policy Statement, (PPS) (2014); Ontario's Endangered Species Act, (ESA) (2007); Ontario Regulation 162/06 (CH's Development, Interference with Wetlands and Alterations to Shorelines and Watercourse Regulation); and the associated Policies, Procedures and Guidelines for the Administration of Ontario Regulation 162/06 and

Land Use Planning Policy Document (Conservation Halton, 2006), to demonstrate how the proposed development conforms to the requirements of these policies/legislation. The Halton Region Official Plan (2006, 2009) and the Liveable Oakville Plan (Oakville Official Plan 2009) were also reviewed for compliance. However, the Livable Oakville Plan does not apply to lands within the NOWSP, and so is not addressed.

Table 5.1 - Summary of applicable EIR study requirements identified in the North Oakville EIR and FSS Terms of Reference (Town of Oakville, 2007)

NHS¹ Component	EIR Study Requirements according to Terms of Reference	How Requirement is addressed
Cores and Linkages	Delineate boundaries and Linkage areas based on NOCSS and present the boundaries on recent aerial photographs	Core and Linkage boundaries from NOCSS are presented on 2009 aerial photographs on Figure 5.1 of this report. Core and Linkage boundaries have not been field confirmed or surveyed.
	Assemble background information on natural environment features and functions within the Core(s) and Linkage(s) from the NOCSS and other secondary sources. For Cores, include features, functions and management recommendations.	Designated natural environment features occurring within the overlapping EIR subcatchments are presented on Figure 5.1. A summary of natural environment features, functions and management recommendations for Core #1 ² is presented in Section 5.3.5.5.
	Conduct preliminary field review of features to confirm limits and character of vegetation communities within Cores and Linkages (e.g. roadside review or similar using recent aerial photographs).	Roadside review of Core #1 and the Linkage to Core #2 (located in off-site portion of overlapping subcatchment FM1109) was completed on August 18 and September 11, 2009. A summary of field observations is presented in Section 5.3.5.5.
	Identify any effect of other works (i.e. road crossings, servicing, SWM, etc.) and associated requirements related to Cores and Linkages.	Effects and associated requirements of road and servicing crossings of Core #1 and the Linkage to Core #2 are discussed in Table 5.14 to 5.16.
	For Linkages, review stream corridor assessment to ensure that any proposed proponent modifications to stream corridors (locations, widths, etc.) that may influence Linkages are identified.	Proposed watercourse modifications do not affect stream corridors associated with Linkages. See Figure 6.4A for an overview of proposed watercourse modifications.

¹ Natural Heritage System

² Core #1 is a component of the proposed Natural Heritage System for North Oakville and is associated with the Fourteen Mile Creek valley. Core #1 is located off-site to the northeast.

NHS ¹ Component	EIR Study Requirements according to Terms of Reference	How Requirement is addressed
Stream Corridors	Identify any relevant fish habitat setbacks, on a reach basis based on the fisheries buffers recommended in the NOCSS Management Report, and as confirmed through the studies.	Fisheries setbacks as recommended by NOCSS have been applied on a reach basis and combined with the stream corridor width delineation to obtain the development limit/open space area.
	With respect to Species at Risk, fish habitat setbacks will be identified on a reach basis with reference to NOCSS, and through discussions with relevant agencies.	The setback associated with the High Constraint reach and those reaches supporting Redside Dace consists of meander belt plus 30 m, consistent with the requirements of the MNRF.
Fish and Fish Habitat	Prepare detailed habitat mapping for all streams that contain fish habitat, which potentially may be impacted by the proposed development.	Habitat within the Subject Property was documented during multi-season field investigations and described in Section 5.3.4.4.
	Additional fish sampling may be necessary to fill information gaps.	Additional fish community sampling was undertaken in the upstream reaches of the watercourses within the Subject Property to document potential seasonal habitat. This information is presented in Section 5.3.4.1. As well, a detailed examination of the Farm Pond (Reach 14W-14A) was presented in NH#1 Technical Memo (Appendix 5.9).
	Detail proposed works (e.g. stormwater management facilities, road crossings, grading) adjacent to the fish habitats and assess/predict the impacts of construction and operation of the works, considering channel length and form, riparian buffers, flow volume and duration, water quality and water temperature.	Potential impacts to aquatic habitat associated with the proposed development are detailed in Section 5.9.1 and Table 5.14.
	Detail mitigation measures and assess potential residual impacts of any works in or adjacent to fish habitats.	Potential mitigation measures and an assessment of residual effects to aquatic habitat associated with the proposed development are detailed in Sections 5.9 and 5.10 and Table 5.14.

NHS¹ Component	EIR Study Requirements according to Terms of Reference	How Requirement is addressed
Stream Modification or Rehabilitation	Conduct a detailed field investigation of the reach requiring modification or an appropriate reference reach (channel relocation) in order to determine existing aquatic habitat features.	Habitat within the Subject Property was documented during multi-season field investigations and described in Section 5.3.4.4. This information was obtained in suitable detail to guide modification/relocation works.
	Prepare a fish habitat compensation plan that clearly demonstrates how modified reaches will achieve a net gain in fish habitat and meet the 'no net loss in fish habitat productivity' as required by Section 35(2) of the <i>Fisheries Act</i> (FA) (1985).	Fish habitat enhancement concepts are presented in Section 5.9.1. These concepts will form the basis for the preparation of the fish habitat enhancement plan once commented on by the regulatory agencies. The enhancements take into consideration the requirements and focus of the amended FA (1985) (November, 2013), effective November, 2013. The 'no net loss in fish habitat productivity' is no longer an applicable policy under the amended FA (1985).
	Illustrate the extent of any features supporting critical life stages of fish or other aquatic biota and clearly demonstrate how the proposed compensation will replace the form and function of this habitat.	Due to the type of habitat present within the reaches to be modified/relocated, critical habitat was not identified. The compensation concept takes into account limiting habitat within the Subject Property with an objective to enhance the habitat present.
Forested Stands within Stream Corridors	Use a combination of aerial photographs, ground truthing, and ELC mapping to determine the extent of forested cover within potential stream corridor(s).	Two (2) forested stands within a stream corridor are present on the Subject Property. ELC mapping of these communities are presented on Figure 5.2 Vegetation Units 3A and 5A).
	Identify the characteristics of forested stands and their relationship to the stream corridor (including potential implications, if any, on stream corridor width/location.	A summary of vegetation community characteristics is presented in Table 5.7.
	Identify forested stands within the stream corridor(s) and measures to be used to protect and/or manage them as appropriate.	Feature will be protected with setbacks as discussed in Table 5.15 and presented on Figure 5.5 and in Section 6.0, Figures 6.4a-e

NHS ¹ Component	EIR Study Requirements according to Terms of Reference	How Requirement is addressed
Hydrologic Features 'A' and 'B'	Use a combination of aerial photographs, ground truthing, and ELC mapping to determine the extent of wetland cover for each Hydrologic Feature 'A'.	The Location of Hydrologic Features 'A' on the Subject Property is presented on Figure 5.1. ELC mapping showing the extent of wetland cover is presented on Figure 5.2 and Table 5.7.
	Identify the form and function of each Hydrologic Feature 'A' and document its ecological and hydrologic relationship to the watercourse (e.g. does the feature represent an online pond or wetland).	A summary of form and function of each Hydrologic Feature 'A' wetland community, including its ecological and hydrologic relationship to the watercourse, is presented in Table 5.7.
	Identify how the ecological and hydrological relationships of the Hydrologic Feature 'A' is considered in the proposed stream modification.	The form and function of Hydrologic Features 'A' will be recreated within realigned stream corridors, as described in Section 5.9.
	There are no EIR Study Requirements for Hydrologic Features 'B'.	The locations of Hydrologic Features 'B' are presented on Figure 5.1. The feature associated with Reach 14W-16 will be retained within the natural heritage setbacks for the stream reach (Figure 5.7).

5.1.3 Agency Consultation

Consultation with CH and the MNRF were undertaken during the preparation of the EIR to verify the classification of the natural environment features on-site. Selected agency communications are provided in Appendix 5.8.

Conservation Halton

- March 30, 2009 – Record of Communication: Temperature and Dissolved Oxygen Monitoring per the NOCSS management strategy. Completed March 31, 2009.
- June 29, 2010 – On-site meeting with CH and Town of Oakville staff to stake the top of bank features.
- August 17, 2010 – CH confirmed the classification of on-site wetlands identified as provincially significant on *Provincially Significant North Oakville – Milton West Wetland Complex* mapping (MNR, 2006). According to Ms. Brenda Axon, the MNRF indicated that they would amend the North Oakville-Milton West wetland complex to remove the wetlands as part of the complex.
- September 23, 2010 - On-site meeting with CH representatives Ms. Leah Smith and Ms. Samantha Mason to discuss on-site fish and fish habitat resources in an effort to confirm the reach classifications, setback requirements and development constraints. Meeting Minutes October 5, 2010.

-
- November 15, 2010 - North Oakville Agency Review Meeting where MMM Group presented the proposed concept plan including channel realignments, development setbacks, incorporation of the Farm Pond (Reach 14W-14A) into the stormwater management plan and constraint classification of watercourse reaches based on habitat types.
 - January 20, 2011 - CH issued comments based on material presented on November 15, 2010. MMM Group responded to the comments on March 1, 2011.
 - January 25, 2011 – Meeting with CH representative Samantha Mason, as well as, representatives from the MNRF to discuss the proposed concept plan and presence of sensitive species on the Subject Property. Meeting Minutes February 1, 2011.
 - April 19, 2011 – On-site meeting with CH representatives Ms. Leah Smith and Ms. Samantha Mason, as well as, representatives from the MNRF, Town of Oakville and Halton Region to discuss the proposed concept plans. Meeting Minutes April 29, 2011.
 - September 6, 2011 – CH and Town of Oakville (September 16, 2011) comments on the draft EIR/FSS.
 - October 20, 2011 – On-site meeting with CH representative Leah Smith, as well as, representatives from the MNRF and Fisheries and Oceans Canada (DFO) to discuss the proposed development concepts in relation to existing stream reaches on the Subject Property. Meeting Minutes November 24, 2011.
 - March 30, 2012 – MMM response to CH and Town of Oakville Comments (September 6, 2011).
 - August 16, 2012 – CH comments on the response to EIR/FSS comments and 2011 Natural Heritage information for Stream Reach 14W-14A.
 - August 20, 2012 – North Oakville Agency Review (NOAR) Meeting attended by representatives from CH and the Town of Oakville.
 - January 9, 2013 – MMM email response to provide Technical Memorandum NH#1 technical data (Reach 14W-14A)
 - March 21, 2013 - CH letter response to EIR/FSS (MMM Group, December 2012).
 - July 4, 2013 - MMM Issues Disposition List in advance of the multi-agency September 10, 2013 Workshop.
 - September 10, 2013 – Multi-agency Workshop and Presentation.
 - September 13, 2013 - MMM Action items in response to September 10, 2013 Multi-Agency Workshop.
 - February 27, 2014 – MMM response to CH comments (email communication) February 13, 2014).
 - June 11, 2014 - CH correspondence indicating that CH are satisfied with the responses to previous comments.
 - November 2014 – MMM submits EIR/FSS 3rd Submission to CH.
 - May 27, 2015 – CH issues comments related to the EIR/FSS 3rd Submission.
 - June 19, 2015 – MMM response to CH comments.
 - August 10 and 11, 2015 – Technical meetings attended by CH and MMM.
 - December 23, 2016 – MMM submits a Flow Regime Analysis Memorandum based on CH's comments received on July 15, 2016 on the Hydraulic Model Interim Submission.

- March 10, 2017 - CH issues comments related to the December 23, 2016 Flow Regime Analysis Memorandum.
- May 26, 2017 – Email communication between CH and MMM related to clarification of the CH comments received on March 10, 2017.

Ministry of Natural Resources and Forestry

- June 22, 2009 - A permit was obtained from the MNRF (Aurora District) for a License to Collect Fish for Scientific Purposes in order to conduct fish community sampling within the Subject Property (License # 1052019).
- July 15, 2010 – CH to MNRF (email communication) regarding wetland staking: Wetland Units 2 and 3, North Oakville-Milton West Wetland Complex).
- August 17, 2010 – MNRF's decision to declassify the PSW (email communication).
- November 17, 2010 – Request MNRF involvement in discussions related to the proposed development; channel realignments associated with Redside Dace habitat (email communication).
- November 22, 2010 - Melinda Thompson-Black of the MNRF (Aurora District) was consulted to obtain provincial Species at Risk (SAR) records. Email response November 23, 2010.
- January 25, 2011 - Consultation with the MNRF to discuss the proposed concept plan on two species; Redside Dace and Bobolink, protected under the *Endangered Species Act 2007* (ESA).
- April 19, 2011 – On-site meeting with MNRF representative Mr. John Pisapio, as well as, representatives from the CH, Town of Oakville and Halton Region to discuss the proposed concept plans.
- October 20, 2011 – On-site meeting with MNRF representative Mr. John Pisapio, as well as, representatives from CH and DFO to discuss the proposed development concepts and provincially significant fish species related to existing stream reaches on the Subject Property. Meeting Minutes (November 24, 2011).
- May 31, 2013 – MMM requesting clarification of MNRFs requirements to provide comment to the EIR (email communication).
- July 25, 2013 – MNRF provided Redside Dace habitat classification of watercourses on Lazy Pat Farm lands (email communication).
- October 24, 2013 – MNRF confirmed that no further fish community sampling is required for the Farm Pond (Reach 14W-14A) (email communication).
- December 20, 2013 – MNRF Comments to the EIR/FSS (2nd Submission, December 2012).
- January 15, 2014 (*correspondence mistakenly dated January 15, 2013*) – MMM Response to MNRF December 20, 2013 comments associated with the review of the EIR (2nd Submission, December 2012).
- February 26, 2014 – Meeting at MNRF Aurora District to discuss SAR implications to the Lazy Pat Farm lands. Meeting Minutes (July 4, 2014).
- March 10, 2014 – Circulation of February 26, 2014 Draft Meeting Minutes.
- April 29, 2014 – MNRF revised meeting minutes (email communication).
- June 18, 2014 – MNRF indicated that the Draft Meeting Minutes can be finalized (email communication).

-
- July 4, 2014 – Meeting Minutes (February 26, 2014) finalized and circulated (email communication).
 - July 23, 2014 – MNRF indicates (email communication M. Heaton) that no PSW exists on subject property.
 - March 26, 2015 – MMM receives MNRF comments related to ESA (2007) permitting / approvals based on a review of the EIR/FSS 3rd Submission (MNRF letter misdated dated 2014).
 - May 23, 2017 – MNRF provides comments to MMM related to the December 23, 2016 Flow Regime Analysis Memorandum (email communication).
 - June 6, 2017 – MMM responds to MNRF comments dated May 23, 2017 (email communication).

Department of Fisheries and Oceans

- October 20, 2011 – On-site meeting with DFO representative Rick Kiriluk, as well as, representatives from CH and MNRF to discuss the proposed development concepts and FA (1985) Authorization requirements related to existing stream reaches on the Subject Property.

5.1.4 Field Investigations

Field investigations for aquatic, vegetation, wildlife resources and select SAR were undertaken in 2002, 2005, 2009, 2010, 2011, 2012, 2013, 2015, 2016 and 2017. During these years, the surveys and monitoring efforts covered multiple seasons and are summarized in Table 5.1.1 Field Work Chronology in Appendix 5.1.

5.2 Natural Heritage Planning Policy

In this section, we provide an overview of Natural Heritage planning policy and relevance to the Subject Property.

5.2.1 North Oakville Creeks Subwatershed Study

The North Oakville Creeks Subwatershed Study is the main Natural Heritage policy document guiding the development process in North Oakville. The North Oakville Creeks Subwatershed Study (NOCSS) (Town of Oakville, 2004), adopts a Core Areas approach to planning of the Natural Heritage System in North Oakville. Utilizing the Core Area approach, clusters of habitats (i.e. Cores) were identified within the planning area based on a number of criteria (discussed below), and “Linkages” between Cores were identified. This network of Cores and Linkages, combined with identified High and Medium Constraint Stream Corridors, comprise the proposed Natural Heritage System in North Oakville.

As stated in the NOCSS Management Report for terrestrial features – “Using this approach, the terrestrial features which are outside the boundaries of the Cores and Linkages may be removed” (Page 6-35). While for the stream corridors, NOCSS stated the following management options:

- **High Constraint** - the corridor is left in its present condition with development occurring outside of its boundaries where it is anticipated that development is not likely to affect the watercourse. Alternatively, if the watercourse is anticipated to be affected, the recommendation is that the reach

is to be maintained in the present location and undertake enhancement of the geomorphic and aquatic habitat conditions within the affected watercourse.

- **High Constraint Requiring Rehabilitation** - Maintain the watercourse in its current location; however; provide enhancement opportunities for effective protection while maintaining function.
- **Medium Constraint** - Similar to High Constraint, with an additional option to undertake stream relocation with enhancement of the existing conditions. Medium Constraint reaches typically have been straightened or modified for agricultural drainage purposes, which suggests they have a reduced sensitivity to relocation; therefore, enhancement efforts would provide benefits to the overall form and function of the system.
- **Low Constraint** - Where the watercourse will not be affected, it is recommended that the corridor be left in its present condition, leaving the channel/swale in the existing condition. If the watercourse will be affected, it is first recommended that designs combine stormwater management/surface drainage systems and if this cannot be accommodated, replicate the affected reach through a system of surface water conveyance techniques (i.e. backyard swales).

5.2.1.1 Core(s) and Linkage(s)

Core areas described in the NOCSS were established according to a set of specific criteria, such that when the Cores are linked together, they create the basis for a Natural Heritage System in North Oakville. The criteria are: diversity of habitat, size, contiguity, connectivity, significance, representativeness and overall watershed functionality. The intent was to identify large and sustainable units consisting of a diversity of continuous habitats and adjacent areas that are considered to be integral to the function of the habitat captured by the Core area. Management of Core areas is based on the function of the area with respect to the ecological “theme”. These themes include: Forest Interior, Open Country and Habitat Connectivity within Cores. Special Considerations for Redside Dace habitat and Buttonbush swamp influence the management of the Core area where these habitats occur.

Cores are connected to each other via Linkages. Locations of Linkages were generally selected to follow natural features whenever possible and are intended to be of sufficient size and character to ensure the functionality and sustainability of the Natural Heritage System.

No Cores or Linkages are identified on the Subject Property.

Core #1 (Fourteen Mile Creek [Main]) and the Linkage between Core #1 and Core #2 are identified within EIR subcatchment FM1109 which extends on to the north corner of the Subject Property. A summary of background information describing natural environment features and functions within Core #1 and the Linkage to Core #2 from the NOCSS and other secondary sources and coarse level field review is provided in Section 5.3.5.5 and mapped on Figure 5.1.

5.2.1.2 Stream Corridors

Streams require riparian setbacks to protect them from the impacts of urban development and associated human activity. Typically these setbacks widths range from 15 to 30 m to maintain the biological components of many wetlands and streams. There are occasions when the need for larger setbacks is appropriate. For

Redside Dace streams, the stream corridor identified as Redside Dace habitat under the ESA (2007) consists of a 30 m setback on either side of the meander belt width. According to NOCSS, Reach 14W-12 requires the meander belt plus 30 m setback with non-Redside Dace reaches requiring a minimum width of 15 m. The upper reach has been informally identified as Reach 14W-12A and is shown in Figure 5.4. Redside Dace habitat associated with Reach 14W-12 will be retained in full with the exception of minor encroachments associated with outlets.

A detailed assessment of the appropriate stream corridor width is presented in Section 6.3. The stream corridors setbacks for Reach 14W-11A, Reach 14W-14 and Reach 14W-16 exceed the recommended general 15 m fisheries setback. However, due to the classification of Reach 14W-12 as a High Constraint reach due to Redside Dace habitat in NOCSS, the recommended ESA (2007) fisheries setback exceed these floodplain and fluvial corridors and forms the development limit.

5.2.1.3 Other Features

Woodlots

Woodlots are not specifically identified and afforded management strategies in the NOCSS; however, woodlands larger than 0.5 ha are considered to be an important Natural Heritage feature and are candidates for assessment as *Significant Woodlands* under the Halton Region *Official Plan* (2006), *Section 130(1)e*.

There is one woodlot (Vegetation Unit 4, Figure 5.2) that was previously identified as regionally significant based on proximity (< 50 m) to a medium constraint stream (NOCSS, p 6-48). This woodlot was excluded from the Natural Heritage System based on the “Core Area Approach” adopted by NOCSS (see Section 1.4.1 for discussion). According to this approach, “the terrestrial features which are outside the boundaries of the Cores and Linkages may be removed” (NOCSS p. 6-35). NOCSS provides additional justification for removal of this feature due to its location within the proposed Highway 407 Transitway right-of-way that will be partially or entirely cleared to accommodate this new corridor. When the proposed Transitway development proceeds, it is anticipated that the woodlot would fall below the area threshold required to be considered for evaluation as a woodland (i.e. 0.5 ha).

The Regional Official Plan (2006) allows local municipalities to substitute a ‘Systems Approach’ to identifying and protecting the Greenlands System within a Secondary Plan area and permits use of criteria other than those identified in the Regional Official Plan, provided that certain criteria are met, including that the alternative Greenlands System is introduced in an appropriate Local Official Plan amendment and is approved by the Region. The Natural Heritage System approach proposed in NOCSS and in the NOWSP, has received Ontario Municipal Board (OMB) approval in part, in December 2009.

The NOWSP (Official Plan Amendment No. 289) was adopted by Council on May 25, 2009, which resulted in an amendment to the existing Town’s Official Plan (2006) to include the NOWSP. Through the amendment, the Significant Woodland/Greenland B designation in the original Town’s Official Plan would be revised as it relates to the North Woodlot (Vegetation Unit 4), based on the inclusion of the Natural Heritage System approach identified in the NOWSP. The new Liveable Oakville Plan (Oakville Official Plan 2009) applies only to “for lands within the Town, south of Dundas Street and north of Highway 407, to 2031”. It does not apply to those areas under the NOWSP. The woodlot, based on the Natural Heritage System approach identified in the NOWSP, would therefore not be considered a constraint to development of the Subject Property.

5.2.1.4 Forested Stands within Stream Corridors

The North Oakville EIR and FSS Terms of Reference states that, “preservation of forested stands within stream corridors is generally preferred, and recommendations were provided in the NOCSS for forest preservation within stream corridors”. Two forested stands within a stream corridor are present within the Subject Property (Vegetation Units 3A and 5A, Figure 5.2). These features will be retained in full and protected with setbacks.

5.2.1.5 Hydrologic Features ‘A’ and ‘B’

Hydrologic Features ‘A’ and ‘B’ are pond or wetland features that have a hydrologic function. Type ‘A’ features are associated with the Natural Heritage System and are located inside the corridor of a High or Medium Constraint Stream. Type ‘B’ features are not associated with the Natural Heritage System. EIR study requirements for Hydrologic Features ‘A’ within the proposed modified stream corridors are summarized in Table 5.1 found in Section 5.1.2.

The NOCSS identifies three type ‘A’ features and three type ‘B’ features within the Subject Property (Figure 5.1). The type ‘A’ features are associated with stream Reach 14W-14 and Reach 14W-16, as well as, and the Farm Pond (Reach 14W-14A) connected to stream Reach 14W-12A. Two of the type ‘B’ features are located to the west of stream Reach 14W-16 and the other feature is located west of 3367 Dundas Street West.³ In addition to the Hydrologic Features identified in NOCSS, we have identified two additional wetland features through field studies in 2009 and 2010. Two are located within high or medium constraint stream corridors and given their context, these wetlands meet the criteria for classification as Hydrologic Features ‘A’ and are located within the stream corridors associated with stream Reach 14W-11A and Reach 14W-16 (Figure 5.2).

The development concepts proposed for the relocation of Reach 14W-14 and Reach 14W-11A, as well as, the conversion of Reach 14W-14A into a SWM facility are anticipated to have impacts to wetlands classified as Hydrologic Features ‘A’ in NOCSS and wetlands that meet the criteria for classification as Hydrologic Features ‘A’ not included in NOCSS located within these reaches. A description of the form, function and ecological relationship of Hydrologic Features ‘A’ is presented in Table 5.7. Hydrologic Features ‘A’ will be recreated within the proposed modified stream corridors, as illustrated on Figures 6.4A to 6.4E in Section 6.0. No ecological study requirements for Hydrologic Features ‘B’ are identified within the EIR ToR; therefore, these features are not considered constraints to development from an ecological perspective under the NOCSS policy framework.

5.2.2 Provincial Policy Statement (MMAH 2014)

The Provincial Policy Statement (PPS) is issued under Section 3 of the *Planning Act*. The current PPS came into effect April 30, 2014. According to the natural heritage provisions of the PPS (Section 2.1.4 and 2.1.5), development and site alteration shall not be permitted in:

³ Note: these are small topographic depressions that were ploughed in 2009/2010, with no associated wetland vegetation.

(2.1.4):

- a. *significant wetlands* in Ecoregions 5E, 6E and 7E⁴; and
- b. *significant coastal wetlands*.

or in

(2.1.5):

- a. *significant wetlands* in the Canadian Shield north of Ecoregions 5E, 6E and 7E⁴;
- b. *significant woodlands* in Ecoregions 6E and 7E⁴ (excluding islands in Lake Huron and the St. Marys River);
- c. *significant valleylands* in Ecoregions 6E and 7E⁴ (excluding islands in Lake Huron and the St. Marys River);
- d. *significant wildlife habitat*;
- e. *significant areas of natural and scientific interest*; and
- f. *coastal wetlands* in Ecoregions 5E, 6E and 7E⁴ that are not subject to policy 2.1.4(b), unless it has been demonstrated that there will be no *negative impacts* on the natural features or their *ecological functions*.

Based on field work conducted to date, available background information and subsequent analysis, the following information describes the Natural Heritage provisions for sensitive species, PSWs and significant woodlots on the Subject Property:

- **Endangered / Threatened Species:** Three Endangered / Threatened species are known to occur on the Subject Property: Redside Dace, Bobolink (*Dolichonyx oryzivorus*) and Barn Swallow (*Hirundo rustica*). Melinda Thompson-Black of the Aurora District MNRF was consulted on November 22, 2010, to determine the potential presence of SAR on the Subject Property. At that time, two Endangered or Threatened species were identified; Redside Dace and Bobolink. Since that time the status of Barn Swallow (Threatened) that was observed during field reinvestigations have changed and now receive protection under the ESA (2007). In 2013, the Little Brown Myotis (*Myotis lucifugus*) and Northern Myotis (*Myotis septentrionalis*) (bats) were classified as Endangered under the ESA (2007). Screening of the site for these bat species was required, as discussed with the MNRF during the February 26, 2014 meeting. The status of species is continually being updated and revised. Below is a summary of the actions that will occur in relation to the Endangered / Threatened species and their associated habitat:
 - Occupied Redside Dace habitat associated with Reach 14W-12 will be retained in full. The proposed setbacks identified were developed in accordance with the policies of the NOCSS and ESA (2007).
 - According to the MNRF, Reach 14W-16 is considered Redside Dace Habitat Occupied habitat and is subject to the same development constraints and setbacks associated with Reach 14W-12. Habitat associated with Reach 14W-16 will be retained in full, with exception of a minor encroachment associated with the new crossing for the Burnhamthorpe Road Extension.
 - Field Studies and incidental observations in 2005, 2009, and 2010 observed Bobolink (Threatened provincially) on the Subject Property. However, 2013 species specific field investigations did not identify Bobolink onsite. Consultation with MNRF was undertaken to identify potential habitat / planning implications as indicated in the MNRF letter date March 26,

⁴ The subject property lies within Ecoregion 7E.

2015 (misdated 2014). The letter indicated that the habitat for Bobolink within the Subject Property is of marginal quality, and as such, the extent to which an ESA (2007) authorization is required will require further examination and discussion.

- Barn Swallow has been documented on the Subject Property during field investigations and site visits in 2005 and 2009. Consultation with MNRF to identify potential habitat / planning implications was conducted. The March 26, 2015 (misdated 2014) letter from MNRF indicated that the removal of Barn Swallow nests and nesting structures (barns) can be addressed by a Notice of Activity as per the requirements of Section 23.5 of Ontario Regulation 242/08.
- Consultation with the MNRF to identify potential habitat / planning implications regarding Little Brown Myotis and Northern Myotis was undertaken. The March 26, 2015 (misdated 2014) letter from MNRF indicated that the candidate habitat for bats (related to the FOD forest communities) within the Subject Property will not be impacted by the proposed development, and as such, the MNRF has no concerns related to *Myotis spp.* and the forest communities.

The existing farm buildings were also examined as potential habitat for these species. Exit surveys of all structures on the Subject Property was undertaken in 2015. The results indicated that two specimens of the *Myotis spp.* were observed exiting the large barn structure. Given the low numbers observed, either the barn has very few maternity roosting bats or the bats were males. MNRF is aware of these results and advised that any alteration or removal of these buildings would be subject to review under the ESA (2007). T

- **PSWs:** There are no PSWs on the Subject Property⁵. Portions of the Subject Property are located on 'adjacent lands' to the North Oakville – Milton West PSW as defined within the PPS (i.e. within 120 m of proposed development lands on the Subject Property). Portions of the Oakville-Milton wetland complex are identified within overlapping EIR subcatchments, outside of the Subject Property boundaries, as indicated on Figure 5.1. An overview of this feature is provided in Section 5.3.2.
- **Significant Woodlands:** The woodland present on the Subject Property (Vegetation Unit 4, Figure 5.2) was assessed as regionally significant during the NOCSS based on size >0.5 ha and proximity (within 50 m of) a medium constraint watercourse. However, this feature was excluded from the proposed Natural Heritage System (NHS) based on the Core Area NHS planning approach adopted by the NOCSS. Additionally, it will not likely qualify as regionally significant if the planned Highway 407 Transitway proceeds. The valley forest (Unit 5, Figure 5.2) may be considered significant under the PPS due to the uncommon status of this community (S3S4 per NHIC S-ranks). No evaluation of the significance of this feature is presented here because it will be retained in full with setbacks as required under the policies of the NOCSS.
- **Area of Natural Scientific Interest (ANSI):** There are no provincially significant ANSI's on the Subject Property. A portion of the Subject Property is located on 'adjacent lands' to one of the woodlands designated as part of the Oakville – Milton Wetlands & Uplands Candidate Life Science ANSI (i.e., within 120 m of proposed development lands on the Subject Property (Figure 5.1). No impacts to the

⁵ Portions of the North Oakville-Milton West PSW complex were previously identified on the subject lands, but this designation was rescinded within the Subject Property to comply with NOCSS (personal communication with Conservation Halton, August 2010). This was confirmed by email correspondence with the MNRF (M. Heaton, July, 2014).

candidate ANSI associated with the proposed development are anticipated because the feature is functionally isolated from the Subject Property by Highway 407.

5.2.3 Conservation Halton Regulation 162/06 and Wetland Policy (2006)

Under Ontario Regulation 162/06 and the associated policy document “Policies, Procedures and Guidelines for the Administration of Ontario Regulation 162/06 and Land Use Planning Policy Document” (Conservation Halton, 2006), CH regulates wetlands and all hazards associated with the watercourses, including the Regional Storm floodplain, stable top of bank and meander belt, as well as, the associated 7.5 m allowances, within the study area. Several wetland areas were identified on the Subject Property through background information review and through the vegetation community mapping undertaken in 2009 and 2010. The location of wetlands on the Subject Property are mapped on Figure 5.2.

5.2.4 Endangered Species Act, 2007

Species documented on the Subject Property that are listed as Threatened or Endangered are subject to species and/or habitat protections under the Provincial ESA (2007) including amendments to the ESA through Ontario Regulations 242/08, 293/11 and 65/12, as described below.

Redside Dace:

Listed in Schedule 2 and classified by Committee on the Status of Species at Risk in Ontario (COSSARO) as an Endangered species. O. Reg. 230/08 (ESA, 2007) and under Ontario Regulation 242/08 Section 29.1.

Within the Subject Property, habitat for Redside Dace in Reach 14W-12 and Reach 14W-16 is subject to Subsection 29.1(1) as these reaches are considered to be Occupied habitat “used by a Redside Dace”.

Bobolink:

Listed in Schedule 3 and classified by COSSARO as a Threatened species. O. Reg. 230/08 (ESA, 2007), Ontario Regulation 242/08.

Bobolink has general habitat protection. General habitat was defined on July 2, 2013. This habitat includes the nest, and the area within 10 m of the nest (Category 1), the area between 10 m and 60 m of the nest (Category 2), and the area of continuous suitable habitat between 60 m and 300 m of the nest or approximated centre of the defended territory. In these areas continuation of agricultural practices, recreational use, and general yard work are generally compatible activities, whilst development activities, and indiscriminate application of pesticides is generally not compatible uses. Exemptions to the ESA (2007) under Section 23.6 (O. Reg. 242/08) would apply to the Subject Property.

Barn Swallow:

Listed in Schedule 3 and classified by COSSARO as a Threatened species. O. Reg. 230/08 (ESA, 2007), Ontario Regulation 242/08.

Barn Swallow has general habitat protection. General habitat for Barn Swallow was defined on July 2, 2013. This general habitat includes the nest (Category 1), habitat within 5 m of a nest (Category 2), and habitat within 200 m of a nest (Category 3). Exemptions to the ESA (2007) under Section 23.5 (O.Reg. 242/08)

would apply to the habitat for Barn Swallow on the Subject Property. Several Barn Swallow nests were confirmed to exist on structures within the Subject Property.

5.3 Existing Conditions

5.3.1 Physiography, Drainage and Soils

The Subject Property lies within the South Slope physiographic region, a strip of land between the former Lake Iroquois Shoreline to the south and the Peel Plain to the north (Chapman and Putnam, 1984). The EIR/FSS study area lies just south of the Trafalgar Moraine, which is located north of Highway 407. The region is characterized by low relief drumlinized topography. Detailed descriptions of the physiography, drainage and soils are presented in Section 4.0.

In general, the surface drainage features include a series of four (4) un-named watercourse that function as tributaries to Fourteen Mile Creek. These watercourses generally flow from northwest to southeast across the Subject Property. Three of the watercourse merge near the centre of the property and continue southeast to the culvert at Dundas Street West. The fourth watercourse transects the northeast corner of the property. The swales are generally poorly defined features that convey surface runoff from lands north of Highway 407.

5.3.2 Environmental Designations

Environmental designations have been assigned to several features located on the Subject Property or off-site portions of EIR subcatchments that partially overlap the Subject Property, as described below:

- **Oakville-Milton Wetlands & Uplands Candidate Life Science Area of Natural and Scientific Interest (ANSI)**, (MNR 2006). The candidate ANSI consists of 11 woodlots units comprising approximately 290 ha in total area. This candidate ANSI has been selected for its representation of kettle and headwater wetlands and drier tableland forests in Site District 7E4. Three (3) of the woodlots are located within the off-site portions of overlapping EIR subcatchments north of Highway 407 (Figure 5.1). A portion of the Subject Property would be considered “adjacent lands” as defined in the PPS (i.e. within 120 m of the ANSI).
- **North Oakville – Milton Wetlands – West Provincially Significant Wetland (PSW) Complex** (MNR 2006a). The PSW complex includes 147 individual wetlands with a combined area of 20.29 ha comprised of 70% marsh and 30% swamp. The wetlands occur on and around the western portion of the Trafalgar Moraine, and are primarily situated in headwater areas of tributaries of Sixteen Mile Creek, Fourteen Mile Creek and Taplow Creek and in adjacent internally draining areas. Portions of this PSW complex had previously been identified on the Subject Property; however, these portions were removed from the complex to conform with NOCSS watercourse classifications (personal communication with Brenda Axon, Conservation Halton 2010). Although publically available wetlands mapping (MNR, 2014) shows a portion of this PSW complex present within EIR subcatchments that extend onto the property, none of the mapped PSW’s are found on the Subject Property in actuality (Figure 5.1). This has been confirmed by the MNR staff via e-mail correspondence (M. Heaton, email correspondence, July 23, 2014). A portion of the Subject Property would be considered “adjacent lands” as defined in the PPS (i.e. within 120 m of the PSW).

-
- **Trafalgar Moraine Candidate Provincially Significant Earth Science ANSI (MNR 2006b).** The Trafalgar Moraine is a broad high ridge of glacial till, approximately 20 km long x 30 m high. It is considered an “*excellent example of the last standstill of the Lake Ontario ice lobe...(supported) glacial Lake Peel, and deflect(ed) the path of East Sixteen Mile Creek, creating the most dramatic landscape of Oakville*”. This candidate ANSI is located immediately north of the Subject Property, north of Highway 407.
 - **Halton Region Significant Woodland/Greenlands B.** The North Woodlot on the Subject Property (Unit 4, Figure 5.2) was determined to be a *Significant Woodland* according to the criteria defined in the Halton Region Official Plan (2006) through analysis completed during the NOCSS. According to policy 130 (1) of the Halton Region Official Plan (2006), *Significant Woodlands* are considered *Greenlands B*, a component of the regional *Greenlands System*. The Regional Official Plan allows local municipalities to adopt a ‘Systems Approach’ to identifying and protecting the Greenlands System within a Secondary Plan area by using criteria other than those identified in the regional Official Plan, provided that certain criteria are met, including that the alternative Natural Heritage System approach to *Greenlands B* are introduced in an appropriate Local Official Plan amendment and are approved by the Region.

Through NOCSS, the north woodlot was identified as significant but was not included in the proposed Natural Heritage System. The NOWSP (Official Plan Amendment No. 289) was adopted by Council on May 25, 2009, which resulted in an amendment to the existing Town’s Official Plan (2006) to include the NOWSP. The Livable Oakville Plan (Oakville Official Plan, 2009), does not apply to those lands under the NOWSP (Section 1.1a). The woodlot, based on the Natural Heritage System approach identified in NOWSP would; therefore, not be considered a constraint to development of the Subject Property.

- **NOCSS Core #1 and Linkage to Core #2.** The NOCSS identified Cores and Linkages within the North Oakville planning area. These features, combined with medium and high constraint streams, form the proposed Natural Heritage System in North Oakville. No Cores or Linkages are located on the Subject Property. Core #1 and Linkage to Core #2 are located off-site in EIR subcatchment FM1109, a small portion of which extends onto the northeast edge of the Subject Property.
- **Stream Corridors.** NOCSS identifies stream corridors according to the characteristics and processes that affect the health of a stream system within a watershed, which is detailed in the NOCSS and summarized here. These characteristics and processes include: Environmental, Geomorphologic, Hydrologic and Hydrogeologic. The interaction of the four components, their sensitivities and the ability of the system to respond to development pressures, provided the basis for developing appropriate management strategies. These different levels of management are identified according to the associated constraints to development or alterations permitted within these systems. The following describes the areas of constraints, the management and where these occur within the Subject Property.

High Constraint Stream Corridor (Red Stream)

High Constraint Reaches are considered to be a high quality resource and in the case with Reach 14W-12 results from the presence of Redside Dace a species classified as Endangered in Ontario

and is subject to protection under the *ESA*. There is one High Constraint reach within the limits of the Subject Property; 14W-12 within subcatchment FM1001.

High Constraint Stream Corridor Requiring Rehabilitation (Red Hatched Stream)

Reach 14W-11 in the northeast portion of the site, located within subcatchment FM1109, is classified as a High Constraint Reach Requiring Rehabilitation.

Medium Constraint Stream Corridor (Blue Stream)

Streams identified as Medium Constraint are considered to have the potential for rehabilitation as they may or may not have a well-defined morphology but do maintain a geomorphic function. There are three Medium Constraint streams within the Subject Property including Reach 14W-14, Reach 14W-14A and Reach 14W-16 that discharge into Reach 14W-12 (High Constraint) within subcatchment FM1001. Reach 14W-16 is considered to be a Medium Constraint Stream Corridor in accordance with NOCSS; however, recent consultations with MNRF (October 20, 2011) indicate that constraints associated with Redside Dace are warranted. The MNRF considers Reach 14W-16 to be Redside Dace Occupied habitat up to and to the north of Highway 407 and is; therefore, subject to protection under the *ESA* (2007) (*ESA Clause (a) Subsection 2(1)* - Ontario Regulation 242/08 S29.1. The remaining Medium Constraint Reach is located in the northeast corner of the Subject Property identified as Reach 14W-11A within subcatchment FM1109 that flows into Reach 14W-11, a High Constraint stream requiring rehabilitation.

Low Constraint Stream Corridor (Green Stream)

Watercourses identified as green are considered to be ephemeral headwater swales that lack definition and function to convey flow and sediments within a system. Reach 14W-13 is the only Low Constraint Reach within the Subject Property. It discharges into Reach 14W-12 (High Constraint).

- **Hydrological Features.** Hydrological features are defined by their association with other Natural Heritage Systems including stream corridors. Type 'A' features are associated with the Natural Heritage System located inside the corridor of a High or Medium Constraint Stream.

A Hydraulic Feature B is not associated with the Natural Heritage System and may be relocated and consolidated with other wetlands, water features or SWM facilities, provided the hydrologic function of the feature is maintained.

There are three type 'A' features and three type 'B' features within the Subject Property as identified in NOCSS. The type 'A' features are associated with Reaches 14W-14, Reach 14W-14A and Reach 14W-16 while the type 'B' features are located within the Reach 14W-16 and west of 3367 Dundas Street West (Figure 5.1). In addition, two other wetland features identified through field studies would meet the criteria for classification as Hydrologic Features 'A' which are located within the stream corridors associated with stream Reach 14W-11A and Reach 14W-16.

5.3.3 Species of Conservation Concern

5.3.3.1 Species At Risk

As mentioned in Section 5.1.3 *Agency Consultation* the MNRF has been consulted through the process to obtain input related to SAR and implications with the ESA (2007). The MNRF will continue to be consulted as it relates to SAR in subsequent phases of the project related to obtaining ESA (2007) approvals with CH and the Town included and/or circulated on the results of these discussions.

Redside Dace

Redside Dace was previously recorded in a lower section of Reach 14W-12 immediately upstream of Dundas Street. The MNRF has indicated that Reaches 14W-12 and 14W-16 are considered Occupied habitat while Reach 14W-11A, Reach 14W-12A, Reach 14W-13, Reach 14W-14 and Reach 14W-14A are considered Contributing habitat. As a result, the MNRF's interest lies principally with the proposed activities that have the potential to have an effect upon groundwater, surface water and physical disturbances within the classified habitat.

The following points summarize the status of Redside Dace and habitat potential on the Subject Property:

Status

- Designated as "Endangered" by the Committee On the Status of Species At Risk in Ontario (COSSARO) under the ESA (2007), and listed as "Endangered" on the Species at Risk in Ontario (SARO) list (Ontario Regulation 230/08, ESA (2007), current June 7, 2017).
- Designated "Endangered" by the Committee on the Status of Endangered Wildlife in Canada (COSEWIC) in 2007, Schedule 3 and "Endangered" under the Federal Species at Risk Act (SARA) (2002) (current May 3, 2017).
- Redside Dace has a provincial S-Rank of S2 (Imperiled) (current July 30, 2014).
- This species receives protection under the ESA (2007); and species specific regulation under Section 23.1 of Ontario Regulation 242/08 (current September 14, 2016).
- Species-specific habitat regulation for this species is now afforded under Section 29.1 of Ontario Regulation 242/08 (current September 14, 2016).

Habitat and Field Observations

- Redside Dace are generally found in clean, clear, cool water, slow moving sections of watercourses less than 10 m in width that meander through meadows with scattered trees and shrubs. They are arboreal insectivores which rely on pools and clear water to see their prey and to jump out of the water to catch it. For this reason they are sensitive to temperature changes, vegetation disturbance, and turbidity (MNRF, 2011).
- Redside Dace were captured in a refuge pool immediately upstream of Dundas Street culvert inlet in September 2001.
- Suitable habitat existing in the lower section of Reach 14W-12 to support this species.
- The project team met with MNRF on January 25, 2011 to discuss ESA (2007) issues and MNRF confirmed on March 26, 2015 (misdated 2014) that the proposed road crossings through regulated habitat would require a permit under the ESA (2007).

Bobolink

Bobolink was recorded on the Subject Property during breeding bird surveys conducted in 2005, and again through incidental observations during the breeding bird season in 2010. Subsequent MNRF endorsed surveys undertaken in 2013 to specifically target Bobolink (and Eastern Meadowlark (*Sturnella magna*)) did not result in the observation of Bobolink.

The following points summarize the status of Bobolink and habitat potential on the Subject Property:

Status

- Designated “Threatened” by COSSARO and listed as “Threatened” on the SARO list (Ontario Regulation 230/08, ESA (2007), and current June 2, 2017).
- This species receives protection under the ESA (2007); and species specific regulation under Section 4.1, 23.2, and 23.6 of Ontario Regulation 242/08 (current September 14, 2016). Although Section 4.1 of the ESA (2007) (which pertains to agricultural operations) is set to expire on December 31, 2025.
- Because this species was listed as Threatened after June 30, 2008, it receives automatic general habitat protection under the ESA (2007).
- General habitat is defined as: Category 1 - The nest, and the area within 10 m of the nest, Category 2 - the area between 10 m and 60 m of the nest, and Category 3 - the area of continuous suitable habitat between 60 m and 300 m of the nest or approximated centre of the defended territory.
- No species-specific habitat regulation under the ESA (2007) is in force at this time.
- Designated “Threatened” by COSEWIC, No Schedule and No Status under SARA (2002) (current June 1, 2017).
- Bobolink has a provincial S-Rank of S4B (Apparently secure in Ontario, Breeding) (current June 12, 2017).

Habitat and Field Observations

- Bobolink originally nested in tall-grass prairie, but has adapted to nest in forage crops (e.g. hayfields) and open grassland habitats following the conversion of the vast majority of prairie ecosystems to agricultural uses.
- Suitable grassland/agricultural habitat is present on the Subject Property within the drainage channel network.
- During breeding bird surveys in 2005, 40 Bobolink were recorded at Station # 7 (BB7, Figure 5.3). In addition, approximately 40 Bobolink were recorded in the riparian meadow between Station #6 and Station #7. Based on habitat suitability and the fairly large number of individuals recorded, breeding was likely.
- In 2010, a total of 16 Bobolink were observed over the course of 2 consecutive days (July 13th and 14th) within the drainage channel network as indicated on Figure 5.4. Breeding evidence in 2010 was based on males singing on territory in suitable nesting habitat.
- Two (2) Bobolink were observed in 2010 north of Station #1 during water quality monitoring surveys.
- Surveys in accordance with the MNRF Bobolink survey methodology under the ESA (2007) (MNRF, 2011) undertaken in the Spring of 2013 did not result in an observation of Bobolink.
- Consultation with the MNRF was undertaken to determine general and/or species-specific habitat protection for this species on the Subject Property per the ESA (2007). MNRF indicated in the March 26, 2015 (misdated 2014) correspondence, that only small areas exist on site that would be

considered suitable habitat for Bobolink based on their habitat assessment. These include ELC communities 2A, 2B, 2F and 2G which are wholly or partially included in the open spaces designation and will not be damaged. As the habitat is limited to riparian areas and is of marginal quality, the extent to which an ESA (2007) Authorization is needed requires further examination and discussion during detail design.

- If required, the MNRF recommends a 1:1 ratio of replacement could be used to potentially address habitat impacts and that opportunities to incorporate additional suitable habitat into the open space areas and/or NHS (i.e. cultural meadow, grasslands, or meadow marsh) would be beneficial. Consultation during detailed design with the MNRF will be resumed to confirm the requirements for habitat replacement based on current and past records for observations of this species.
- Given the marginal nature of the habitat, the retention of riparian habitat where Bobolink were observed, the proposed incorporation of meadow marsh habitat (as indicated by MNRF as currently providing habitat) in the realigned channels and the availability of mechanisms under the ESA (2007) to address Bobolink habitat removal at off-site locations, we would anticipate that this item would not result in delays to the Draft Plan Approval considering these items can only be addressed at the detail design stage.

Barn Swallow

Barn Swallow was observed on the Subject Property and is using the existing barn for breeding, located at the south end of the property adjacent to the large Farm Pond (Reach 14W-14A). Foraging habitat for this species is likely sufficient in the post-development scenario within the natural corridors. MNRF indicated in March 26, 2015 (misdated 2014) that the removal of nest and nesting habitat can be undertaken through the Notice of Activity as per Ontario Regulation 242/08. Under the registry, the MNRF indicates that removal of habitat (i.e. existing barn) would require replacement habitat structures, which could occur in the natural corridors. Confirmation from the MNRF that foraging habitat replacement is not required will be obtained during detailed design.

Status

- Designated “Threatened” by COSSARO and listed as Schedule 3, “Threatened” on the SARO list (Ontario Regulation 230/08, ESA, (2007)) (current June 2, 2017).
- This species receives protection under the ESA (2007); and species specific regulation under Section 23.5 of Ontario Regulation 242/08 (current September 14, 2016). Because this species was listed as Threatened after June 30, 2008, it receives automatic general habitat protection under the ESA (2007).
- This general habitat includes the nest (Category 1), habitat within 5 m of a nest (Category 2), and habitat within 200 m of a nest (Category 3).
- Designated “Threatened” by COSEWIC (2011), No Schedule and No Status under SARA (2002) (current June 1, 2017).
- Barn Swallow has a provincial S-Rank of S4B (Apparently secure in Ontario, Breeding) (current June 12, 2017).

Habitat and Field Observations

- Evidence of breeding was observed on the Subject Property as recently fledged young or downy young were documented.

- This species shows a preference for open habitats for foraging, including grassy fields, pastures, agricultural crops, lake and river shorelines, cleared rights-of-way, farmyards and wetlands.
- This species nests in small, loose colonies, taking advantage of manmade structures to build nests.
- Barn Swallows are aerial insectivores and have been observed flying over the large Farm Pond (Reach 14W-14A).
- Surveys of the existing barn were undertaken in 2013 to confirm usage by Barn Swallow for nesting. Several barn swallow nests were confirmed to exist on structures within the Subject Property.

Eastern Meadowlark

Eastern Meadowlark was not observed on the Subject Property during 2005 breeding bird surveys or incidental observations on the Subject Property. As with Bobolink, dedicated surveys were carried out in the spring of 2013 to confirm the presence/absence of this species and/or habitat on the Subject Property.

Status

- Designated “Threatened” by COSSARO and listed as Schedule 3, “Threatened” on the SARO list (Ontario Regulation 230/08, ESA (2007), current June 2, 2017).
- Because this species was listed as Threatened after June 30, 2008, it receives automatic general habitat protection under the ESA (2007).
- General Habitat for Eastern Meadowlark includes: Category 1 – The nest and the area within 10 m of the nest, Category 2 – The area between 10 m and 100 m of the nest or centre of approximated territory, Category 3 – The area of continuous suitable habitat between 100 m and 300 m from nest or approximated centre of defended territory.
- Designated “Threatened” by COSEWIC, No Schedule and No Status under SARA (2002) (current June 1, 2017).
- Eastern Meadowlark has a provincial S-Rank of S4B (Apparently Secure in Ontario, “Breeding”) (current June 12, 2017).

Habitat and Field Observations

- Preferred breeding habitat for Eastern Meadowlark includes native grasslands, pastures, and savannas, but also hay and alfalfa fields, weedy borders of croplands, roadsides, orchards, golf courses, reclaimed strip mines, airports, shrubby overgrown fields, or other open areas; tall-grass prairie (western edge of range) and desert grassland (southwestern populations).
- This species shows preference for habitats with good grass and litter cover (Lanyon, 1995).
- The Subject Property may provide suitable breeding habitat for Eastern Meadowlark, in areas that contain large wheat fields, pasture, hayfields, a fallow woody agricultural field and wet meadow areas.
- Mowing and harvesting of existing crops both present a risk to the survival of this species.
- Surveys in accordance with the MNR Eastern Meadowlark survey methodology under the ESA (2007) (MNR, 2011) undertaken in the Spring of 2013 did not result in an observation of Eastern Meadowlark.

Eastern Milksnake

Eastern Milksnake (*Lampropeltis triangulum*) was previously recorded in the general vicinity of the Subject Property (MNR personal communication, 2010). The following points summarize the status of Eastern

Milksnake and habitat potential on the Subject Property:

Status

- Removed from the Species at Risk in Ontario (SARO) list on June 15, 2016 (Ontario Regulation 230/08, current June 2, 2017).
- Designated “Special Concern” by COSEWIC, and listed as “Special Concern” on Schedule 1 of SARA (2002) (current, June 1, 2017).
- Eastern Milksnake has a provincial S-Rank of S4 (Apparently Secure in Ontario) (current June 12, 2017).
- Eastern Milksnake has species only protection. Habitat for Eastern Milksnake is not specifically protected by the ESA (2007) or SARA (2002).

Habitat and Field Observations

- Eastern Milksnake is a habitat generalist that occupies a wide variety of habitats including field, swamp, open woodlot and culturally influenced habitats. In Ontario, this snake is more common in heavily forested areas (deciduous, evergreen and mixed) than in areas of low forest cover but is also common in rural pastures and hayfields, as well as, in and around barns, sheds and houses (COSEWIC 2002).
- Suitable habitat for this species is present on the Subject Property (i.e. within agricultural fields, North Woodlot, Valley Forest, swale network, around barns, etc.).
- No Eastern Milksnake have been observed on the Subject Property to date, although no targeted surveys for this species were conducted.
- Suitable habitat for Eastern Milksnake will persist post-development within retained natural environment features including Vegetation Units 3, 4, 5 and retained portions of Vegetation Unit 2 (Figure 5.2). In addition, the realigned watercourse sections will be restored to natural vegetation cover that will provide potential habitat for habitat generalists including Eastern Milksnake.

Monarch Butterfly

Monarch Butterfly (*Danaus plexippus*) was previously recorded in the general vicinity of the Subject Property (MNRF personal communication, 2010) and was observed on the Subject Property during field surveys in 2009 and 2010. The following points summarize the status of Monarch Butterfly and habitat potential on the Subject Property:

Status

- Designated “Special Concern” by COSSARO and listed as Schedule 4 - “Special Concern” on the SARO list (Ontario Regulation 230/08, current June 2, 2017)
- Designated “Endangered” by COSEWIC and listed as Special Concern on Schedule 1 of SARA (2002) (current October 21, 2014).
- Monarch has a provincial S-Rank of S2N,S4B (Imperiled – Non-breeding, Apparently secure in Ontario - Breeding) (current June 12, 2017).
- Monarch has species only protection. Habitat for Monarch is not specifically protected by the ESA (2007) or SARA (2002).
- Based on the draft Significant Wildlife Habitat Ecoregion Criteria Schedules and Addendum to Significant Wildlife Habitat Technical Guide” (OMNR Working Draft, February 2012), no significant

habitat for Monarch is present on-site (i.e. no butterfly migratory route/stopover areas – undisturbed field and forest 10 ha or greater within 5 km of Lake Ontario).

- Monarchs were seen on the subject property during field investigations in 2009, 2010, and 2014.

Habitat and Field Observations

- The Subject Property contains suitable breeding and feeding habitat for this species within cultural meadow/meadow marsh areas. Habitat suitability is defined by the presence of milkweed species (*Asclepias* sp., the only plant on which Monarch caterpillars feed) and the presence of nectar producing plants (which provide a food source for adult Monarchs). The cultural meadow and meadow marsh habitats throughout the Subject Property support occasional stands of Common Milkweed (although no notable stands were observed) and abundant nectar producing plants including asters, goldenrods, thistle, etc.
- It is expected that suitable habitat for this species will persist post-development within retained portions of Vegetation Unit 2 (Figure 5.2). In addition, the realigned watercourse sections will be restored to open meadow/meadow marsh vegetation cover and *Asclepias* sp. and nectar producing plants will be included in re-vegetation seed mixes to enhance habitat potential for Monarch (Section 6.0; Figure 6.4A to 6.4E).

Snapping Turtle

Snapping Turtle (*Chelydra serpentina*) was previously recorded in the general vicinity of the Subject Property (MNRF personal communication, 2010) and its presence confirmed in 2011. The following points summarize the status of Snapping Turtle and habitat potential on the Subject Property:

Status

- Designated “Special Concern” by COSSARO and listed as Schedule 4 “Special Concern” on the SARO list (Ontario Regulation 230/08, current June 2, 2017).
- Designated “Special Concern” by COSEWIC, on Schedule 1 “Special Concern” under SARA (2002) (current June 1, 2017).
- Snapping Turtle has a provincial S-Rank of S3 (Vulnerable in Ontario) (current June 12, 2017).
- Snapping Turtle has only species protection. Habitat for Snapping Turtle is not specifically protected by the ESA (2007) or SARA (2002).

Habitat and Field Observations

- According to COSEWIC Status Report (2008), the preferred habitat for the Snapping Turtle is characterized by slow-moving water with a soft mud bottom and aquatic vegetation. Established populations are most often located in ponds, sloughs, shallow bays or river edges and slow streams.
- Suitable habitat is found within the Farm Pond (Reach 14W-14A) feature. Marginal habitat may be present along wetter portions of the swales, but this habitat is somewhat ephemeral.

Bats

Little Brown Myotis and Northern Myotis were flagged as having the potential to be present on the Subject Property and the MNRF provided accepted protocols for bat surveys within the Subject Property. The site was screened for potential habitat within forest communities and existing structures. All candidate habitat associated with the vegetation (i.e., ELC Forest communities (FOD) – 3A, 3B, 4, 5A and 5B) is located in

Open Spaces designated areas and will not be impacted by the proposed development. As such, MNRF has no concern related to *Myotis spp.* in those habitats.

The existing structures were further investigation in 2015 (June and July) for bat maternity roosting habitat through exits surveys. The results were present to the MNRF which indicated that although bats were using the barn structures, only two specimens of the *Myotis spp.* were recorded. The low numbers of exiting *Myotis spp.* (and other bat species) indicate usage of the buildings is likely restricted to either a very small maternal roost site or is a non-maternal roost, such as, that used by males, who tend to roost individually or in low numbers. Any alteration or removal of the large barn will be subject to review under the ESA (2007).

Status

Little Brown Myotis (formerly Little Brown Bat)

- Designated “Endangered” by COSSARO and listed as Schedule 2 “Endangered” on the SARO list (ESA (2007), Ontario Regulation 230/08, current June 2, 2017).
- Designated as “Endangered” by COSEWIC, on Schedule 1 “Endangered” under SARA (current June 1, 2017).
- Little Brown Myotis has a provincial S-Rank of S4 (Apparently Secure) (current June 12, 2017), although this data is likely not representative due to quick declines in bat populations.
- Because this species was listed as Endangered after June 30, 2008, it receives automatic species and general habitat protection under the ESA (2007).
- General habitat guidelines have not yet been produced by the MNRF.
- Critical habitat has been partially identified by Environment Canada.

Northern Myotis (formerly Northern Long-eared bat)

- Designated “Endangered” by COSSARO and listed as Schedule 2 “Endangered” on the SARO list (ESA (2007), Ontario Regulation 230/08, current June 2, 2017).
- Designated as “Endangered” by COSEWIC, on Schedule 1 “Endangered” under SARA (2002) (current June 1, 2017).
- Northern Myotis has a provincial S-Rank of S3 (Vulnerable) (current June 12, 2017).
- Because this species was listed as Endangered after June 30, 2008, it receives automatic general habitat protection under the ESA (2007).
- General habitat guidelines have not yet been produced by the MNRF.
- Critical habitat has been partially identified by Environment Canada.

Habitat and Field Observations

- Little Brown Myotis are insectivores, feeding at night and are most active in the two or three hours after sunset. They are nocturnal, roosting during the day in trees and buildings. They often select attics, abandoned buildings and barns for summer colonies.
- Northern Myotis are typically associated with boreal forests, roosting under loose bark and in the cavities of trees. They are found throughout forested areas in southern Ontario.
- Exit surveys of the existing barn structures on the Subject Property were undertaken in 2015 with the results indicating that *Myotis spp.* are using the large barn for roosting.

5.3.3.2 Provincially Significant Species

One provincially significant bird species, Black-crowned Night-heron (*Nycticorax nycticorax*, S3B, S3N – Vulnerable – Breeding, Vulnerable – Non Breeding), was observed on the Subject Property on August 20, 2009. One adult and one juvenile were flushed from the shallows of the Farm Pond (Reach 14W-14 and Vegetation Unit 1, Figure 5.2). This observation occurred outside of the breeding bird season and does not suggest breeding activity on the Subject Property.

5.3.3.3 Regionally Rare/Uncommon Species

A total of 11 vegetation species considered rare or uncommon in Halton Region and/or the Greater Toronto Area and/or Site District 7E-4 (per Varga *et al.* 2000) were observed on the Subject Property: Panicked Aster (*Symphyotrichum lanceolatum* ssp. *lanceolatum*), Fringed Sedge (*Carex crinita*), Shagbark Hickory (*Carya ovata* var. *ovata*), Turtlehead (*Chelone glabra*), Torrey's Rush (*Juncus torreyi*), Eastern Red Cedar (*Juniperus virginiana*), Rice Cutgrass (*Leersia oryzoides*), Sandbar Willow (*Salix interior*), Carolina Rose (*Rosa carolina*), Northern Wild-raisin (*Viburnum nudum* var. *cassinoides*) and Winterberry (*Ilex verticillata*). The location of regionally rare/uncommon species is noted in Table 5.7 and Table 5.8. All eleven regionally rare/uncommon species observed have provincial S-ranks of S4 or S5 and are considered common in Ontario.

The Halton Natural Areas Inventory (2006) was consulted to identify the potential rarity of species in the region. Based on the rankings provided therein applied to the plant list for the property: Five (5) species considered uncommon (HU) in Halton Region were observed – Common Hornwort (*Ceratophyllum demersum*), Eastern Red Cedar (*Juniperus virginiana*), Fringed Sedge (*Carex crinita*), Torrey's Rush (*Juncus torreyi*), and Narrow-leaved Spring Beauty (*Claytonia virginica*). One (1) species considered rare (HR) in Halton Region was observed: Swamp White Oak (*Quercus bicolor*). One species with a rank of F (requires further review) was observed: Common Evening-primrose (*Oenothera biennis*). Two species that were not listed in the inventory were observed: Northern Wild-raisin (*Viburnum cassinoides*) and Corn-marigold (*Chrysanthemum segetum*).

Nine (9) bird species (both breeding and non-breeding) considered uncommon in Halton Region (Dwyer 2006) were observed on the Subject Property: Gadwall (*Anas strepera*), Blue-wing Teal (*Anas discors*), Black-crowned Night-heron, Northern Harrier (*Nycticorax nycticorax*), Wilson's Snipe (*Gallinago delicata*), Willow Flycatcher (*Empidonax traillii*), Horned Lark (*Eremophila alpestris*), Northern Rough-winged Swallow (*Stelgidopteryx serripennis*) and Eastern Towhee (*Pipilo erythrophthalmus*). All of these have provincial S-ranks of S4 or S5, except Black-crowned Night-Heron which has an S-rank of S3B (discussed in Section 5.3.3.2). Observation locations are noted in Table 5.8 in Section 5.3.6.2.

5.3.4 Aquatic Resources

Aquatic community and habitat investigations were undertaken through the spring, summer and fall of 2009, as well as, the winter of 2010 by MMM Group aquatic ecologists to supplement the existing information within NOCSS (2006) and field investigations undertaken in 2002. Subsequent field investigations were undertaken on July 1 and August 31, 2011 in support of Technical Memo NH#1 to address CH comments and then again in 2017 to review the flow regime during the spring freshet to coincide with the timing identified in the *Evaluation, Classification and Management of Headwater Drainage Features Guidelines Approved July 2013*

(CVC/TRCA, Finalized January 2014). Sampling and habitat documentation was undertaken in each reach to assist with the characterization of the habitat present across the Subject Property.

With reference to guidance from the NOCSS (pg. 7-16), minor refinements of stream reaches are permitted during studies for the preparation of the EIR/FSS. As such, the refinement of the upstream section of Reach 14W-12 was considered based on the field studies undertaken in support of the EIR/FSS for the Subject Property between 2009 and 2011. During these studies, habitat conditions in Reach 14W-12 were evaluated based on the factors that led to the original reach classification. Observations indicate that the form and function of existing habitat in the upper section of Reach 14W-12, connecting the confluence of Reach 14W-13m Reach 14W-14 and Reach 14W-14A with the confluence of Reach 14W-16 and Reach 14W-12, is functionally distinct from existing habitat within the main section of Reach 14W-12 downstream of the confluence with Reach 14W-16. Therefore, for the purposes of this Report, Reach 14W-12 has been descriptively divided into two reaches; such that the functionally distinct section that originates at the Farm Pond (Reach 14W-14A) and flows westerly to its confluence with Reach 14W-16 is described hereafter as the Reach 14W-12A, while the remaining stream section that continues downstream to Dundas Street retains the original designation as Reach 14W-12. Reach 14W-12A is also considered to be a hydraulically distinct feature from Reach 14W-12.

Aquatic resource investigations within the Subject Property included fish community sampling, benthic macroinvertebrate community sampling, aquatic habitat mapping, and water quality monitoring (Dissolved Oxygen (DO), Temperature, Conductivity, pH, Total Dissolved Solids (TDS) and Water Clarity). Fish community sampling was not undertaken in Reach 14W-12 as part of this study to avoid disturbing Redside Dace and their habitat.

Fish Community Approach

Fish community sampling in 2009 was primarily undertaken in May. Several fish sampling sites were located co-incident with Ontario Stream Assessment Protocol (OSAP) sites. These sites relied on the location to have suitable conditions (i.e. sufficient water) to carry out OSAP, as well as, providing the appropriate fish community sampling conditions. The timing of fish community sampling was selected based on the previous field investigations carried out in 2002, which identified a number of tributaries as exhibiting intermittent/ephemeral flow regimes. Sampling in stream reaches and spot sampling along the perimeter of the two ponds was conducted using a HT-2000 Halltech Battery Backpack Electroshocker. A single pass method was used in the tributaries where water was observed and in the wadeable nearshore areas of the two ponds. At that time, fish community sampling within potential fish habitat that did not meet the OSAP conditions was undertaken where possible. These areas principally consisted of Highway 407 culvert outlets where refuge pools had been scoured. These areas were spot sampled using the backpack electroshocker where sufficient water was present in July 2009.

Additional sampling surveys were undertaken in 2011 to satisfy September 6, 2011 CH comments related to sampling effort in Reach 14W-14A conducted in 2002 using minnow traps and in 2009 using an electrofisher. Sampling efforts in 2011, consisted of both minnow traps and pot traps, set for a period of approximately 24 hours. Details of the 2011 fish community sampling is described in Technical Memorandum – NH #1 included in Appendix 5.9 and summarized in Section 5.3.4.1. All fish were processed (i.e. identification, measurement & tally) on-site and returned promptly to the approximate capture site. Fish community sampling locations from all years are shown in Figure 5.4.

Benthic Macroinvertebrate Community Approach

Benthic macroinvertebrate sampling was conducted at each of the OSAP sites using the compatible Ontario Benthos Biomonitoring Network (OBBN) protocol. Benthos collection was completed using the traveling kick and sweep method covering a 10 m distance over three minutes in both pool and riffle habitats. Benthic macroinvertebrate samples were preserved in the field and taken back to the lab for processing according to OBBN. Samples were rinsed and randomly sorted into sub-samples using the bucket method, and the sub-samples were picked until at least 100 organisms were collected. The picked organisms were tallied and identified according to the OBBN coarse 27 group mix of Phyla, Orders, Classes and Families.

Water Quality Approach

The OMB *Mediation Item: Stormwater Management – Temperature and Dissolved Oxygen Targets* (July 12, 2007) indicates that specific target levels are recommended for water temperature and dissolved oxygen for the purposes of fisheries protection. A conservative target maximum daily water temperature of 20°C is achieved for fisheries protection and applied in the stormwater management for lands draining to Fourteen Mile Creek. Based on the Provincial Water Quality Objective (MOE, 1994) for coldwater fisheries associated with the target water temperature, a conservative DO target of 6 mg/l is to be applied. The OMB decision recommended that a temperature and DO monitoring program be established prior to development to establish a baseline against which target levels can be assessed and modified. This would provide a baseline condition in the intermittent watercourses that may not meet the previously mentioned targets. CH was contacted to determine the best location and procedure to monitor the water quality (specifically DO and temperature) as per the requirements of the mediation (Kim Barrett, Conservation Halton; Pers. Comm. March 30, 2009).

Water quality parameters were recorded at each station every two weeks (bi-monthly) beginning May 12, 2009 and ending October 30, 2009, including water temperature, TDS, conductivity, pH and DO. Water temperature, TDS, conductivity and pH were measured using a Hanna Instruments HI98129 multimeter and DO was measured using an Extech Instruments Waterproof Exstik II Dissolved Oxygen Meter. Temperature monitoring was undertaken using temperature sensors that were installed in the tributaries where sufficient water was believed to persist throughout the monitoring period to keep the sensor submerged. For consistency, water quality sampling was conducted at the water temperature monitoring stations on a bi-monthly basis between May 12, 2009 and October 30, 2009. Water quality parameters were recorded around the same time of day whenever possible, following data retrieval/download of the temperature sensor. Additional water quality data was recorded at benthic and fish community sampling locations in 2009.

A site specific water quality monitoring program at the request of CH (September 6, 2011) was carried out in the Farm Pond (Reach 14W-14A) to collect data in 2011 to provide a detailed characterization of the quality and type of fish habitat available in this feature. Water quality data collected in this feature included: stratified water temperature data, stratified DO data and water clarity, as well as, TDS, conductivity and pH of the surface water. Sampling occurred at three locations throughout the pond. The details of the sampling method and results of the water quality monitoring are described in the Technical Memorandum – NH#1 included in Appendix 5.9.

Aquatic Habitat Approach

Field investigations undertaken in 2009 and 2010 were developed using the EIR/FSS Terms of Reference (Town of Oakville, August 2, 2007). Beyond the limits of the Subject Property, existing conditions were documented at the subcatchment level of detail to characterize stream reaches. These observations were generally made from road crossings beyond the Subject Property including Highway 407 (ETR), Tremaine Road, GE Company laneway, and downstream of Dundas Street (main channel crossing). This information is used to compare the current conditions with previous findings reported in the NOCSS Characterization Report and to provide context for on-site aquatic habitat documented at a greater level of detail. Within the Subject Property, field staff detailed the existing conditions and drainage characteristics including aquatic habitat features. Specific focus was placed on habitat potential and effects related to Redside Dace, which is considered to inhabit Reach 14W-12.

On-site habitat characterization was detailed using Ontario Stream Assessment Protocol (OSAP) mapping, detailed photographs and notes during multiple site visits during the spring, summer and fall of 2009. The OSAP protocol requires that the sampling site should represent at least one riffle-pool sequence, be at least 40 m long, and beginning and ending at a crossover point. In channelized or modified streams, such as those occurring within the Subject Property, a site can be selected based on a 40 m length of stream with similar bank heights and relative uniformity of depth profile across the channel. Due to the limited amount of flow within the watercourses, only three potential locations met the above criteria during spring field investigations.

In 2011 aquatic habitat conditions were further documented in Reach 14W-14A to supplement documentation of this feature from previous years to provide more details of the available habitat to satisfy CH September 6, 2012 comments on earlier investigations. Habitat in Reach 14W-14A was completed using an underwater camera to view conditions in the open water areas at depths exceeding 2 m. Aquatic vegetation (submergent, emergent and floating) was documented from a canoe to characterize the available habitat visible from the surface (Appendix 5.7 and 5.9).

5.3.4.1 Fish Community

The majority of the fish community for Fourteen Mile Creek consists of generalist species, which are tolerant of warmwater temperatures with moderate amounts of organic enrichment. The exception to this is Redside Dace recorded in the lower section of Reach 14W-12 as this species requires cool, clear flowing water with riffle-pool sequences and overhanging bank vegetation (NOCSS Characterization Report, 2006).

Fish community data presented below summarizes previous field investigations undertaken in 2002, information available in NOCSS, as well as, supplemental field investigations undertaken in 2009 in support of this EIR. Fish community sampling undertaken in 2002 was undertaken during the low flow period (July and September) and used a combination of methods including electrofishing, minnow traps and incidental observations within the main channel and the associated ponds (MMM, 2003). Fish community sampling in 2002 was limited to Reach 14W-12, Reach 14W-16 and Reach 14W-14A due to the lack of water in the remaining reaches. The location of each sampling site is identified in Figure 5.4.

Recognizing the intermittent/ephemeral nature of the other reaches on-site, the 2009 field investigations were undertaken in both the spring (May) and summer (July) to document seasonal fish habitat use and the connectivity of the reaches during this high flow period.

The results of the fish community sampling are summarized in Table 5.2, below.

Table 5.2 – Fish Community Data for QuadReal – Lazy Pat Lands, Oakville (MESP 2003, MMM, 2003 & MMM, 2009)

Fish Species		Reach Identification						
Fish Species	Scientific Name	Reach 14W-11A Site 1	Reach 14W-11A Site 2	Reach 14W-12 Site 1*	Reach 14W-12 Site 2*	Reach 14W-14	Reach 14W-14A (Farm Pond)	Pond 1 (Dug Pond)
Blacknose Dace	<i>Rhinichthys atratulus</i>			66	17			3
Bluntnose Minnow	<i>Pimephales notatus</i>	2	8		17			
Brook Stickleback	<i>Culaea inconstans</i>		2	24	4	8	2	
Brown Bullhead	<i>Ictalurus nebulosus</i>			2	5		1	
Creek Chub	<i>Semotilus atromaculatus</i>	4	15	82	67		37*	
Fathead Minnow	<i>Pimephales promelas</i>	9	9	14	12	2		
Largemouth Bass (YoY)	<i>Micropterus salmoides</i>						3*	2
Redside Dace	<i>Clinostomus elongatus</i>			2				
White Sucker	<i>Catostomus commersonii</i>			6	2		7*	

*2002 Fish Community Sampling Results

Reach 14W-11

Fish community within this tributary consists of three species including Brook Stickleback (*Culaea inconstans*), Fathead Minnow (*Culaea inconstans*) and Creek Chub (*Semotilus atromaculatus*) (Table 5.2). Based on the results of sampling efforts, this tributary provides spawning opportunities for both Brook Stickleback and Fathead Minnow, as young of the year were observed. Due to the minor flow observed later in the season and high flows observed on October 20, 2011 it is anticipated that these specimens originate from downstream fish habitat and use this reach seasonally.

Reach 14W-12

The fish community sampling was not undertaken in 2009 due to the classification of this reach as providing Redside Dace habitat (MNR, 2009). Historic fish community sampling in September 2002 resulted in the capture of eight warmwater and coolwater species including Redside Dace. Fish community sampling sites in this reach included a refuge pool located immediately upstream of the Dundas Street culvert inlet, as well as, a second refuge pool located approximately 200 m upstream of Dundas Street at an existing farm road crossing of the watercourse. Fish were only sampled in these areas as the remainder of the watercourse had insufficient flow/water. Redside Dace was only captured at the downstream refuge pool immediately

upstream of Dundas Street during sampling. During 2009 field investigations fish continued to be observed schooling in the downstream refuge section.

The continued presence of fish indicates that this reach continues to directly support what is presumed to be a self-sustaining fish population as the Dundas Street culvert likely functions as a seasonal barrier to fish movement due to the perched outlet (approximately 0.15 m), a second vertical drop within the culvert (approximately 0.15 m) and the base of the culvert that creates shallow sheet flow over smooth concrete with little cover/velocity breaks. During periods of higher flows in this system that may occur during spring freshet conditions or following storm events, fish movement upstream through the Dundas Street culvert may be possible. However, flow velocities during high flows, such as those observed on October 20, 2011 when more than 59.5 mm of rain fell in the Oakville area, may prohibit most fish from navigating through the culvert.

Reach 14W-12A

Fish community sampling was not undertaken in Reach of 14W-12A as there was insufficient flowing water during spring field investigations. Furthermore, fish were not observed in pooled habitat during subsequent water quality monitoring investigations. This section may provide seasonal fish habitat during periods of flow for fish located within the pond (Reach 14W-14A) and perhaps fish originating from Reach 14W-12; however, due to its channel form and the habitat present it would likely only support generalist species during the period when flow is present.

Reach 14W-13

Fish community sampling was conducted within this reach in July downstream of the Highway 407 culvert outlet. Due to the limited amount of water present, this section was selectively sampled using the backpack electroshocker; however, did not result in the capture of any fish. This and historic field observations of a dry channel confirms the NOCSS classification of this system as not functioning as (direct) aquatic habitat.

Reach 14W-14

Fish community sampling was also undertaken in this reach during July in response to the observation of pooled water in the vicinity of the Highway 407 culvert outlet. Similar to sampling in Reach 14W-13 this section was selectively sampled using the backpack electroshocker due to the limited amount of water present. Sampling resulted in the capture of Brook Stickleback and Fathead Minnow. Both are considered warmwater species that are tolerant of a variety of habitat conditions with the substrate and emergent vegetation in pool habitat providing suitable habitat. The absence of other species with more specialized habitat requirements (i.e. coarse substrate, thermal regimes, etc.) indicates that this area provides marginal direct fish habitat. These species may have originated from upstream/downstream habitat during the spring freshet and been unable to migrate downstream due to receding water levels later in the season as field investigations through the year indicate that the channel connecting this refuge pool to permanent habitat (Reaches 14W-14A and 14W-12) appeared to remain dry for the summer months.

Reach 14W-14A (Farm Pond)

Fish community sampling was undertaken in 2002, 2009 and 2011 by MMM Group Aquatic Ecologists, as well as, by the authors of the NOCSS (2006) documents in support of their study. The pond supports a warmwater and coolwater baitfish and warmwater sportfish (Largemouth Bass) community. The presence